

Practice: 362 - Diversion

Scenario: #1 - Diversion

Scenario Description:

An earthen channel constructed across long slopes with supporting ridge on lower side, to divert runoff away from farmsteads, gullies, critical erosion areas, construction areas or other sensitive areas. Outlet may be waterway, underground outlet. or other suitable outlet. Typical diversion is, 2300 feet long and requires 1 CY excavation per LF. Channel may be level or gradient and ridge may be vegetated or farmed. The quantity of excavation and fill is balanced.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Diversion is 2300 feet long installed using a dozer and/or scraper. Storm water runoff is diverted away from the area to be protected. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Underground Outlet (620), Mulching (484), and Subsurface Drainage (606).

Scenario Feature Measure: Diversion Excavated Volume

Scenario Unit: Cubic Yard

Scenario Typical Size: 2,300

Scenario Cost: \$7,633.89

Scenario Cost/Unit: \$3.32

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Scraper, Self Propelled, 14 CY	2306	Self propelled earthmoving scraper with 14 CY capacity. Does not include labor.	Hour	\$258.16	19	\$4,905.04
Motor Grader, 150 HP	1781	Motor Grader or Maintainer, 150 hp. Typical of equipment with HP in range of 130-170. Equipment cost, does not include labor.	Hour	\$99.98	4	\$399.92
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.87	710	\$617.70
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$36.74	2	\$73.48
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$24.95	23	\$573.85
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.99	4	\$75.96
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$493.97	2	\$987.94