

Practice: 558 - Roof Runoff Structure**Scenario: #1 - Roof Gutter****Scenario Description:**

A roof runoff structure, consisting of gutter(s), downspout(s), and appropriate outlet facilities on a 200 feet long building by 10 feet tall side walls. Used to keep roof clean water runoff uncontaminated and provide a stable outlet to ground surface. Facilitates waste management and protects environment by minimizing clean water additions to waste systems and addresses water quality concerns.

Associated practices include Waste Storage Facility (313), Composting Facility (317), Heavy Use Area Protection (561), Watering Facility (614), Underground Outlet (620), Diversion (362), Roofs and Covers (367), and any relevant irrigation practices.

Before Situation:

Applicable where: (1) a roof runoff management facility is included in an overall plan for an overall plan for a waste management system; (2) roof runoff needs to be diverted away from structures or contaminated areas; (3) there is a need to collect, control, and transport runoff from roofs to a stable outlet.

After Situation:

A gutter, downspout, and outlet system servicing the portion of the building roof that would otherwise drain into a waste management system or create erosion. Roof line of 200 feet serviced with gutter, downspouts, and appurtenances.

Scenario Feature Measure: Linear Length of Roof to be Guttered

Scenario Unit: Linear Feet

Scenario Typical Size: 200

Scenario Cost: \$878.62

Scenario Cost/Unit: \$4.39

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.71	12	\$224.52
Materials						
Downspout, Aluminum, Small	1700	Aluminum downspout (3" to 5") in width with hangers. Materials only.	Foot	\$3.07	30	\$92.10
Gutter, Aluminum, Small	1689	Aluminum gutter (4" to 6") in width with hangers. Materials only.	Foot	\$2.81	200	\$562.00