

Practice: 620 - Underground Outlet

Scenario: #4 - 4-6 inch PVC or Dual-Wall HDPE Pipe with Riser

Scenario Description:

Install 400 feet of 4" & 6" approved plastic pipe (PVC or Dual Wall HDPE) to convey stormwater from one location to a suitable and stable outlet in high pressure flow conditions, situations needing greater capacity or where rodent damage may be a concern. Trench excavation is 48" deep and 12" wide for 4" pipe, and 18-24" wide for 6" pipe. Costs include 6" PVC pipe, 6" Perforated PVC Riser Inlet, labor to install pipe, trench excavation, trench backfill, and rodent guard. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 400

Scenario Cost: \$2,469.87

Scenario Cost/Unit: \$6.17

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.17	6	\$31.02
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.24	400	\$496.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.71	8	\$149.68
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.49	1	\$37.49
Materials						
Pipe, PVC, 4", SDR 35	992	Materials: - 4" - PVC - SDR 35 - ASTM D3034	Foot	\$1.67	200	\$334.00
Pipe, PVC, 6", SDR 35	993	Materials: - 6" - PVC - SDR 35 - ASTM D3034	Foot	\$3.75	200	\$750.00
Inlet, riser, 6"	1261	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 6" diameter. Materials only.	Each	\$69.66	2	\$139.32
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$266.18	2	\$532.36

Practice: 620 - Underground Outlet

Scenario: #6 - <= 6 inch Single-Wall PE Pipe with Riser

Scenario Description:

Install 400 feet of 4" & 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet in non-pressure flow conditions. Trench excavation is 48" deep and 12" wide. Costs include 4" and 6" HDPE corrugated single wall plastic tubing, 6" Perforated PVC Riser Inlet, labor to install pipe, trench excavation, trench backfill, and rodent guard. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 400

Scenario Cost: \$1,699.87

Scenario Cost/Unit: \$4.25

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.24	400	\$496.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.17	6	\$31.02
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.71	8	\$149.68
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.49	1	\$37.49
Materials						
Inlet, riser, 6"	1261	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 6" diameter. Materials only.	Each	\$69.66	2	\$139.32
Pipe, HDPE, 4", PCPT, Single Wall	1270	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 4" diameter - ASTM F405. Material cost only.	Foot	\$0.45	200	\$90.00
Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	\$1.12	200	\$224.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$266.18	2	\$532.36

Practice: 620 - Underground Outlet

Scenario: #7 - 8-10 inch PVC or Dual-Wall HDPE Pipe with Riser

Scenario Description:

Install 400 feet of 8" and 10" approved plastic pipe (PVC or Dual Wall HDPE) to convey stormwater from one location to a suitable and stable outlet in non-pressure flow conditions and when multiple practices drain into it. Trench Excavation is 48" deep and 24" wide. Typical costs include 8" and 10" PVC pipe, 10" riser inlet, labor to install pipe, trench excavation, trench backfill, and rodent guard. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 400

Scenario Cost: \$5,565.95

Scenario Cost/Unit: \$13.91

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.82	400	\$1,128.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.17	10	\$51.70
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.71	8	\$149.68
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.49	1	\$37.49
Materials						
Inlet, riser, 8"	1262	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 8" diameter. Materials only.	Each	\$108.36	2	\$216.72
Pipe, PVC, 10", SDR 35	1251	Pipe, PVC, SDR 35, 10" Diameter - ASTM D3034. Material cost only.	Foot	\$10.53	200	\$2,106.00
Pipe, PVC, 8", SDR 35	994	Materials: - 8" - PVC - SDR 35 - ASTM D3034	Foot	\$6.72	200	\$1,344.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$266.18	2	\$532.36

Practice: 620 - Underground Outlet

Scenario: #8 - 6-10 inch PVC or Dual-Wall HDPE Pipe with Canopy or Riser (single inlet)

Scenario Description:

Install 80 feet of 8" approved plastic pipe (PVC or Dual Wall HDPE) to convey stormwater from one location to a suitable and stable outlet in pressure flow conditions and when draining single practices. Trench Excavation is 48" deep and 24" wide. Typical costs include 8" PVC pipe, 8" canopy or hooded inlet, labor to install pipe, trench excavation, trench backfill, and rodent guard. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 80

Scenario Cost: \$1,524.19

Scenario Cost/Unit: \$19.05

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.17	5	\$25.85
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.82	80	\$225.60
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.49	1	\$37.49
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.71	4	\$74.84
Materials						
Hooded Inlet, 8"	1421	Hooded Inlet for 8" dia. pipe. Includes materials and labor for fabrication and installation.	Each	\$90.45	1	\$90.45
Pipe, PVC, 8", SDR 35	994	Materials: - 8" - PVC - SDR 35 - ASTM D3034	Foot	\$6.72	80	\$537.60
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$266.18	2	\$532.36

Practice: 620 - Underground Outlet

Scenario: #9 - 12-18 inch PVC or Dual-Wall HDPE Pipe with Riser

Scenario Description:

Install 400 feet of 12" and 18" approved plastic pipe (PVC or Dual Wall HDPE) to convey stormwater from one location to a suitable and stable outlet in non-pressure flow conditions and when multiple practices drain into it. Trench Excavation is 58" deep and 28" wide. Costs include 12" and 18" HDPE pipe, 10" Perforated PVC Riser Inlet, labor to install pipe, trench excavation, trench backfill, and rodent guard. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 400

Scenario Cost: \$5,863.77

Scenario Cost/Unit: \$14.66

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.82	400	\$1,128.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.17	14	\$72.38
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.71	8	\$149.68
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.49	1	\$37.49
Materials						
Inlet, riser, 10"	1263	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 10" diameter. Materials only.	Each	\$146.93	2	\$293.86
Pipe, HDPE, CPT, Double Wall, Soil Tight, 12"	1244	Pipe, Corrugated HDPE Double Wall, 12" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$7.18	200	\$1,436.00
Pipe, HDPE, CPT, Double Wall, Soil Tight, 18"	1245	Pipe, Corrugated HDPE Double Wall, 18" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$11.07	200	\$2,214.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$266.18	2	\$532.36

Practice: 620 - Underground Outlet

Scenario: #10 - 12-18 inch PVC or Dual-Wall HDPE Pipe with Canopy or Riser (single inlet)

Scenario Description:

Install 80 feet of 12" approved plastic pipe (PVC or Dual Wall HDPE) to convey stormwater from one location to a suitable and stable outlet in pressure flow conditions and when draining single practices. Trench Excavation is 48" deep and 24" wide. Costs include 12" PVC pipe, 12" canopy or hooded inlet, labor to install pipe, trench excavation, trench backfill, and rodent guard. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 80

Scenario Cost: \$2,842.76

Scenario Cost/Unit: \$35.53

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.82	80	\$225.60
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.17	7	\$36.19
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.71	4	\$74.84
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.49	1	\$37.49
Materials						
Pipe, PVC, 12", SDR 35	1252	Pipe, PVC, SDR 35, 12" Diameter - ASTM D3034. Material cost only.	Foot	\$22.49	80	\$1,799.20
Hooded Inlet, 12"	1423	Hooded Inlet for 12" dia. pipe. Includes materials and labor for fabrication and installation.	Each	\$137.08	1	\$137.08
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$266.18	2	\$532.36

Practice: 620 - Underground Outlet

Scenario: #11 - > 18 inch PVC or Dual-Wall HDPE Pipe with Riser

Scenario Description:

Install 60 feet of greater than 18" approved plastic (PVC or Dual Wall HDPE) or CMP pipe to convey stormwater from one location to a suitable and stable outlet in non-pressure flow conditions and when multiple practices drain into it. Trench Excavation is 58" deep and 28" wide. Costs include 24" HDPE dual wall pipe, 36" dual wall HDPE pipe riser inlet, labor to install pipe, trench excavation, trench backfill, and rodent guard. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

Before Situation:

Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

After Situation:

Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

Scenario Feature Measure: Length of Conduit

Scenario Unit: Feet

Scenario Typical Size: 60

Scenario Cost: \$2,240.38

Scenario Cost/Unit: \$37.34

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.88	35	\$65.80
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.54	35	\$88.90
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.49	4	\$149.96
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.71	4	\$74.84
Materials						
Pipe, HDPE, CPT, Double Wall, Soil Tight, 24"	1246	Pipe, Corrugated HDPE Double Wall, 24" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$18.61	60	\$1,116.60
Pipe, HDPE, CPT, Double Wall, Soil Tight, 36"	1248	Pipe, Corrugated HDPE Double Wall, 36" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$35.32	6	\$211.92
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$266.18	2	\$532.36