

<i>Component</i>	<i>Unit</i>	<i>Cost Share Type*</i>	<i>Cost</i>	<i>Notes</i>
Bentonite	ton	AC	\$240.00	Includes the amendment material and mixing of the soil with the amendment
Brush Management - Chemical - Aerial broadcast	ac	AC	\$23.00	Includes chemical and application
Brush Management - Chemical - Ground broadcast	ac	AC	\$20.00	Includes chemical and application
Brush Management - Chemical - Ground spot treatment	ac	AC	\$19.00	Includes chemical and application - Spot treatment is defined as treating less than 40% of the field
Brush Management - Mechanical - Cut stump treatment - Low Infestation Level	ac	AC	\$40.00	Includes sawing, clipping, or shearing plus herbicide application. Does not include mowing. Infestation levels defined according to Brush Management (314) Practice Specification.
Brush Management - Mechanical - Cut stump treatment - Medium Infestation Level	ac	AC	\$70.00	Includes sawing, clipping, or shearing plus herbicide application. Does not include mowing. Infestation levels defined according to Brush Management (314) Practice Specification.
Brush Management - Mechanical - Cut stump treatment - High Infestation Level	ac	AC	\$110.00	Includes sawing, clipping, or shearing plus herbicide application. Does not include mowing. Infestation levels defined according to Brush Management (314) Practice Specification.
Canopy or Drop Inlet Spillway - PVC, PE, and CMP - 6 and 8 in dia	lf	AC	\$14.00	Includes trash rack, inlet, barrel, anti-seep collars or filter diaphragm, pipe support, and manually tamped backfill of the barrel
Canopy or Drop Inlet Spillway - PVC, PE, and CMP - 10 and 12 in dia	lf	AC	\$24.00	Includes trash rack, inlet, barrel, anti-seep collars or filter diaphragm, pipe support, and manually tamped backfill of the barrel
Canopy or Drop Inlet Spillway - PVC, PE, and CMP - 14 and 15 in dia	lf	AC	\$35.00	Includes trash rack, inlet, barrel, anti-seep collars or filter diaphragm, pipe support, and manually tamped backfill of the barrel
Canopy or Drop Inlet Spillway - PVC, PE, and CMP - 16 and 18 in dia	lf	AC	\$42.00	Includes trash rack, inlet, barrel, anti-seep collars or filter diaphragm, pipe support, and manually tamped backfill of the barrel
Canopy or Drop Inlet Spillway - PVC, PE, and CMP - 21 and 24 in dia	lf	AC	\$50.00	Includes trash rack, inlet, barrel, anti-seep collars or filter diaphragm, pipe support, and manually tamped backfill of the barrel
Concrete - Floor or slab and curb	cuyd	AC	\$175.00	Includes site preparation, nominal foundation excavation, fill sand, concrete with additives, reinforcing steel, wire fabric, and forming
Concrete - Formed structure and wall	cuyd	AC	\$300.00	Includes site preparation, nominal foundation excavation, fill sand, concrete with additives, reinforcing steel, wire fabric, and forming
Concrete Block Chute - 8 in x 8 in x 16 in blocks	block	AC	\$3.50	Includes site preparation, bedding, geotextile, concrete blocks, and installation
Concrete Block Drop Structure - 2 ft x 2 ft x 4 ft or smaller pre-cast blocks	block	AC	\$40.00	Includes site preparation, bedding, geotextile, concrete blocks, and installation
Concrete Block Drop Structure - 2.5 ft x 2.5 ft x 5 ft pre-cast blocks	block	AC	\$80.00	Includes site preparation, bedding, geotextile, concrete blocks, and installation
Coppicing	ac	AC	\$400.00	Includes tree cutting, stump treatment of undesirable trees, stacking trees, laying over trees
Diversion, Earthfill - Gradient, level, and underground outlet	cuyd	AC	\$1.20	Includes the site preparation, earthfill, and blocks
Drainfill (sand - ASTM C33 or similar)	ton	AC	\$12.00	Includes material and installation, used as drainfill or bedding for riprap
Drop Inlet Spillway - PVC, PE, and CMP - 30 in dia	lf	AC	\$105.00	Includes trash rack, riser and base, barrel, anti-seep collars or drain diaphragm, pipe support, and manually tamped backfill of both the riser and barrel (use barrel dia. and lf)
Drop Inlet Spillway - PVC, PE, and CMP - 36 in dia	lf	AC	\$140.00	Includes trash rack, riser and base, barrel, anti-seep collars or drain diaphragm, pipe support, and manually tamped backfill of both the riser and barrel (use barrel dia. and lf)

*Cost Share Type: AC - Average cost; FR - Flat Rate

<i>Component</i>	<i>Unit</i>	<i>Cost Share Type*</i>	<i>Cost</i>	<i>Notes</i>
Drop Inlet Spillway - PVC, PE, and CMP - 42 in dia	lf	AC	\$170.00	Includes trash rack, riser and base, barrel, anti-seep collars or drain diaphragm, pipe support, and manually tamped backfill of both the riser and barrel (use barrel dia. and lf)
Early Successional Vegetative Treatment	ac	AC	\$12.00	Includes all methods of tillage or mowing
Earthfill, Compacted	cuyd	AC	\$1.40	Includes site preparation, water as needed, mixing, and compaction
Earthfill, Compacted Waste Pond Liner	cuyd	AC	\$2.60	Includes site preparation, water, mixing, compaction, and cover
Equipment rate	hr	AC	\$120.00	Includes equipment and operator working on site (mobilization is included) for WRP maintenance or microtopography creation
Excavation	cuyd	AC	\$1.70	Includes site preparation, excavation, and spoil disposal
Fence - Permanent power	lf	AC	\$0.73	Includes 3-, 4-wire fence
Fence - Wire	lf	AC	\$1.60	Includes 4-, 5-wire and woven wire fence
Firebreak	ac	AC	\$26.00	Includes clean cultivation
Flexible Irrigation Hose - 4-inch dia	lf	AC	\$4.50	Includes lay flat irrigation hose and reel for manure transfer to field
Flexible Irrigation Hose - 6-inch dia	lf	AC	\$8.00	Includes lay flat irrigation hose and reel for manure transfer to field
Flexible Irrigation Hose - 8-inch dia	lf	AC	\$15.00	Includes lay flat irrigation hose and reel for manure transfer to field
Forest Site Preparation - Medium	ac	AC	\$400.00	Includes all site preparation methods where the area needing reforestation is equal to or less than 40 percent of the inventoried acreage
Forest Site Preparation - Heavy	ac	AC	\$800.00	Includes all site preparation methods where the area needing reforestation is greater than 40 percent of the inventoried acreage
Forest Stand Thinning	ac	AC	\$77.00	Includes cutting, girdling, frilling, and or herbicide treatment. Does not include pruning
Gabion Structure - Riprap	cuyd	AC	\$200.00	Includes site preparation, bedding, geotextile, riprap, wire baskets, and installation
Geotextile Fabric	sqyd	AC	\$3.65	Includes material and application
Glass-Fused-to-Steel Storage Facility	cuft	AC	\$3.00	Includes site preparation, foundation, reinforced concrete floor and footing, and glass-fused-to-steel storage facility
Grass Planting - Fertilizer	lb	AC	\$0.20	All nutrients
Grass Planting - Introduced grasses	ac	AC	\$43.00	Includes seedbed preparation, drilling, and seed. Does not include establishment of standing cover crop nor addition of forbs / legumes to the mixture.
Grass Planting - Introduced grasses - Critical area planting	ac	AC	\$69.00	Includes seedbed preparation, drilling, and seed. Does not include establishment of standing cover crop nor addition of forbs / legumes to the mixture.
Grass Planting - Introduced legumes	ac	AC	\$2.70	Includes only seed cost. Legumes are seeded along with a grass seed mixture.
Grass Planting - Lime	tons	AC	\$12.00	Includes ECC tons of lime applied and application
Grass Planting - Native forbs / legumes	ac	AC	\$14.00	Includes only seed cost. Forbs / legumes are seeded along with a grass seed mixture.
Grass Planting - Native grasses	ac	AC	\$50.00	Includes seedbed preparation, drilling, and seed. Does not include establishment of standing cover crop nor addition of forbs / legumes to the mixture.
Grass Planting - Native grasses - Critical area planting	ac	AC	\$69.00	Includes seedbed preparation, drilling, and seed. Does not include establishment of standing cover crop nor addition of forbs / legumes to the mixture.
Grass Planting - Rhizomes (prairie cordgrass/common reed)	ea	AC	\$0.75	Includes planting and plants

*Cost Share Type: AC - Average cost; FR - Flat Rate

<i>Component</i>	<i>Unit</i>	<i>Cost Share Type*</i>	<i>Cost</i>	<i>Notes</i>
Grass Planting - Sprigs and sprigging (bermuda grass)	ac	AC	\$160.00	Includes seedbed preparation, sprigging, and sprigs
Grassed Waterway - Topsoiling - Special site conditions	ac	AC	\$870.00	Includes the topsoil and placement
Grassed Waterway - Shaping - All	ac	AC	\$1,240.00	Includes site preparation and shaping
Gravel - 3 in dia maximum	ton	AC	\$12.00	Includes material and application
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 4 in dia	lf	AC	\$3.70	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 6 in dia	lf	AC	\$4.70	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 8 in dia	lf	AC	\$5.80	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 10 in dia	lf	AC	\$7.60	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 12 in dia	lf	AC	\$10.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 15 in dia	lf	AC	\$15.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 18 in dia	lf	AC	\$21.80	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 21 in dia	lf	AC	\$23.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 24 in dia	lf	AC	\$24.50	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 30 in dia	lf	AC	\$35.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 36 in dia	lf	AC	\$39.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 42 in dia	lf	AC	\$55.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - PVC, dual wall PE, and CMP - 48 in dia	lf	AC	\$65.00	Includes main conduit, risers when main conduit > 100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - Single wall PE - 4 in dia	lf	AC	\$2.60	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - Single wall PE - 6 in dia	lf	AC	\$3.70	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - Single wall PE - 8 in dia	lf	AC	\$4.80	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - Single wall PE - 10 in dia	lf	AC	\$5.20	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - Single wall PE - 12 in dia	lf	AC	\$7.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - Single wall PE - 15 in dia	lf	AC	\$11.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards

*Cost Share Type: AC - Average cost; FR - Flat Rate

<i>Component</i>	<i>Unit</i>	<i>Cost Share Type*</i>	<i>Cost</i>	<i>Notes</i>
Inlet, Outlet, and Culvert - Single wall PE - 18 in dia	lf	AC	\$14.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inlet, Outlet, and Culvert - Single wall PE - 24 in dia	lf	AC	\$21.00	Includes main conduit, risers when main conduit >100 ft, manually tamped backfill, local berm, and bar and/or rodent guards
Inline Water Control Structure - 6 in dia	ea	AC	\$670.00	Includes inline water control structure, inlet and outlet pipe, manually tamped backfill of structure and pipe, bar guard, rodent guard, and back flap (if needed)
Inline Water Control Structure - 8 in dia	ea	AC	\$850.00	Includes inline water control structure, inlet and outlet pipe, manually tamped backfill of structure and pipe, bar guard, rodent guard, and back flap (if needed)
Inline Water Control Structure - 10 in dia	ea	AC	\$1,100.00	Includes inline water control structure, inlet and outlet pipe, manually tamped backfill of structure and pipe, bar guard, rodent guard, and back flap (if needed)
Inline Water Control Structure - >= 12 in dia	ea	AC	\$1,350.00	Includes inline water control structure, inlet and outlet pipe, manually tamped backfill of structure and pipe, bar guard, rodent guard, and back flap (if needed)
Irrigation - Conversion from high pressure to low pressure nozzles	ea	AC	\$29.00	Includes drops, pressure regulators, and nozzles
Irrigation - Conversion from surface to low pressure center pivot - <=320 ac	ac	AC	\$490.00	Includes the complete center pivot installation with towers, overhead pipelines, drops, pressure regulators, and nozzles (main line not included)
Irrigation - Conversion from surface to low pressure center pivot - >320 ac	ac	AC	\$270.00	Includes the complete center pivot installation with towers, overhead pipelines, drops, pressure regulators, and nozzles (main line not included)
Irrigation - Gated irrigation pipe - PVC and aluminum - 6, 8, and 10 in dia	lf	AC	\$3.50	Includes site preparation, pipe, and placement
Irrigation Pipeline - High pressure and low pressure plastic - <= 8 in dia	lf	AC	\$5.00	Includes valves, risers, dogleg (z-pipe), excavation, testing, and backfill (pump stand and flow meter not included in the cost)
Irrigation Pipeline - High pressure and low pressure plastic - 10 in dia	lf	AC	\$6.00	Includes valves, risers, dogleg (z-pipe), excavation, testing, and backfill (pump stand and flow meter not included in the cost)
Irrigation Pipeline - High pressure and low pressure plastic - 12 in dia	lf	AC	\$8.00	Includes valves, risers, dogleg (z-pipe), excavation, testing, and backfill (pump stand and flow meter not included in the cost)
Irrigation Pipeline - High pressure and low pressure plastic - >= 14 in dia	lf	AC	\$12.50	Includes valves, risers, dogleg (z-pipe), excavation, testing, and backfill (pump stand and flow meter not included in the cost)
Irrigation - Subsurface drip irrigation (SDI)	ac	AC	\$1,250.00	Includes the SDI system with filters, regulators, valves, manifold, laterals, and flush lines (main line not included)
Irrigation - Tree and Shrub	ea	AC	\$2.60	Includes pipe, applicators, filters, pressure regulators, and flush valves
Mechanical Solid/Liquid Separator	ea	FR	\$30,000.00	Includes site preparation, stand, separator, and installation
Metal End Section (flared end) - 6 in to 15 in dia	ea	AC	\$130.00	Includes material, installation, and backfill
Metal End Section (flared end) - 18 in to 24 in dia	ea	AC	\$200.00	Includes material, installation, and backfill
Metal End Section (flared end) - 30 in dia	ea	AC	\$350.00	Includes material, installation, and backfill
Metal End Section (flared end) - >=36 in dia	ea	AC	\$550.00	Includes material, installation, and backfill
Monitoring Well - Drilling and casing - <= 5 in dia	lf	AC	\$17.00	Includes site preparation, drilling, casing material, gravel pack, grout, and development
Mulching - Blanket Mulch	sqyd	AC	\$2.90	Includes application and material
Mulching - Plant Residue	ton	AC	\$45.00	Includes material only
Mulching - Weed barrier fabric	lf	AC	\$0.48	Includes application and material
Pest Management - Herbicide non-selective	ac	AC	\$8.50	Includes application and herbicide

*Cost Share Type: AC - Average cost; FR - Flat Rate

<i>Component</i>	<i>Unit</i>	<i>Cost Share Type*</i>	<i>Cost</i>	<i>Notes</i>
Pest Management - Herbicide selective	ac	AC	\$18.00	Includes application and herbicide
Pest Management - Mechanical	ac	AC	\$12.00	Includes all methods of tillage or mowing
Pipe Support - 6 in to 12 in dia pipe	ea	AC	\$185.00	Includes all materials (timber, connectors, pipe, concrete, etc.) and installation
Pipe Support - 15 in to 21 in dia pipe	ea	AC	\$250.00	Includes all materials (timber, connectors, pipe, concrete, etc.) and installation
Pipe Support - 24 in to 30 in dia pipe	ea	AC	\$450.00	Includes all materials (timber, connectors, pipe, concrete, etc.) and installation
Prescribed Burning	ac	AC	\$6.00	
Pump and Solar Panels System	ea	AC	\$4,250.00	Includes site preparation, pump, solar panels, and installation
Pump - Manure transfer	ea	AC	\$5,000.00	Includes pump, site preparation, and base
Riprap - Well Graded	ton	AC	\$48.00	Includes well graded material (EFH Part 642, Material Spec. 523, Type 3), delivery, and installation
Riprap - Poorly Sorted	ton	AC	\$20.00	Includes poorly sorted material (local source approved by designer), delivery, and installation
Riser for Inlet and Outlet (main conduit <=100 ft) - 6 in dia	ea	AC	\$125.00	Includes riser, orifice, and manually tamped backfill of riser - add this when the main conduit <= 100 ft
Riser for Inlet and Outlet (main conduit <=100 ft) - 8 in dia	ea	AC	\$200.00	Includes riser, orifice, and manually tamped backfill of riser - add this when the main conduit <= 100 ft
Riser for Inlet and Outlet (main conduit <=100 ft) - 10 in dia	ea	AC	\$330.00	Includes riser, orifice, and manually tamped backfill of riser - add this when the main conduit <= 100 ft
Riser for Inlet and Outlet (main conduit <=100 ft) - 12 in dia	ea	AC	\$400.00	Includes riser, orifice, and manually tamped backfill of riser - add this when the main conduit <= 100 ft
Riser for Inlet and Outlet (main conduit <=100 ft) - 15 in dia	ea	AC	\$550.00	Includes riser, orifice, and manually tamped backfill of riser - add this when the main conduit <= 100 ft
Roof	sqft	AC	\$7.90	Includes material and installation
Roof Gutters and Downspouts (per gutter length)	lf	AC	\$5.00	Includes gutter and downspout material and installation
Soda Ash	ton	AC	\$550.00	Includes amendment material and mixing of the soil with the amendment
Spring Development	ea	AC	\$2,450.00	Includes site preparation, collection and delivery pipe, spring box and/or riser-flush valve, rock or gravel, and installation
Staff Gauge - Waste Storage Facility	ea	AC	\$250.00	Includes materials and installation of staff gauges for waste storage facilities
Standing Cover Crop	ac	AC	\$30.00	Includes seedbed preparation, drilling, seed, and management of cover crop
Temporary Erosion Control - Filter fabric fence or straw bale barrier	lf	AC	\$3.00	Includes site preparation, material, and installation
Terrace - Level (channel width >30 ft--flat channel) - Including parallel	lf	AC	\$0.76	Includes site preparation, earthfill, and blocks
Terrace - Gradient and level (channel width <= 30 ft) - Including parallel	lf	AC	\$0.66	Includes site preparation, earthfill, and blocks
Terrace - Grass back slope <=15% slope	lf	AC	\$2.44	Includes site preparation, earthfill, and blocks
Terrace - Grass back slope >15% slope	lf	AC	\$3.30	Includes site preparation, earthfill, and blocks
Terrace - Underground outlet	lf	AC	\$1.05	Includes site preparation, earthfill, and blocks
Tree - Balled <= 18" Height	ea	AC	\$1.90	Includes seedbed preparation, planting, and plants
Tree - Balled > 18" Height	ea	AC	\$4.50	Includes seedbed preparation, planting, and plants

*Cost Share Type: AC - Average cost; FR - Flat Rate

<i>Component</i>	<i>Unit</i>	<i>Cost Share Type*</i>	<i>Cost</i>	<i>Notes</i>
Tree - Bareroot	ea	AC	\$1.40	Includes seedbed preparation, planting, and plants
Tree - Containerized	ea	AC	\$4.30	Includes seedbed preparation, planting, and plants
Tree - Cuttings (willow species)	ea	AC	\$2.50	Includes harvesting, planting, and plants
Tree - Direct seeding	ac	AC	\$200.00	Includes seedbed preparation, planting, and plants
Tree - Herbicide selective	ac	AC	\$43.00	Includes herbicide and application
Waste Facility Cover - Ethylene propylene diene terpolymer (EPDM)	sqft	AC	\$0.70	Includes EPDM synthetic rubber material and installation
Waste Pond Liner - (PVC, PE, or EPDM)	sqft	AC	\$0.85	Includes liner material, geotextile for side slopes, subgrade preparation, liner placement, and placement of soil cover
Waste Pond Liner - Covered Geosynthetic Clay Liner (GCL)	sqft	AC	\$0.85	Includes GCL, subgrade preparation, liner placement, and placement of soil cover
Waste Water Valve - 4-inch dia	ea	AC	\$220.00	Includes valve, fittings, and installation in gravity discharge pipes used for emptying a storage or treatment facility
Waste Water Valve - 6-inch dia	ea	AC	\$250.00	Includes valve, fittings, and installation in gravity discharge pipes used for emptying a storage or treatment facility
Waste Water Valve - 8-inch dia	ea	AC	\$300.00	Includes valve, fittings, and installation in gravity discharge pipes used for emptying a storage or treatment facility
Water Supply Line - <= 2 in dia	lf	AC	\$1.45	Includes valves, hydrants, excavation, testing, and backfill
Water Supply Line - > 2 in dia	lf	AC	\$1.75	Includes valves, hydrants, excavation, testing, and backfill
Water Supply Line, Siphon Over Dam - 1½ in and 2 in dia	ea	AC	\$1,000.00	Includes intake, valves, valve box and lid, filler pipe assembly, excavation, testing, and manually tamped backfill
Water Supply Line, Under Dam - 1½ in and 2 in dia	ea	AC	\$450.00	Includes intake, valves, operating rod, valve box and lid, anti-seep collars or sand diaphragm, testing, and manually tamped backfill
Water Supply Line, Under Dam - >= 4 in dia	ea	AC	\$1,000.00	Includes intake, valves, operating rod, valve box and lid, anti-seep collars or sand diaphragm, testing, and manually tamped backfill
Water Well - Drilling and casing	lf	AC	\$17.00	Includes site preparation, drilling, casing material, gravel pack, grout, and development
Water Well Plugging (Decommissioning) - <= 15 in dia	ea	AC	\$500.00	Includes site preparation, material, plugging, and spoil disposal
Water Well Plugging (Decommissioning) - > 15	ea	AC	\$700.00	Includes site preparation, material, plugging, and spoil disposal
Watering Facility - Watering Fountain - <= 100 gal.	ea	AC	\$950.00	Includes site preparation, fountain, concrete and additives, sand, gravel, crushed rock, float, overflow, and installation
Watering Facility - Additional Storage Tank - Fiberglass or steel	ea	AC	\$1,000.00	Includes site preparation, platform, storage tank, float, and installation
Watering Facility - Tank - Any approved material	gal	AC	\$1.00	Includes site preparation, rim or tank, concrete and additives, sand, gravel, crushed rock, float, overflow, and installation
Watering Facility - Frost Free - Earth covered tank	ea	AC	\$850.00	Includes site preparation, tank, sand, gravel, crushed rock, earth cover, vent, float, overflow, and installation
Well Water Testing	ea	AC	\$100.00	Includes water sampling, water test analysis, and test results and interpretations
Wildlife Guzzler - >=10 ft by >=10 ft surface	ea	AC	\$490.00	Includes site preparation, frame, roof, gutter, downspout, storage tank, access ramp, and installation
Wood Picket Structure	sqft	AC	\$18.00	Includes all material and installation

*Cost Share Type: AC - Average cost; FR - Flat Rate