

PracticeName	PracticeCode	Soil Erosion	Soil Erosion2	Soil Erosion3	Soil Erosion4	Soil Erosion5	Soil Quality Degradation	Soil Quality Degradation6	Soil Quality Degradation7
		-Sheet, Rill, & Wind Erosion	-Sheet, Rill, & Wind Erosion	-Concentrated Flow Erosion	-Concentrated Flow Erosion	-Excessive Bank Erosion from Streams Shorelines or Water Conveyance Channels	-Organic Matter Depletion	-Compaction	-Subsidence
		-- Sheet and Rill Erosion	-- Wind Erosion	-- Ephemeral Gully Erosion	-- Classic Gully Erosion	-- Streambank, Shoreline, Water Conveyance Channels	-- Organic Matter Depletion	-- Compaction	-- Subsidence
Irrigation System, Sprinkler	442	0	2	0	0	0	0	-1	0
Irrigation System, Surface and Subsurface	443	0	1	0	-1	-1	0	-1	0
Irrigation System, Tailwater Recovery	447	0	0	1	1	1	0	0	0
Irrigation Water Conveyance, Ditch and Canal Lining, Flexible Membrane	428B	0	0	0	0	0	0	0	0
Irrigation Water Conveyance, Ditch and Canal Lining, Plain Concrete	428A	0	0	0	0	0	0	0	0
Irrigation Water Management	449	0	2	0	0	0	1	0	0
Karst Sinkhole Treatment	527	0	0	4	4	0	0	0	0
Land Clearing	460	0	0	0	0	0	-3	-1	0
Land Reclamation, Abandoned Mined Land	543	4	4	4	1	0	3	1	0
Land Reclamation, Currently Mined Land	544	4	4	4	1	0	3	1	0
Land Smoothing	466	0	0	1	0	0	-2	-2	0
Lined Waterway or Outlet	468	0	0	5	2	0	0	0	0
Livestock Shade Structure	717	0	0	0	0	0	0	0	0
Monitoring and Evaluation	799	0	0	0	0	0	0	0	0
Mulching	484	4	4	1	1	2	2	0	0
Nutrient Management	590	0	0	0	0	0	2	0	0
Obstruction Removal	500	0	0	0	0	0	1	-1	0
Open Channel	582	0	0	0	0	2	0	0	0
Pipeline	516	0	0	0	1	0	0	1	0
Pond	378	0	0	0	2	1	0	0	0
Pond Sealing or Lining, Bentonite Sealant	521C	0	0	0	0	0	0	0	0
Pond Sealing or Lining, Compacted Clay Treatment	521D	0	0	0	0	0	0	0	0
Pond Sealing or Lining, Flexible Membrane	521A	0	0	0	0	0	0	0	0
Pond Sealing or Lining, Soil Dispersant	521B	0	0	0	0	0	0	0	0
Precision Land Forming	462	0	0	2	4	0	-2	-1	0
Prescribed Burning	338	2	2	1	1	1	1	0	-1
Prescribed Grazing	528	4	4	3	1	3	4	2	0
Pumping Plant	533	0	0	0	0	0	0	0	2
Range Planting	550	4	4	4	2	2	4	4	0
Recreation Area Improvement	562	1	1	1	1	1	1	1	0
Recreation Land Grading and Shaping	566	0	0	0	4	2	1	0	0
Recreation Trail and Walkway	568	1	1	1	4	2	0	2	0
Residue and Tillage Management, Mulch Till	345	4	4	1	2	0	2	1	0
Residue and Tillage Management, No- Till/Strip Till/Direct Seed	329	4	4	4	3	0	3	2	0
Residue and Tillage Management, Ridge Till	346	4	4	4	1	0	2	2	0
Residue Management, Seasonal	344	1	1	1	1	0	1	0	0
Restoration and Management of Declining Habitats	643	2	2	2	0	0	0	0	0
Riparian Forest Buffer	391	3	2	1	3	4	4	4	0
Riparian Herbaceous Cover	390	2	2	1	0	4	4	4	0
Roof Runoff Structure	558	2	0	3	3	1	0	0	0
Roofs and Covers	367	0	0	0	-2	0	0	0	0
Row Arrangement	557	3	1	3	0	0	1	0	0
Runoff Management System	570	0	0	2	0	3	0	1	0
Salinity and Sodic Soil Management	610	0	0	0	0	0	0	0	0
Seasonal High Tunnel System for Crops	798	0	0	-1	0	0	1	0	0
Sediment Basin	350	0	0	2	2	0	0	0	0
Shallow Water Development and Management	646	0	0	0	0	0	1	0	0
Silvopasture Establishment	381	5	5	5	2	2	4	0	0
Spoil Spreading	572	0	0	0	0	0	1	-1	0

PracticeName	PracticeCode	Soil Erosion	Soil Erosion2	Soil Erosion3	Soil Erosion4	Soil Erosion5	Soil Quality Degradation	Soil Quality Degradation6	Soil Quality Degradation7
		-Sheet, Rill, & Wind Erosion	-Sheet, Rill, & Wind Erosion	-Concentrated Flow Erosion	-Concentrated Flow Erosion	-Excessive Bank Erosion from Streams Shorelines or Water Conveyance Channels	-Organic Matter Depletion	-Compaction	-Subsidence
		-- Sheet and Rill Erosion	-- Wind Erosion	-- Ephemeral Gully Erosion	-- Classic Gully Erosion	-- Streambank, Shoreline, Water Conveyance Channels	-- Organic Matter Depletion	-- Compaction	-- Subsidence
Spring Development	574	0	0	0	1	1	0	-1	0
Stream Crossing	578	0	0	0	0	2	0	0	0
Stream Habitat Improvement and Management	395	0	0	0	0	5	0	0	0
Streambank and Shoreline Protection	580	0	0	0	0	4	0	0	0
Stripcropping	585	4	4	4	0	0	2	0	0
Structure for Water Control	587	0	0	0	0	0	0	0	0
Surface Drainage, Field Ditch	607	0	-1	2	-1	0	-2	2	-1
Surface Drainage, Main or Lateral	608	0	-1	2	-1	0	0	2	0
Terrace	600	5	1	4	2	1	1	-1	0
Tree/Shrub Establishment	612	5	5	4	2	2	4	2	0
Tree/Shrub Pruning	660	1	0	0	0	0	1	0	0
Tree/Shrub Site Preparation	490	0	0	0	0	0	0	0	0
Underground Outlet	620	0	0	5	4	-1	0	0	0
Upland Wildlife Habitat Management	645	3	3	3	2	1	0	0	0
Vegetated Treatment Area	635	4	4	0	0	0	3	3	0
Vegetative Barrier	601	4	1	5	2	0	0	0	0
Waste Storage Facility	313	0	0	0	0	0	1	1	0
Waste Transfer	634	0	0	0	0	0	0	-1	0
Waste Treatment	629	0	0	0	0	0	1	1	0
Waste Treatment Lagoon	359	0	0	0	0	0	1	1	0
Waste Utilization	633	2	1	1	0	0	2	0	0
Water and Sediment Control Basin	638	0	0	2	2	0	0	0	0
Water Well	642	2	2	2	0	0	0	0	0
Watering Facility	614	2	2	2	3	4	0	0	0
Well Decommissioning	351	0	0	0	0	0	0	0	0
Wetland Creation	658	0	0	0	0	0	2	0	0
Wetland Enhancement	659	0	0	0	0	0	1	0	0
Wetland Restoration	657	0	0	0	0	0	1	0	0
Wetland Wildlife Habitat Management	644	0	0	0	0	0	0	0	0
Windbreak/Shelterbelt Establishment	380	1	5	2	0	0	4	2	0
Woody Residue Treatment	384	1	1	1	1	0	-1	-2	0

