

**Practice: 309 - Agrichemical Handling Facility**

**Scenario: #1 - Agrichemical Storage with Handling Pad inside an enclosed building**

**Scenario Description:**

This practice scenario is an agrichemical handling facility for storage and mixing and loading operations. This practice addresses water quality degradation and due to mis-handling, storing and mixing of agrichemicals where nutrients and/or chemicals are running off into surface waters or leaching into ground water.

Associated practices: Heavy Use Area Protection (561), Diversion (362), Access Road (560), Pipeline (516), Roof Runoff Management (558), Pumping Plant for Water Control (533), Nutrient Management (590), Pest Management (595)

**Before Situation:**

Agrichemicals are improperly stored on the ground or next to a well. Operator mixes the agrichemicals and fills the sprayer tank next to a hydrant. Spills or overflows of agrichemicals contaminate the soil, runoff to surface waters and leaching to ground water.

**After Situation:**

An agrichemical storage and handling facility is constructed inside an enclosed building. The average size of the agrichemical handling facility for storage and mixing and loading is 35' x 40' with an application equipment length of 36 ft. The handling pad for mixing and loading operations is sized to contain the length of the agrichemical spray tank and its volume. Install a curbed reinforced concrete handling pad for mixing and loading with proper storage of associated dry and/or liquid agrichemicals. The concrete is sealed and sloped to a collection sump, facility containment is surrounded by square and ramped curbs. This practice will contain agrichemicals and prevent contamination of surface and ground water resources.

**Scenario Feature Measure:** Total Containment Area

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 1,400

**Scenario Cost:** \$25,681.32

**Scenario Cost/Unit:** \$18.34

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$105.40	18	\$1,897.20
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$333.03	10	\$3,330.30
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$61.56	8	\$492.48
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.19	8	\$209.52
<b>Materials</b>						
Post Frame Building, enclosed 4 sides	1046	Enclosed post frame building, four walls. Building sites with expected snow loads up to 30 lbs per square foot and wind exposure in semi protected areas (wooded or terrain with numerous closely spaced obstructions). Includes materials, shipping, and lab	Square Foot	\$9.47	1760	\$16,667.20
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$34.40	22	\$756.80
Emergency shower and eye wash station	1499	Emergency shower and eye wash station unit. Materials only.	Each	\$586.94	1	\$586.94
Painting, concrete surface, impermeable	1497	Painting of concrete surfaces with an impermeable coating. Includes materials and application.	Square Foot	\$1.03	1400	\$1,442.00
<b>Mobilization</b>						

**Mobilization**

Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$64.67	1	\$64.67
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	1	\$234.21

**Practice: 309 - Agrichemical Handling Facility**

**Scenario: #2 - Earthen Liquid Agrichemical Storage with a Handling Pad**

**Scenario Description:**

This practice scenario is an agrichemical handling facility for storage of liquid agrichemicals along with a mixing and loading pad. This practice addresses water quality degradation and due to mis-handling, storing, and mixing of agrichemicals where nutrients and/or chemicals are running off into surface waters or leaching into ground water.

Associated practices: Heavy Use Area

Protection (561), Diversion (362), Access Road (560), Pipeline (516), Pumping Plant for Water Control (533), Nutrient Management (590), Pest Management (595), Pond Sealing or Lining Flexible Membrane (521A)

**Before Situation:**

Agrichemicals are improperly stored on the ground or next to a well. Operator mixes the agrichemicals and fills the sprayer tank next to a hydrant. Spills or overflows of agrichemicals contaminate the soil, runoff to surface waters and leaching to ground water.

**After Situation:**

An agrichemical handling facility is constructed for storage of liquid agrichemicals along with a handling pad for mixing and loading operations. The average size of the agrichemical handling facility for proper storage of liquid agrichemicals is in an earthen lined containment with bottom dimensions of 30 ft x 40 ft. A handling pad for mixing and loading is located next to the liquid containment and is 20' x 40' with an application equipment length of 36 ft. The handling pad for mixing and loading operations is sized to contain the length of the agrichemical spray tank and its volume. Install a curbed reinforced concrete handling pad for mixing and loading. The concrete is sealed and sloped to a collection sump. This practice will contain agrichemicals and prevent contamination of surface and ground water resources.

**Scenario Feature Measure:** Floor surface area of Liquid Containment Area + Handling pad

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 2,000

**Scenario Cost:** \$4,374.10

**Scenario Cost/Unit:** \$2.19

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$1.96	235	\$460.60
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.14	70	\$149.80
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$105.40	15	\$1,581.00
<b>Materials</b>						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$34.86	9	\$313.74
Painting, concrete surface, impermeable	1497	Painting of concrete surfaces with an impermeable coating. Includes materials and application.	Square Foot	\$1.03	800	\$824.00
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$34.40	13	\$447.20
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	2	\$468.42
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$64.67	2	\$129.34

**Practice: 309 - Agrichemical Handling Facility**

**Scenario: #3 - Fabricated Liquid Agrichemical Storage with a Handling Pad**

**Scenario Description:**

This practice scenario is an agrichemical handling facility for storage of liquid agrichemicals along with a mixing and loading pad. Due to topography, limited site space and/or geological conditions a fabricated structure is needed. This practice addresses water quality degradation and due to mis-handling, storing, and mixing of agrichemicals where nutrients and/or chemicals are running off into surface waters or leaching into ground water.

Associated

practices: Heavy Use Area Protection (561), Diversion (362), Access Road (560), Pipeline (516), Pumping Plant for Water Control (533), Nutrient Management (590), Pest Management (595), Pond Sealing or Lining Flexible Membrane (521A)

**Before Situation:**

Agrichemicals are improperly stored on the ground or next to a well. Operator mixes the agrichemicals and fills the sprayer tank next to a hydrant. Spills or overflows of agrichemicals contaminate the soil, runoff to surface waters and leaching to ground water.

**After Situation:**

An agrichemical handling facility is constructed for storage of liquid agrichemicals along with a handling pad for mixing and loading operations. The average size of the agrichemical handling facility for proper storage of liquid agrichemicals is in fabricated containment that is 30 ft x 40 ft with flexible membrane lined walls. The walls are of modular blocks stacked two for a 4ft wall height on four sides. A handling pad for mixing and loading is located next to the liquid containment and is 16' x 32' with an application equipment length of 28 ft. The handling pad for mixing and loading operations is sized to contain the length of the agrichemical spray tank and its volume. Install a curbed reinforced concrete handling pad for mixing and loading. The concrete is sealed and sloped to a collection sump. This practice will contain agrichemicals and prevent contamination of surface and ground water resources.

**Scenario Feature Measure: Liquid Containment Area + Handling Pad**

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 1,712

**Scenario Cost:** \$12,010.82

**Scenario Cost/Unit:** \$7.02

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.14	15	\$32.10
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$105.40	19	\$2,002.60
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$61.56	8	\$492.48
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$39.53	8	\$316.24
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$333.03	8	\$2,664.24

**Materials**

Painting, concrete surface, impermeable	1497	Painting of concrete surfaces with an impermeable coating. Includes materials and application.	Square Foot	\$1.03	512	\$527.36
Block, pre-cast concrete, modular	1496	Pre-cast concrete blocks, typically 2ft x 2ft x 6ft , includes installation and delivery.	Cubic Yard	\$104.44	42	\$4,386.48
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$34.86	4	\$139.44
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$34.40	27	\$928.80

**Mobilization**

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$157.53	1	\$157.53
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	1	\$234.21
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$64.67	2	\$129.34

**Practice: 309 - Agrichemical Handling Facility**

**Scenario: #4 - Outdoor Liquid Agrichemical Storage with a Roofed Building for Dry Chemical Storage and Handling Pad**

**Scenario Description:**

This practice scenario is an agrichemical handling facility for storage of liquid agrichemicals along with a roofed mixing and loading pad that is also sized to store dry chemicals. This practice addresses water quality degradation and due to mis-handling, storing, and mixing of agrichemicals where nutrients and/or chemicals are running off into surface waters or leaching into ground water.

Associated practices: Heavy Use Area

Protection (561), Diversion (362), Access Road (560), Pipeline (516), Pumping Plant for Water Control (533), Nutrient Management (590), Pest Management (595), Pond Sealing or Lining Flexible Membrane (521A), Roof Runoff Management (558)

**Before Situation:**

Agrichemicals are improperly stored on the ground or next to a well. Operator mixes the agrichemicals and fills the sprayer tank next to a hydrant. Spills or overflows of agrichemicals contaminate the soil, runoff to surface waters and leaching to ground water.

**After Situation:**

An agrichemical handling facility is constructed for storage of liquid agrichemicals along with a roofed building to store dry agrichemicals with a handling pad for mixing and loading operations. The average size of the agrichemical handling facility for proper storage of liquid agrichemicals is in an earthen lined containment with bottom dimensions of 60 ft x 40 ft. A roofed building for dry agrichemicals and handling pad for mixing and loading is located next to the liquid containment and is 30' x 40' with an application equipment length of 36 ft. The handling pad for mixing and loading operations is roofed and sized to contain the length of the agrichemical spray tank and its volume. Install a curbed reinforced concrete handling pad for mixing and loading. The concrete is sealed and sloped to a collection sump, facility containment has at least two sides constructed of 5 ft post and plant walls. This practice will contain agrichemicals and prevent contamination of surface and ground water resources.

**Scenario Feature Measure:** Floor surface area of Liquid Containment Area + Handling pad

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 3,600

**Scenario Cost:** \$21,095.11

**Scenario Cost/Unit:** \$5.86

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$105.40	19	\$2,002.60
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$1.96	380	\$744.80
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.14	231	\$494.34
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$333.03	2.6	\$865.88
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$20.63	80	\$1,650.40
<b>Materials</b>						
Dimension Lumber, Treated	1044	Treated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners	Board Foot	\$0.85	853	\$725.05
Roof, Post Frame Building, 30' to 60' wide	1676	Post Frame Building, no sides, - 30' to 60' width. Building sites with expected snow loads up to 30 lbs per square foot and wind exposure in semi protected areas (wooded or terrain with numerous closely spaced obstructions). Includes materials, shipping	Square Foot	\$5.40	2000	\$10,800.00

**Materials**

Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$34.86	38	\$1,324.68
Painting, concrete surface, impermeable	1497	Painting of concrete surfaces with an impermeable coating. Includes materials and application.	Square Foot	\$1.03	1200	\$1,236.00
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$34.40	19	\$653.60

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	2	\$468.42
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$64.67	2	\$129.34

**Practice: 309 - Agrichemical Handling Facility**

**Scenario: #5 - Agrichemical Handling Pad for mixing and loading**

**Scenario Description:**

This practice scenario is an agrichemical handling facility for mixing and loading operations. This practice addresses water quality degradation and due to mis-handling, and mixing of agrichemicals where nutrients and/or chemicals are running off into surface waters or leaching into ground water.

Associated practices:

Heavy Use Area Protection (561), Diversion (362), Access Road (560), Pipeline (516), Pumping Plant for Water Control (533), Nutrient Management (590), Pest Management (595)

**Before Situation:**

Agrichemicals are improperly stored on the ground or next to a well. Operator mixes the agrichemicals and fills the sprayer tank next to a hydrant. Spills or overflows of agrichemicals contaminate the soil, runoff to surface waters and leaching to ground water.

**After Situation:**

This scenario is an agrichemical handling facility pad for mixing and loading operations. The average size of the agrichemical handling pad for mixing and loading is 16' x 40' with an application equipment length of 36 ft. The handling pad for mixing and loading operations is sized to contain the length of the agrichemical spray tank and its volume. Install a curbed reinforced concrete handling pad for mixing and loading. The concrete is sealed and sloped to a collection sump, containment of the pad is surrounded by sloped and ramped reinforced concrete. This practice will contain agrichemicals and prevent contamination of surface and ground water resources.

**Scenario Feature Measure:** Total Containment Area

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 640

**Scenario Cost:** \$3,000.40

**Scenario Cost/Unit:** \$4.69

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$105.40	12	\$1,264.80
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$61.56	4	\$246.24
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.19	4	\$104.76
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$20.63	4	\$82.52
<b>Materials</b>						
Painting, concrete surface, impermeable	1497	Painting of concrete surfaces with an impermeable coating. Includes materials and application.	Square Foot	\$1.03	640	\$659.20
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$34.40	10	\$344.00
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	1	\$234.21
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$64.67	1	\$64.67

**Practice: 309 - Agrichemical Handling Facility**

**Scenario: #6 - Agrichemical Storage & Handling for Greenhouses**

**Scenario Description:**

This practice scenario is an agrichemical storage and handling facility for mixing and loading operations within a greenhouse. This practice addresses water quality degradation and due to mis-handling, storing, and mixing of agrichemicals where nutrients and/or chemicals are running off into surface waters or leaching into ground

water.

Associated practices: Heavy Use Area

Protection (561), Diversion (362), Pipeline (516), Pumping Plant for Water Control (533), Nutrient Management (590), Pest Management (595)

**Before Situation:**

Agrichemicals are improperly stored on the ground or next to a well. Operator mixes the agrichemicals and fills the sprayer tank next to a hydrant. Spills or overflows of agrichemicals contaminate the soil, runoff to surface waters and leaching to ground water.

**After Situation:**

This scenario is an agrichemical handling facility storage an impermeable barrier poly pad for mixing and loading operations. The average size of the agrichemical handling storage is for a pallet drum on a 5 ft x 5 ft containment pallet with sump capacity included. A poly pad is used for mixing and loading that is 8ft x 8ft with an application equipment length of 4 ft. The handling pad for mixing and loading operations is sized to contain the length of the agrichemical spray tank and its volume. This practice will contain agrichemicals and prevent contamination of surface and ground water resources.

**Scenario Feature Measure:** Storage Containment Area + Handling pad

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 89

**Scenario Cost:** \$1,789.51

**Scenario Cost/Unit:** \$20.11

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$20.63	8	\$165.04
<b>Materials</b>						
PVC Containment Basin, 6' x 6'	1611	Poly containment basin typically 8" to 12" deep with area dimensions in the range of 6' x 6' or larger.	Square Foot	\$20.89	64	\$1,336.96
2 Drum Spill Pallet, 66 Gallon	1610	Pre fabricated containment basin with a capacity of approximately 66 gal. Materials only.	Each	\$287.51	1	\$287.51

**Practice: 309 - Agrichemical Handling Facility**

**Scenario: #7 - Agrichemical Storage with Handling Pad in an Existing Building**

**Scenario Description:**

This practice scenario is an agrichemical handling facility for storage and mixing and loading operations. This practice addresses water quality degradation and due to mis-handling, storing and mixing of agrichemicals where nutrients and/or chemicals are running off into surface waters or leaching into ground water.

Associated practices: Heavy Use Area Protection (561), Diversion (362), Access Road (560), Pipeline (516), Roof Runoff Management (558), Pumping Plant for Water Control (533), Nutrient Management (590), Pest Management (595)

**Before Situation:**

Agrichemicals are improperly stored on the ground or next to a well. Operator mixes the agrichemicals and fills the sprayer tank next to a hydrant. Spills or overflows of agrichemicals contaminate the soil, runoff to surface waters and leaching to ground water.

**After Situation:**

An agrichemical storage and handling facility is constructed inside an existing building. The average size of the agrichemical handling facility for storage and mixing and loading is 24 ft x 36 ft with an application equipment length of 30 ft. The handling pad for mixing and loading operations is sized to contain the length of the agrichemical spray tank and its volume. Install a curbed reinforced concrete handling pad for mixing and loading with proper storage of associated dry and/or liquid agrichemicals. The concrete is sealed and sloped to a collection sump, facility containment is surrounded by square and ramped curbs and independent of the existing building. This practice will contain agrichemicals and prevent contamination of surface and ground water resources.

**Scenario Feature Measure:** Total Containment Area

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 864

**Scenario Cost:** \$7,439.59

**Scenario Cost/Unit:** \$8.61

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$61.56	4	\$246.24
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$105.40	14	\$1,475.60
Demolition, concrete	1498	Demolition and disposal of reinforced concrete structures including slabs and walls. Includes labor and equipment.	Cubic Yard	\$15.18	7	\$106.26
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$333.03	8	\$2,664.24
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$39.53	10	\$395.30
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$20.63	16	\$330.08
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.19	4	\$104.76
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$21.25	10	\$212.50
<b>Materials</b>						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$34.40	14	\$481.60

**Materials**

Painting, concrete surface, impermeable	1497	Painting of concrete surfaces with an impermeable coating. Includes materials and application.	Square Foot	\$1.03	864	\$889.92
---	------	--	-------------	--------	-----	----------

**Mobilization**

Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$64.67	1	\$64.67
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	2	\$468.42