

**Practice: 521B - Pond Sealing or Lining, Soil Dispersant**

**Scenario: #2 - Covered, Compacted soil liner, Soil Dispersant**

**Scenario Description:**

Construction of a compacted soil liner, treated with a soil dispersant, to reduce seepage from ponds or waste storage impoundment structures. Practice implementation includes incorporation of the dispersant with the soil liner under proper moisture conditions, compaction to the designed liner thickness, and placement of soil cover over the treated liner. Practice implementation may require filter compatibility with the subgrade (graded filter or geotextile). Associated practice PS378, PS313.

**Before Situation:**

In-place soils at site exhibit seepage rates in excess of acceptable limits. Soils are suitable for treatment with dispersants.

**After Situation:**

Water conservation and environmental protection provided by limiting seepage losses from ponds or waste storage impoundments.

**Scenario Feature Measure:** Volume of Liner Material including Soil Cover over Liner

**Scenario Unit:** Cubic Yard

**Scenario Typical Size:** 3,226

**Scenario Cost:** \$16,049.62

**Scenario Cost/Unit:** \$4.98

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
	1143				1	
<b>Equipment/Installation</b>						
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$50.02	6	\$300.12
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$3.65	3226	\$11,774.90
<b>Labor</b>						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$21.25	6	\$127.50
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.30	8	\$298.40
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$100.73	2	\$201.46
<b>Materials</b>						
Soil Dispersant	1490	Soil Amendment (tetrasodium pyrophosphate (TSPP), sodium tripolyphosphate (STPP), or soda ash or approved equivalent)	Ton	\$476.57	6.53	\$3,112.00
<b>Mobilization</b>						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	\$1.03	1	\$1.03
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	1	\$234.21