

Practice: 578 - Stream Crossing

Scenario: #2 - Hard armored low water crossing

Scenario Description:

Stabilize the bottom and slope of a stream channel using rock riprap or cast in place concrete. The typical scenario includes site preparation, dewatering, acquiring and installing gravel or geotextile with rock riprap or cast in place concrete on channel bottom and approaches. Final travel surface shall be the rocks or concrete. If a different travel surface is needed, refer to another appropriate standard for the surfacing. The cost estimate is based on a typical stream that has 30 foot bottom width and approaches. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

Before Situation:

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

After Situation:

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

Scenario Feature Measure: Crossing dimensions

Scenario Unit: Square Foot

Scenario Typical Size: 420

Scenario Cost: \$2,892.55

Scenario Cost/Unit: \$6.89

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$88.70	2	\$177.40
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.65	18	\$29.70
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.19	2	\$52.38
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$133.27	18	\$2,398.86
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	1	\$234.21

Practice: 578 - Stream Crossing

Scenario: #3 - Culvert installation

Scenario Description:

Install a new culvert. Work may include dewatering, site preparation and removing any old crossing, acquiring and installing culvert pipe with gravel bedding and fill (compacted), and building headwalls. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Cost estimate is based on a 36 inch Culvert installation with <75 cy of fill needed and < 2 yds rock riprap for headwalls. Pipe is 40 feet long. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic. Use (587) Structure for Water Control instead, for ditch cross culverts and other intermittent flows.

Before Situation:

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

After Situation:

Access road and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

Scenario Feature Measure: Culvert

Scenario Unit: Diameter Inch Foot

Scenario Typical Size: 720

Scenario Cost: \$4,663.52

Scenario Cost/Unit: \$6.48

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$4.79	3	\$14.37
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$104.47	10	\$1,044.70
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.19	10	\$261.90
Materials						
Pipe, HDPE, CPT, Double Wall, Soil Tight, 30"	1247	Pipe, Corrugated HDPE Double Wall, 30" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$27.47	40	\$1,098.80
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$133.27	2	\$266.54
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$34.86	50	\$1,743.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	1	\$234.21

Practice: 578 - Stream Crossing

Scenario: #4 - Low water crossing using prefabricated products

Scenario Description:

To install a stable crossing medium on channel bottom and approaches. Medium includes but not limited to precast concrete blocks, geocells, pavers, and gabions. If a different travel surface is needed, refer to another appropriate standard for the surfacing. This cost estimate is based on a typical stream that has a 30 foot bottom width and approaches. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

Before Situation:

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

After Situation:

Access road and waterflow are able to cross each other in a stable manner. Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

Scenario Feature Measure: low water crossing

Scenario Unit: Square Foot

Scenario Typical Size: 420

Scenario Cost: \$3,029.06

Scenario Cost/Unit: \$7.21

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.65	18	\$29.70
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$88.70	2	\$177.40
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.19	2	\$52.38
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$20.63	40	\$825.20
Materials						
GeoCell, 4"	1054	Polymer 3-D cellular grid 4" deep that is filled with stone or earth. Includes materials, labor and equipment for the geocell only, does not include backfill.	Square Yard	\$22.21	50	\$1,110.50
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$34.86	18	\$627.48
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$34.40	6	\$206.40

Practice: 578 - Stream Crossing

Scenario: #5 - Steam Crossing, Concrete Bottom

Scenario Description:

Stabilize the bottom and slope of a stream channel using cast in place concrete with gravel approaches. This scenario includes site preparation, dewatering, acquiring and installing gravel or geotextile with gravel and cast in place concrete on channel bottom and approaches. Final travel surface shall be the rocks above normal highwater mark and concrete below the normal highwater mark. If a different travel surface is needed, refer to another appropriate standard for the surfacing. Typical stream used for cost estimate has 30 linear feet of concrete (bottom width and approaches) with 10 foot gravel approaches on either side above the normal highwater mark. Width is 14 feet for a total area as 420sf. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

Before Situation:

An unimproved stream crossing has rill and gully erosion causing excessive sediments and excess nutrient potential. Erosion is made worse by vehicle traffic through the stream or rutting has progressed to the point that access to the field on the other side is no longer possible. Stream flow/velocity during storm events is such that culverts or a less rigid ford type crossing is not anticipated to last its design life. Access is difficult to the field across the stream and water quality is negatively impacted.

After Situation:

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

Scenario Feature Measure: Crossing dimensions

Scenario Unit: Square Foot

Scenario Typical Size: 420

Scenario Cost: \$3,184.09

Scenario Cost/Unit: \$7.58

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$105.40	18	\$1,897.20
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$88.70	2	\$177.40
Excavation, common earth, wet, side cast, large equipment	1228	Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$3.85	50	\$192.50
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$20.63	16	\$330.08
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.19	2	\$52.38
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$34.40	5	\$172.00
Geotextile, non-woven, heavy weight	1210	Non-woven greater than 8 ounce/square yard geotextile with staple anchoring. Materials and shipping only.	Square Yard	\$4.01	32	\$128.32
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$234.21	1	\$234.21