

**Practice: 436 - Irrigation Reservoir**

**Scenario: #1 - Embankment Dam with On-Site Borrow, 3 ac ft Reservoir**

**Scenario Description:**

The reservoir, created by an embankment built across a natural depression, with an 18" diameter principal spillway outlet through the embankment, is controlled by a canal-style gate. Outlet can also serve as overflow protection with a 12" diameter standpipe and tee to the 18" pipe. Any watershed runoff will be diverted around reservoir. It will be built with approximately 4,500 cubic yards of on-site material. It will be about 19.9 feet high and 200 feet long and hold approximately 1,000,000 gallons (3 acre-feet). The top of berm will be 10 feet wide and the embankment side slopes will be 2.5 H to 1 V up and down stream.

Resource concern: Insufficient Water - Inefficient use of irrigation water.

Associated practices include: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 378 - Pond; 447 - Irrigation System, Tailwater Recovery; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

Divert water around - no spillway

**After Situation:**

This is an embankment, installed across a natural off-stream intermittent watercourse, used to store water for subsequent irrigation. It will be used to accumulate and store water for timely and efficient application of water through an irrigation system. The water source could be a well, irrigation district pipeline, and/or a pump from a stream. It is designed to deliver water by gravity to an open ditch or non-pressurized pipeline, generally in excess of 5 cfs. All earthen materials will be from on-site sources.

**Scenario Feature Measure: Volume of Compacted Earthfill**

**Scenario Unit:** Cubic Yards

**Scenario Typical Size:** 4,500

**Scenario Cost:** \$20,352.03

**Scenario Cost/Unit:** \$4.52

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, common earth, large equipment, 1500 ft	1221	Bulk excavation of common earth including sand and gravel with scrapers with average haul distance of 1500 feet. Includes equipment and labor.	Cubic Yard	\$3.46	4500	\$15,570.00
<b>Labor</b>						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.98	8	\$303.84
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.98	16	\$303.68
<b>Materials</b>						
Pipe, HDPE, CPT, Double Wall, Soil Tight, 12"	1244	Pipe, Corrugated HDPE Double Wall, 12" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$7.05	36	\$253.80
Pipe, HDPE, CPT, Double Wall, Soil Tight, 18"	1245	Pipe, Corrugated HDPE Double Wall, 18" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$10.87	120	\$1,304.40
Coupling, HDPE CPT Dual Wall, Tee, 18"x18"x12"	1921	Tee, 18"x18"x12" - HDPE CPT Tee. Materials only.	Each	\$270.51	1	\$270.51
Screw gate, cast iron, 18" diameter, 10/0 head	1917	18" diameter cast iron screw (canal) gate rated at 10 seating head 0 feet unseating head. Materials only.	Each	\$1,021.26	1	\$1,021.26
<b>Mobilization</b>						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$434.63	2	\$869.26
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$227.64	2	\$455.28

**Practice: 436 - Irrigation Reservoir**

**Scenario: #2 - Embankment Dam with Off-Site Borrow, 3 ac ft Reservoir**

**Scenario Description:**

The reservoir, created by an embankment built across a natural depression, with an 18" diameter principal spillway through the embankment, is controlled by a canal-style gate. It will be built with approximately 4,500 cubic yards of material from off the site. It will be about 19.9 feet high and 200 feet long and hold approximately 1,000,000 gallons (3 Ac-Ft.). The top of berm will be 10 feet wide and the embankment side slopes will be 2.5 H to 1 V up and down stream.

Resource concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

**After Situation:**

This is an embankment, installed across a natural off-stream intermittent watercourse, used to store water for subsequent irrigation. It will be used to accumulate and store water for timely and efficient application of water through an irrigation system. The water source could be, a well, irrigation district pipeline, and/or a pump from a stream. It is designed to deliver water by gravity to an open ditch or non-pressurized pipeline, generally in excess of 5 cfs. All earthen materials will be from off-site sources.

**Scenario Feature Measure: Volume of Compacted Earthfill**

**Scenario Unit: Cubic Yards**

**Scenario Typical Size: 4,500**

**Scenario Cost: \$35,922.03**

**Scenario Cost/Unit: \$7.98**

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, common earth, large equipment, 1500 ft	1221	Bulk excavation of common earth including sand and gravel with scrapers with average haul distance of 1500 feet. Includes equipment and labor.	Cubic Yard	\$3.46	4500	\$15,570.00
Excavation, common earth, large equipment, 1500 ft	1221	Bulk excavation of common earth including sand and gravel with scrapers with average haul distance of 1500 feet. Includes equipment and labor.	Cubic Yard	\$3.46	4500	\$15,570.00
<b>Labor</b>						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.98	8	\$303.84
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.98	16	\$303.68
<b>Materials</b>						
Pipe, HDPE, CPT, Double Wall, Soil Tight, 12"	1244	Pipe, Corrugated HDPE Double Wall, 12" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$7.05	36	\$253.80
Coupling, HDPE CPT Dual Wall, Tee, 18"x18"x12"	1921	Tee, 18"x18"x12" - HDPE CPT Tee. Materials only.	Each	\$270.51	1	\$270.51
Screw gate, cast iron, 18" diameter, 10/0 head	1917	18" diameter cast iron screw (canal) gate rated at 10 seating head 0 feet unseating head. Materials only.	Each	\$1,021.26	1	\$1,021.26
Pipe, HDPE, CPT, Double Wall, Soil Tight, 18"	1245	Pipe, Corrugated HDPE Double Wall, 18" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$10.87	120	\$1,304.40
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$227.64	2	\$455.28
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$434.63	2	\$869.26

**Practice: 436 - Irrigation Reservoir**

**Scenario: #3 - Delta Embankment Reservoir**

**Scenario Description:**

This is a very large embankment reservoir with a 18" diameter drain pipe through the embankment controlled by a canal-type gate. It is designed to accumulate, store, and deliver water by gravity to an open ditch or non-pressurized pipeline, in excess of 5 cfs. It will have a top width of 12ft and centerline length of embankment of 5,280 feet. Average fill of 10 feet and the side slopes will be no steeper than 3 H to 1 V inside and out. It will be built with approximately 105,000 cubic yards of on-site material. It will have a maximum water depth of 8 feet with 2 feet of freeboard and no auxiliary spillway. Volume is approximately 320 ac-ft (104,500,000 gallons). Critical Area Planting and Mulching is required.

Resource Concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

**After Situation:**

The rectangular reservoir will be built on a relatively flat site and be used to accumulate and store water for timely application through an irrigation system. The water source could be a stream or an irrigation district canal.

**Scenario Feature Measure: Volume of Compacted Earthfill**

**Scenario Unit: Cubic Yards**

**Scenario Typical Size: 105,000**

**Scenario Cost: \$173,286.53**

**Scenario Cost/Unit: \$1.65**

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Scraper, pull, 15 CY	1207	Pull type earthmoving scraper with 15 CY capacity. Does not include pulling equipment or labor. Add Tractor or Dozer, 260 HP typically required for single scraper.	Hour	\$19.51	630	\$12,291.30
Tractor, agricultural, 360 HP	1205	Agricultural tractor with horsepower range of 340 to 390. Equipment and power unit costs. Labor not included.	Hour	\$130.82	630	\$82,416.60
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.76	12907	\$9,809.32
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$32.82		\$0.00
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	\$17.78	8	\$142.24
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$168.35	4	\$673.40
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$59.34	15	\$890.10
Scraper, pull, 18 CY	2093	Pull type earthmoving scraper with 18 CY capacity. Does not include pulling equipment or labor. Add Tractor or Dozer, 260 HP typically required for single scraper.	Hour	\$21.97	630	\$13,841.10
<b>Foregone Income</b>						
Fl, Rice	1974	Rice is Primary Crop	Acre	\$553.10	40	\$22,124.00
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.55	4	\$106.20
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.55	630	\$16,726.50
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.55	15	\$398.25

**Labor**

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.98	16	\$303.68
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.98	16	\$607.68
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$27.22	8	\$217.76

**Materials**

Catwalk, metal	1918	Metal pedestrian walk way giving access to the valve on a structure, typically 3' wide with railing. Materials only.	Foot	\$54.97	50	\$2,748.50
Screw gate, cast iron, 18" diameter, 10/0 head	1917	18" diameter cast iron screw (canal) gate rated at 10 seating head 0 feet unseating head. Materials only.	Each	\$1,021.26	1	\$1,021.26
Pipe, Steel, 18", Std Wt	1366	Materials: - 18" - Steel Std Wt	Foot	\$87.41	100	\$8,741.00

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$227.64	1	\$227.64
--------------------------------	------	---	------	----------	---	----------

**Practice: 436 - Irrigation Reservoir**

**Scenario: #4 - Delta Embankment Reservoir with Hauling**

**Scenario Description:**

This is a very large embankment reservoir with a 18" diameter drain pipe through the embankment controlled by a canal-type gate. It is designed to accumulate, store, and deliver water by gravity to an open ditch or non-pressurized pipeline, in excess of 5 cfs. It will have a top width of 12ft and centerline length of embankment of 5,280 feet. Average fill of 10 feet and the side slopes will be no steeper than 3 H to 1 V inside and out. It will be built with approximately 105,000 cubic yards of on-site material. It will have a maximum water depth of 8 feet with 2 feet of freeboard and no auxiliary spillway. Volume is approximately 320 ac-ft (104,500,000 gallons). Critical Area Planting and Mulching is required.

Resource Concern: Insufficient Water - Inefficient use of irrigation water.

Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

**After Situation:**

The rectangular reservoir will be built on a relatively flat site and be used to accumulate and store water for timely application through an irrigation system. The water source could be a stream or an irrigation district canal.

**Scenario Feature Measure: Volume of Compacted Earthfill**

**Scenario Unit: Cubic Yards**

**Scenario Typical Size: 105,000**

**Scenario Cost: \$203,802.17**

**Scenario Cost/Unit: \$1.94**

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Portable Welder	1407	Portable field welder. Equipment only. Labor not included.	Hour	\$17.78	8	\$142.24
Tractor, agricultural, 360 HP	1205	Agricultural tractor with horsepower range of 340 to 390. Equipment and power unit costs. Labor not included.	Hour	\$130.82	630	\$82,416.60
Scraper, pull, 15 CY	1207	Pull type earthmoving scraper with 15 CY capacity. Does not include pulling equipment or labor. Add Tractor or Dozer, 260 HP typically required for single scraper.	Hour	\$19.51	630	\$12,291.30
Stripping and stockpiling, topsoil	1199	Stripping and stockpiling of topsoil adjacent to stripping area. Includes equipment and labor.	Cubic Yard	\$0.76	12907	\$9,809.32
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$32.82	2	\$65.64
Hauling, bulk, highway truck	1615	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	\$0.29	105000	\$30,450.00
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$59.34	15	\$890.10
Scraper, pull, 18 CY	2093	Pull type earthmoving scraper with 18 CY capacity. Does not include pulling equipment or labor. Add Tractor or Dozer, 260 HP typically required for single scraper.	Hour	\$21.97	630	\$13,841.10
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$168.35	4	\$673.40
<b>Foregone Income</b>						
Fl, Rice	1974	Rice is Primary Crop	Acre	\$553.10	40	\$22,124.00
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.55	4	\$106.20

**Labor**

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.55	630	\$16,726.50
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$27.22	8	\$217.76
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.55	15	\$398.25
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.98	16	\$303.68
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.98	16	\$607.68

**Materials**

Catwalk, metal	1918	Metal pedestrian walk way giving access to the valve on a structure, typically 3' wide with railing. Materials only.	Foot	\$54.97	50	\$2,748.50
Screw gate, cast iron, 18" diameter, 10/0 head	1917	18" diameter cast iron screw (canal) gate rated at 10 seating head 0 feet unseating head. Materials only.	Each	\$1,021.26	1	\$1,021.26
Pipe, Steel, 18", Std Wt	1366	Materials: - 18" - Steel Std Wt	Foot	\$87.41	100	\$8,741.00

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$227.64	1	\$227.64
--------------------------------	------	---	------	----------	---	----------

**Practice: 436 - Irrigation Reservoir**

**Scenario: #5 - Reservoir Machine Compacted**

**Scenario Description:**

Due to the nature of the alluvial soils in the area, especially the high clay content soils, extra compaction is required to work the material into a proper density and to avoid macropores. This is an on-farm storage reservoir constructed from on-site borrow to construct levees above the natural grade. Water is pumped from on-farm drainage (storm runoff, irrigation return flows) into the structure. Typically, the runoff is temporarily stored in a adjacent tailwater channel. The levees are constructed with a 12 foot top and a 4 foot berm at full pool conditions to prevent wave action erosion. The levees are typically built 8 feet above ground with a two to three foot cut in the reservoir bottom. Typical size is 50,000 to 60,000 cu yds of earthfill. An auxiliary spillway is set at the berm elevation to prevent water level rises above the berm. Critical Area Planting and Mulching is required. 25 acres is typical size.

Resource Concern: Aquifer Overdraft, Excess nutrients in surface water.

Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current irrigation system relies on pumped groundwater from an aquifer that is being mined (aquifer overdraft). Farm runoff containing nutrients and sediments is not captured.

**After Situation:**

The on-farm storage reservoir will accumulate and store on-farm runoff during the winter and early spring for use as irrigation water during the growing season as irrigation water, reducing groundwater demand by 75%, reducing storm runoff from the farm by 50% and reducing nutrient delivery similarly.

**Scenario Feature Measure: Volume of Compacted Earthfill**

**Scenario Unit: Cubic Yards**

**Scenario Typical Size: 55,000**

**Scenario Cost: \$219,711.39**

**Scenario Cost/Unit: \$3.99**

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$3.54	55000	\$194,700.00
<b>Foregone Income</b>						
Fl, Rice	1974	Rice is Primary Crop	Acre	\$553.10	25	\$13,827.50
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.98	16	\$303.68
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.98	16	\$607.68
<b>Materials</b>						
Pipe, Steel, 18", Std Wt	1366	Materials: - 18" - Steel Std Wt	Foot	\$87.41	100	\$8,741.00
<b>Mobilization</b>						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$434.63	3	\$1,303.89
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$227.64	1	\$227.64

**Practice: 436 - Irrigation Reservoir**

**Scenario: #6 - Delta Tailwater Pit**

**Scenario Description:**

This is an excavated pit with a control structure. It is designed to accumulate, store, deliver or regulate water for a surface irrigation system. It will have a bottom width of 20 ft and length of 1,250 feet. The side slopes will be no steeper than 1.5 H to 1 V inside and out. It will be built with approximately 20,000 cubic yards of on-site material. It will have a maximum water depth of 10 feet with 1 feet of freeboard. Volume is approximately 12 ac-ft (3,950,303 gallons).

Resource concern: Insufficient Water - Inefficient use of irrigation water. 2.87 acre surface area.

Associated Practices: 521 - Pond Sealing or Lining (various); 320 - Irrigation Canal or Lateral; 430 - Irrigation Pipeline; 428 - Irrigation Ditch Lining; 533 - Pumping Plant; 440 series - Irrigation Systems; 447 - Irrigation System, Tailwater Recovery; 378 - Pond; 484 - Mulching; and 342 - Critical Area Planting.

**Before Situation:**

Current system relies on an intermittent or low-flow rate water source. This results in untimely and/or inefficient water application.

**After Situation:**

An excavated regulating reservoir will be built on a relatively flat site and be used to accumulate and store water for timely application through an irrigation system. The water source could be a stream or an irrigation district canal.

**Scenario Feature Measure:** Volume of Earth Excavated

**Scenario Unit:** Cubic Yards

**Scenario Typical Size:** 19,600

**Scenario Cost:** \$33,287.38

**Scenario Cost/Unit:** \$1.70

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Scraper, pull, 15 CY	1207	Pull type earthmoving scraper with 15 CY capacity. Does not include pulling equipment or labor. Add Tractor or Dozer, 260 HP typically required for single scraper.	Hour	\$19.51	260	\$5,072.60
Tractor, agricultural, 360 HP	1205	Agricultural tractor with horsepower range of 340 to 390. Equipment and power unit costs. Labor not included.	Hour	\$130.82	130	\$17,006.60
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$59.34	40	\$2,373.60
<b>Foregone Income</b>						
FI, Rice	1974	Rice is Primary Crop	Acre	\$553.10	2.87	\$1,587.40
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.98	40	\$759.20
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.55	170	\$4,513.50
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.98	40	\$1,519.20
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$227.64	2	\$455.28