

STATEMENT OF WORK
Contour Orchard and Other Fruit Area (331)
Michigan

These deliverables apply to this individual practice. For other planned practice deliverables, refer to those specific Statements of Work.

DESIGN**Deliverables:**

1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List all required and/or facilitating practices
 - c. Practice standard criteria-related computations and analyses to develop plans and specifications including, but not limited to:
 - i. Vegetative species and seeding rates
 - ii. Minimum/maximum row grade
 - iii. Critical slope length
 - iv. Erosion calculations using RUSLE 2 water erosion prediction
 - v. Outlet stability
 - vi. Buffer strips if needed and width
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describe the requirements to install the practice and obtain necessary permits.
3. Operation and maintenance plan.
4. Certification that the design meets practice standard criteria and complies with applicable laws and regulations.
5. Design modifications during installation as required.

INSTALLATION**Deliverables**

1. Pre-installation conference with client.
2. Verification that client has obtained required permits.
3. Installation guidance as needed.
4. Facilitate and implement required design modifications with client and original designer.
5. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
6. Certification that the installation process and materials meet design and permit requirements as required in electronic Field Office Technical Guide, Section IV, Contour Orchard and Other Fruit Area, Plans and Specifications subsection.

CHECK OUT**Deliverables**

1. Records of installation.
 - a. Actual row grade applied
 - b. Extent of practice units applied
 - c. Actual materials used
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits.
3. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard - Contour Orchard and Other Fruit Area-331
- NRCS National Agronomy Manual
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook