

STATEMENT OF WORK**Diversion (362)****Minnesota**

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06)
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Hydrology/Hydraulics
 - ii. Outlet capacity and stability
 - iii. Vegetation
 - iv. Environmental Considerations
2. Adequate plan view, profiles, cross sections, details, and specifications to ensure that the project can be properly constructed.
3. Operation and Maintenance Plan
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.03 (a) (3)).
5. Design modifications during installation as required.
6. Itemized Engineer's Cost Estimate

INSTALLATION

Deliverables

1. Documentation of pre-construction conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
 - a. Actual materials used
 - b. Inspection records
5. Facilitate required design or cost modifications with client, original designer, permitting and funding agencies.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
5. Certification that the installation process and materials meets design and permit requirements.

CHECK OUT

Deliverables

1. As-Built documentation.
 - a. Extent of practice units applied
 - b. Drawings
 - c. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03 (c) (1)).
3. Progress reporting.

STATEMENT OF WORK

Diversion (362)

Minnesota

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard - Diversion, 362
- NRCS National Engineering Manual (NEM).
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook