

STATEMENT OF WORK
Waste Facility Closure (360)
Missouri

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with other planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - Storm Water Pollution Prevention Plan (SWPPP) Land disturbance permit
 - c. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06)
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Geology and Soil Mechanics (NEM Subpart 531a)
 - ii. Hydrology/Hydraulics
 - iii. Structural
 - iv. Environmental Considerations
 - v. Vegetation
 - (See Critical Area Planting 342 Statement of Work)
 - vi. Safety Considerations (NEM Part 503-Safety, Subpart A, 503.10 through 503.12)
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits...
3. Design Report and Inspection Plan as appropriate (NEM Part 511, Subpart B Documentation, 511.11 and Part 512, Subpart D Quality Assurance Activities, 512.30 through 512.32).
4. Operation and Maintenance Plan
5. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.03 (a) (3)).
6. Design modifications during installation as required.

INSTALLATION

Deliverables

1. Pre activity conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Facilitate and implement required design modifications with client and original designer
5. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
6. Certification that the process and materials meets design and permit requirements.

STATEMENT OF WORK
Waste Facility Closure (360)
Missouri

CHECK OUT

Deliverables

1. As-Built documentation.
 - a. Extent of practice units applied
 - Survey of final site grading if required
 - Material Quantities
 - Vegetation establishment if required (See Critical Area Planting 342 Statement of Work)
 - b. Drawings
 - c. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03 (c) (1)).
3. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard - Waste Facility Closure, 360
- NRCS National Engineering Manual (NEM).
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook