

**Practice: 578 - Stream Crossing****Scenario: #4 - Rip Rap Crossing****Scenario Description:**

A stabilized area or structure constructed across a stream to provide a travel way for people, livestock, equipment, or vehicles. This practice applies to all land uses where an intermittent or perennial watercourse exists and a ford crossing is desired for livestock, people, and /or equipment. Stream bed in the channel reach containing the crossing must be vertically stable. Scenario is for stabilizing the bottom and slope of a stream channel using Rip Rap, gravel and geotextile. This scenario includes site preparation, dewatering, acquiring and installing rip rap and gravel on channel bottom and approaches. Scenario is based on a 20' wide x 50' long crossing. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Crossing dimensions

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 1,000

**Scenario Cost:** \$3,074.76

**Scenario Cost/Unit:** \$3.07

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.84	37	\$68.08
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$27.84	2	\$55.68
<b>Materials</b>						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$24.72	19	\$469.68
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$60.01	37	\$2,220.37
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.95	1	\$260.95

**Practice: 578 - Stream Crossing****Scenario: #5 - Concrete Crossing****Scenario Description:**

A stabilized area or structure constructed across a stream to provide a travel way for people, livestock, equipment, or vehicles. This practice applies to all land uses where an intermittent or perennial watercourse exists and a ford crossing is desired for livestock, people, and /or equipment. Stream bed in the channel reach containing the crossing must be vertically stable. Scenario is for stabilizing the bottom and slope of a stream channel using concrete. This scenario includes site preparation, dewatering, acquiring and installing gravel and concrete channel bottom and approaches. Scenario is based on a 20' wide x 50' long crossing. Use (396) Aquatic Organism Passage instead, when the primary intent is biological concerns, not hydrologic.

**Before Situation:**

Water flow could not cross access road or trail without erosion; or access road or trail could not cross channel.

**After Situation:**

Stream flow is not impeded and a stable base exists for equipment, people and/or animals to cross. Associated practices could be (342) Critical Area Planting, (560) Access Road, (575) Animal Trails and Walkways, (566) Recreational Trails and Walkways, (500) Obstruction Removal, or (584) Channel Stabilization.

**Scenario Feature Measure:** Crossing dimensions

**Scenario Unit:** Square Foot

**Scenario Typical Size:** 1,000

**Scenario Cost:** \$5,614.65

**Scenario Cost/Unit:** \$5.61

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.84	45	\$82.80
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$188.63	19	\$3,583.97
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$405.75	3	\$1,217.25
<b>Materials</b>						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$24.72	19	\$469.68
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$260.95	1	\$260.95