

Practice: 658 - Wetland Creation

Scenario: #1 - Excavated

Scenario Description: A wetland is created on a flat mineral upland at a location where surface runoff may be intercepted and ponded by excavation. Resource concerns are 22 - INDEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

Before Situation: The site is in cropland on an upland, non floodplain site (interfluve).

After Situation: An excavation with an average depth of 12" has created a shallow depression in a broad swale which intercepts surface runoff. The excavated material has been spread on adjacent areas. The INADEQUATE HABITAT FOR FISH AND WILDLIFE resource concern has been addressed with the provision of seasonal open water for terrestrial, aquatic, and waterfowl species.

Scenario Feature Measure: Acres of Wetland

Scenario Unit: Acre

Scenario Typical Size: 5

Total Scenario Cost: \$20,082.55

Scenario Cost/Unit: \$4,016.51

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.15	8067	\$17,334.22
--	----	---	------------	--------	------	-------------

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18
-------------------------------	------	--	------	----------	---	----------

Foregone Income

FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$453.83	2.5	\$1,134.57
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$446.23	2.5	\$1,115.58

Practice: 658 - Wetland Creation

Scenario: #2 - Embankment

Scenario Description: A wetland is created on a flat mineral upland at a location where surface runoff may be intercepted and ponded by excavation and with an embankment. Facilitating practices may include Structure for Water Control (587). Resource concerns are 22 - INEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

Before Situation: The site is in cropland on an upland, non floodplain site (interfluv).

After Situation: An excavation/embankment with an average depth of 12" has created a shallow depression in a broad swale which intercepts surface runoff. The excavated material has been spread on adjacent areas and used to compact the embankment. The INADEQUATE HABITAT FOR FISH AND WILDLIFE resource concern has been addressed with the provision of seasonal open water for terrestrial, aquatic, and waterfowl species.

Scenario Feature Measure: <Unknown>

Scenario Unit: Acre

Scenario Typical Size: 5

Total Scenario Cost: \$22,239.58

Scenario Cost/Unit: \$4,447.92

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$29.43	125	\$3,678.80
----------------------------	-----	---	------	---------	-----	------------

Equipment Installation

Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.50	125	\$15,812.45
---------------	-----	--	------	----------	-----	-------------

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.18	1	\$498.18
-------------------------------	------	--	------	----------	---	----------

Foregone Income

FI, Corn Dryland	1959	Dryland Corn is Primary Crop	Acre	\$453.83	2.5	\$1,134.57
FI, Soybeans Dryland	1961	Dryland Soybeans is Primary Crop	Acre	\$446.23	2.5	\$1,115.58