

Practice: 351 - Water Well Decommissioning**Scenario: #1 - Hand Dug****Scenario Description:**

A licensed well driller will seal and permanently close an inactive, abandoned, or unusable hand dug or shallow water well to prevent excess nutrients in surface and groundwater and to eliminate pesticides transported to surface and ground water. Well will be cleared of all equipment and materials. Residual water column must be treated with chlorine concentration of >50 ppm or according to local, State, Tribal, or Federal regulations.

Before Situation:

Hand dug or shallow well with a 30" diameter casing that is inactive, abandoned, or unusable.

After Situation:

Procedures and sealing materials shall conform to ASTM D5299 and be compatible with all local, State, Tribal, and Federal requirements. Backfill shall be placed and compacted in a manner that minimizes segregation and bulking to prevent surface subsidence. Typical well is hand dug. Associated practices: 342 Critical Area Seeding

Scenario Feature Measure: Length of well casing

Scenario Unit: Linear Feet

Scenario Typical Size: 20

Scenario Cost: \$1,242.93

Scenario Cost/Unit: \$62.15

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Grout pump	1334	Grout pump with tremie pipe. Equipment and power unit costs. Labor not included.	Hour	\$14.78	1	\$14.78
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$58.80	1	\$58.80
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.23	2.73	\$14.28
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$27.55	1	\$27.55
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$33.95	2	\$67.90
Materials						
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	\$2.79	1	\$2.79
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite grout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	\$788.35	1	\$788.35
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$268.48	1	\$268.48

Practice: 351 - Water Well Decommissioning**Scenario: #3 - Drilled ≤100 ft****Scenario Description:**

A licensed well driller will seal and permanently close an inactive, abandoned, or unusable water well to prevent excess nutrients in surface and groundwater and to eliminate pesticides transported to surface and ground water. Well will be cleared of all equipment and materials. Residual water column must be treated with chlorine concentration of >50 ppm or according to local, State, Tribal, or Federal regulations.

Before Situation:

Drilled well with a 6" diameter casing that is inactive, abandoned, or unusable.

After Situation:

Procedures and sealing materials shall conform to ASTM D5299 and be compatible with all local, State, Tribal, and Federal requirements. Backfill shall be placed and compacted in a manner that minimizes segregation and bulking to prevent surface subsidence. Typical length of well casing is 100 feet or less. Associated practices: 342 Critical Area Seeding

Scenario Feature Measure: Length of well casing

Scenario Unit: Each

Scenario Typical Size: 1

Scenario Cost: \$1,015.80

Scenario Cost/Unit: \$1,015.80

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Grout pump	1334	Grout pump with tremie pipe. Equipment and power unit costs. Labor not included.	Hour	\$14.78	1	\$14.78
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$58.80	1	\$58.80
Labor						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$33.95	2	\$67.90
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators ≥50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers ≥12", Dump Trucks, Ag Equipment ≥150 HP, Scrapers, Water Wagons.	Hour	\$27.55	1	\$27.55
Materials						
Grout, cement	1333	Cement grout meeting ASTM specifications for well sealing. Includes both neat-cement grout and bentonite grout mixtures. Includes materials, equipment and labor to place.	Cubic Yard	\$788.35	0.73	\$575.50
Chlorine	1335	Liquid chlorine bleach. Includes materials only.	Gallon	\$2.79	1	\$2.79
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$268.48	1	\$268.48