

**Practice: 587 - Structure for Water Control****Scenario: #1 - Inline Stoplog WCS, Surface Water Control, 6-10 in. dia. Pipe****Scenario Description:**

An Inline Water Control Structure (WCS) composed of plastic that maintains a desired water surface elevation, controls the direction or rate of flow, or conveys water to address the resource concern: Inadequate habitat for Fish and Wildlife. The water surface elevation is controlled by addition or removal of slats or "stoplogs". This scenario is applicable to variable crest weir structures where the elevation is controlled at point along a pipe extending through an embankment, providing ease of access to the structure and provide better protection against beaver activity. There are commercially available models composed of plastic that are commonly used when the width of the is 24" or less. Cost estimate is based on a using a such a commercial product. The typical scenario is an inline structure with a width of 12", height of six feet, The pipe is 65' of 8" SCH 40 PVC (inlet and outlet combined).

**Before Situation:**

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

**After Situation:**

A WCS is installed in a flow line allowing shallow water impoundments. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure:** Number of structures

**Scenario Unit:** Each

**Scenario Typical Size:** 1

**Scenario Cost:** \$2,683.86

**Scenario Cost/Unit:** \$2,683.86

**Cost Details (by category):**

| Component Name  | ID   | Component Description   | Unit              | Price (\$/unit) | Quantity | Cost     |
|---|------|---|-------------------|-----------------|----------|----------|
| <b>Equipment/Installation</b>                                   |      |   |                   |                 |          |          |
| Hydraulic Excavator, .5 CY                                      | 930  | Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.  | Hour              | \$58.80         | 2        | \$117.60 |
| Earthfill, Manually Compacted                                   | 50   | Earthfill, manually compacted, includes equipment and labor   | Cubic yard        | \$5.23          | 55       | \$287.65 |
| <b>Labor</b>  |      |   |                   |                 |          |          |
| Equipment Operators, Heavy                                      | 233  | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.   | Hour              | \$27.55         | 2        | \$55.10  |
| General Labor   | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.  | Hour              | \$22.31         | 8        | \$178.48 |
| <b>Materials</b>  |      |   |                   |                 |          |          |
| Pipe, PVC, 8", SCH 40   | 981  | Materials: - 8" - PVC - SCH 40 - ASTM D1785   | Foot              | \$9.72          | 65       | \$631.80 |
| Trash Guard, metal  | 1608 | Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport | Pound             | \$2.34          | 40       | \$93.60  |
| Steel, Plate, ½"  | 1047 | Flat Steel Plate, ½" thick, materials only.   | Square Foot       | \$4.65          | 36       | \$167.40 |
| Water Control Structure, Stoplog, Inline, fixed costs portion   | 2145 | Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.  | Each              | \$309.67        | 1        | \$309.67 |
| Water Control Structure, Stoplog, Inline, variable cost portion | 2146 | Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.                          | Height x Diameter | \$11.96         | 48       | \$574.08 |

**Mobilization**

**Mobilization**

|                                |      |   |      |          |   |          |
|--------------------------------|------|---|------|----------|---|----------|
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds. | Each | \$268.48 | 1 | \$268.48 |
|--------------------------------|------|---|------|----------|---|----------|

**Practice: 587 - Structure for Water Control****Scenario: #2 - Inline Stoplog WCS, Surface Water Control, 12-18 in. dia. Pipe****Scenario Description:**

An Inline Water Control Structure (WCS) composed of plastic that maintains a desired water surface elevation, controls the direction or rate of flow, or conveys water to address the resource concern: Inadequate habitat for Fish and Wildlife. The water surface elevation is controlled by addition or removal of slats or "stoplogs". This scenario is applicable to variable crest weir structures where the elevation is controlled at point along a pipe extending through an embankment, providing ease of access to the structure and provide better protection against beaver activity. There are commercially available models composed of plastic that are commonly used when the width of the is 24" or less. Cost estimate is based on a using a such a commercial product. The typical scenario is an inline structure with a width of 20", height of six feet, The pipe is 65' of 15" SDR35 PVC (inlet and outlet combined).

**Before Situation:**

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

**After Situation:**

A WCS is installed in a flow line allowing shallow water impoundments. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure: Number of Structures****Scenario Unit:** Each**Scenario Typical Size:** 1**Scenario Cost:** \$3,616.08**Scenario Cost/Unit:** \$3,616.08**Cost Details (by category):**

| Component Name  | ID   | Component Description   | Unit              | Price (\$/unit) | Quantity | Cost       |
|---|------|---|-------------------|-----------------|----------|------------|
| <b>Equipment/Installation</b>                                   |      |   |                   |                 |          |            |
| Hydraulic Excavator, .5 CY                                      | 930  | Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.  | Hour              | \$58.80         | 2        | \$117.60   |
| Earthfill, Manually Compacted                                   | 50   | Earthfill, manually compacted, includes equipment and labor   | Cubic yard        | \$5.23          | 55       | \$287.65   |
| <b>Labor</b>  |      |   |                   |                 |          |            |
| General Labor   | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.  | Hour              | \$22.31         | 8        | \$178.48   |
| Equipment Operators, Heavy                                      | 233  | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.   | Hour              | \$27.55         | 2        | \$55.10    |
| <b>Materials</b>  |      |   |                   |                 |          |            |
| Trash Guard, metal  | 1608 | Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport | Pound             | \$2.34          | 80       | \$187.20   |
| Water Control Structure, Stoplog, Inline, variable cost portion | 2146 | Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only.                          | Height x Diameter | \$11.96         | 90       | \$1,076.40 |
| Water Control Structure, Stoplog, Inline, fixed costs portion   | 2145 | Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.  | Each              | \$309.67        | 1        | \$309.67   |
| Pipe, PVC, 15", SDR 35  | 1722 | Materials: 15" - PVC - SDR35 - ASTM D3034   | Foot              | \$14.06         | 65       | \$913.90   |
| Steel, Plate, ½"  | 1047 | Flat Steel Plate, ½" thick, materials only.   | Square Foot       | \$4.65          | 36       | \$167.40   |

**Materials**

|                    |      |   |             |         |   |         |
|--------------------|------|---|-------------|---------|---|---------|
| Steel, Plate, 3/8" | 1375 | Flat steel plate, 3/8" thickness. Materials only. | Square Foot | \$13.55 | 4 | \$54.20 |
|--------------------|------|---|-------------|---------|---|---------|

**Mobilization**

|                                |      |   |      |          |   |          |
|--------------------------------|------|---|------|----------|---|----------|
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds. | Each | \$268.48 | 1 | \$268.48 |
|--------------------------------|------|---|------|----------|---|----------|

**Practice: 587 - Structure for Water Control****Scenario: #3 - Inline Stoplog WCS, Surface Water Control, >18 in. dia. Pipe****Scenario Description:**

An Inline Water Control Structure (WCS) composed of plastic that maintains a desired water surface elevation, controls the direction or rate of flow, or conveys water to address the resource concern: Inadequate habitat for Fish and Wildlife. The water surface elevation is controlled by addition or removal of slats or "stoplogs". This scenario is applicable to variable crest weir structures where the elevation is controlled at point along a pipe extending through an embankment, providing ease of access to the structure and provide better protection against beaver activity. There are commercially available models composed of plastic that are commonly used when the width of the is 24" or less. Cost estimate is based on a using a such a commercial product. The typical scenario is an inline structure with a width of 31", height of six feet, The pipe is 65' of 24" used steel (inlet and outlet combined).

**Before Situation:**

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

**After Situation:**

A WCS is installed in a flow line allowing shallow water impoundments. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure:** Number of structures

**Scenario Unit:** Each

**Scenario Typical Size:** 1

**Scenario Cost:** \$7,186.72

**Scenario Cost/Unit:** \$7,186.72

**Cost Details (by category):**

| Component Name  | ID   | Component Description  | Unit              | Price (\$/unit) | Quantity | Cost       |
|---|------|--|-------------------|-----------------|----------|------------|
| <b>Equipment/Installation</b>                                   |      |  |                   |                 |          |            |
| Earthfill, Manually Compacted                                   | 50   | Earthfill, manually compacted, includes equipment and labor  | Cubic yard        | \$5.23          | 55       | \$287.65   |
| Hydraulic Excavator, .5 CY                                      | 930  | Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.   | Hour              | \$58.80         | 2        | \$117.60   |
| <b>Labor</b>  |      |  |                   |                 |          |            |
| General Labor   | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.                                 | Hour              | \$22.31         | 8        | \$178.48   |
| Skilled Labor   | 230  | Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.  | Hour              | \$33.95         | 10       | \$339.50   |
| Equipment Operators, Heavy                                      | 233  | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.  | Hour              | \$27.55         | 2        | \$55.10    |
| <b>Materials</b>  |      |  |                   |                 |          |            |
| Water Control Structure, Stoplog, Inline, fixed costs portion   | 2145 | Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.   | Each              | \$309.67        | 1        | \$309.67   |
| Steel, Plate, 1/8"  | 1047 | Flat Steel Plate, 1/8" thick, materials only.  | Square Foot       | \$4.65          | 49       | \$227.85   |
| Water Control Structure, Stoplog, Inline, variable cost portion | 2146 | Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only. | Height x Diameter | \$11.96         | 144      | \$1,722.24 |
| Steel, Plate, 3/8"  | 1375 | Flat steel plate, 3/8" thickness. Materials only.  | Square Foot       | \$13.55         | 8        | \$108.40   |
| Pipe, Steel, 24", Std Wt, USED                                  | 1360 | Materials: - USED - 24" - Steel Std Wt   | Foot              | \$49.37         | 65       | \$3,209.05 |

**Materials**

|                    |      |   |       |        |     |          |
|--------------------|------|---|-------|--------|-----|----------|
| Trash Guard, metal | 1608 | Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport | Pound | \$2.34 | 155 | \$362.70 |
|--------------------|------|---|-------|--------|-----|----------|

**Mobilization**

|                                |      |   |      |          |   |          |
|--------------------------------|------|---|------|----------|---|----------|
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds. | Each | \$268.48 | 1 | \$268.48 |
|--------------------------------|------|---|------|----------|---|----------|

**Practice: 587 - Structure for Water Control****Scenario: #4 - Weir Box Inlet WCS, Surface Water Control, <=16 in. dia. Pipe.****Scenario Description:**

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A fabricated weir box structure with a pipe of 16" diameter or less is placed in a levee to manage water level elevation. Payment incorporates pipe, anti seep collar, trash guard, animal guard, flap gate and weir box structure.

**Before Situation:**

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

**After Situation:**

A weir box structure is placed in a levee to manage water level elevation. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure:** Number of structures

**Scenario Unit:** Each

**Scenario Typical Size:** 1

**Scenario Cost:** \$3,856.65

**Scenario Cost/Unit:** \$3,856.65

**Cost Details (by category):**

| Component Name                 | ID   | Component Description   | Unit        | Price (\$/unit) | Quantity | Cost       |
|--------------------------------|------|---|-------------|-----------------|----------|------------|
| <b>Equipment/Installation</b>  |      |   |             |                 |          |            |
| Hydraulic Excavator, .5 CY     | 930  | Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.  | Hour        | \$58.80         | 2        | \$117.60   |
| Earthfill, Manually Compacted  | 50   | Earthfill, manually compacted, includes equipment and labor   | Cubic yard  | \$5.23          | 55       | \$287.65   |
| <b>Labor</b>                   |      |   |             |                 |          |            |
| Equipment Operators, Heavy     | 233  | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.   | Hour        | \$27.55         | 2        | \$55.10    |
| Skilled Labor                  | 230  | Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.   | Hour        | \$33.95         | 8        | \$271.60   |
| General Labor                  | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.  | Hour        | \$22.31         | 8        | \$178.48   |
| <b>Materials</b>               |      |   |             |                 |          |            |
| Trash Guard, metal             | 1608 | Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport | Pound       | \$2.34          | 82       | \$191.88   |
| Steel, Angle, 3" x 3" x 1/4"   | 1372 | Materials: Angle, 3" x 3" x 1/4", Meets ASTM A36  | Foot        | \$3.42          | 30       | \$102.60   |
| Steel, Plate, 3/8"             | 1375 | Flat steel plate, 3/8" thickness. Materials only.   | Square Foot | \$13.55         | 4        | \$54.20    |
| Pipe, Steel, 16", Std Wt, USED | 1357 | Materials: - USED - 16" - Steel Std Wt  | Foot        | \$28.89         | 65       | \$1,877.85 |
| Steel, Plate, 1/2"             | 1047 | Flat Steel Plate, 1/2" thick, materials only.   | Square Foot | \$4.65          | 49       | \$227.85   |
| Steel, Plate, 3/16"            | 1048 | Flat Steel Plate, 3/16" thick, materials only.  | Square Foot | \$6.98          | 32       | \$223.36   |
| <b>Mobilization</b>            |      |   |             |                 |          |            |
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.   | Each        | \$268.48        | 1        | \$268.48   |

**Practice: 587 - Structure for Water Control****Scenario: #5 - Weir Box Inlet WCS, Surface Water Control, >16 in. dia. Pipe.****Scenario Description:**

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A fabricated weir box structure with a pipe of greater than 16" diameter is placed in a levee to manage water level elevation. Payment incorporates pipe, anti seep collar, trash guard, animal guard, flap gate and weir box structure.

**Before Situation:**

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

**After Situation:**

A weir box structure is placed in a levee to manage water level elevation. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure:** Number of structures

**Scenario Unit:** Each

**Scenario Typical Size:** 1

**Scenario Cost:** \$5,386.37

**Scenario Cost/Unit:** \$5,386.37

**Cost Details (by category):**

| Component Name                 | ID   | Component Description   | Unit        | Price (\$/unit) | Quantity | Cost       |
|--------------------------------|------|---|-------------|-----------------|----------|------------|
| <b>Equipment/Installation</b>  |      |   |             |                 |          |            |
| Earthfill, Manually Compacted  | 50   | Earthfill, manually compacted, includes equipment and labor   | Cubic yard  | \$5.23          | 55       | \$287.65   |
| Hydraulic Excavator, .5 CY     | 930  | Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.  | Hour        | \$58.80         | 2        | \$117.60   |
| <b>Labor</b>                   |      |   |             |                 |          |            |
| Equipment Operators, Heavy     | 233  | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.   | Hour        | \$27.55         | 2        | \$55.10    |
| General Labor                  | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.  | Hour        | \$22.31         | 8        | \$178.48   |
| Skilled Labor                  | 230  | Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.   | Hour        | \$33.95         | 9        | \$305.55   |
| <b>Materials</b>               |      |   |             |                 |          |            |
| Steel, Plate, 3/16"            | 1048 | Flat Steel Plate, 3/16" thick, materials only.  | Square Foot | \$6.98          | 32       | \$223.36   |
| Steel, Plate, 1/8"             | 1047 | Flat Steel Plate, 1/8" thick, materials only.   | Square Foot | \$4.65          | 36       | \$167.40   |
| Pipe, Steel, 24", Std Wt, USED | 1360 | Materials: - USED - 24" - Steel Std Wt  | Foot        | \$49.37         | 65       | \$3,209.05 |
| Steel, Plate, 3/8"             | 1375 | Flat steel plate, 3/8" thickness. Materials only.   | Square Foot | \$13.55         | 8        | \$108.40   |
| Trash Guard, metal             | 1608 | Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport | Pound       | \$2.34          | 155      | \$362.70   |
| Steel, Angle, 3" x 3" x 1/4"   | 1372 | Materials: Angle, 3" x 3" x 1/4", Meets ASTM A36  | Foot        | \$3.42          | 30       | \$102.60   |
| <b>Mobilization</b>            |      |   |             |                 |          |            |
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.   | Each        | \$268.48        | 1        | \$268.48   |



**Practice: 587 - Structure for Water Control****Scenario: #6 - Weir Box Inlet WCS, Surface Water Control Using Existing Pipe (Box Only)****Scenario Description:**

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A fabricated weir box structure is installed on existing piping.

**Before Situation:**

The landowner wishes to provide for a way to control the water surface elevation in a wetland area. The landowner wishes to enhance and enlarge the area to provide habitat for fish and wildlife.

**After Situation:**

A weir box structure is placed in a levee over an existing subsurface system to manage water level elevation. A wetland area is enhanced and water levels can be varied to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure:** Number of structures

**Scenario Unit:** Each

**Scenario Typical Size:** 1

**Scenario Cost:** \$584.44

**Scenario Cost/Unit:** \$584.44

**Cost Details (by category):**

| Component Name                | ID   | Component Description  | Unit        | Price (\$/unit) | Quantity | Cost     |
|-------------------------------|------|--|-------------|-----------------|----------|----------|
| <b>Equipment/Installation</b> |      |  |             |                 |          |          |
| Truck, Pickup                 | 939  | Equipment and power unit costs. Labor not included.  | Hour        | \$39.03         | 2        | \$78.06  |
| <b>Labor</b>                  |      |  |             |                 |          |          |
| Skilled Labor                 | 230  | Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.                | Hour        | \$33.95         | 4        | \$135.80 |
| General Labor                 | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. | Hour        | \$22.31         | 2        | \$44.62  |
| <b>Materials</b>              |      |  |             |                 |          |          |
| Steel, Plate, 3/16"           | 1048 | Flat Steel Plate, 3/16" thick, materials only.   | Square Foot | \$6.98          | 32       | \$223.36 |
| Steel, Angle, 3" x 3" x 1/4"  | 1372 | Materials: Angle, 3" x 3" x 1/4", Meets ASTM A36   | Foot        | \$3.42          | 30       | \$102.60 |

**Practice: 587 - Structure for Water Control****Scenario: #7 - Watertight Flapgate Inflow WCS, Surface Water Control, <=15 in. dia. Pipe****Scenario Description:**

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A Flap/Slide Gate with a pipe of 15" diameter or less is placed in a levee to manage water level elevation. Payment incorporates pipe, anti seep collar, trash guard, animal guard, and flap gate.

**Before Situation:**

A wetland or other area is in need of a flap gate to control the flow of water through a pipe to provide habitat for fish and wildlife. The landowner wishes to provide a way for water to flow into a managed wetland pool yet automatically prevent flow from leaving the pool when the water source inflow head becomes less than the pool head.

**After Situation:**

A WCS pipe with flap gate 15" or less in diameter is installed. The pipe is installed through a water management embankment allowing shallow water impoundments to take on water from a higher elevation such as floodwater. When the surface of the inflow water source drops to an elevation that is lower than the wetland pool water surface, the flap gate automatically closes, preventing the loss of water from the wetland area. A wetland area is enhanced by having the ability to automatically fill with water when the hydrologic opportunity presents itself to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure:** Number of structures

**Scenario Unit:** Each

**Scenario Typical Size:** 1

**Scenario Cost:** \$2,577.93

**Scenario Cost/Unit:** \$2,577.93

**Cost Details (by category):**

| Component Name                 | ID   | Component Description   | Unit        | Price (\$/unit) | Quantity | Cost     |
|--------------------------------|------|---|-------------|-----------------|----------|----------|
| <b>Equipment/Installation</b>  |      |   |             |                 |          |          |
| Backhoe, 80 HP                 | 926  | Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.  | Hour        | \$58.80         | 6        | \$352.80 |
| <b>Labor</b>                   |      |   |             |                 |          |          |
| General Labor                  | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.  | Hour        | \$22.31         | 12       | \$267.72 |
| Skilled Labor                  | 230  | Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.   | Hour        | \$33.95         | 4        | \$135.80 |
| Equipment Operators, Heavy     | 233  | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.   | Hour        | \$27.55         | 6        | \$165.30 |
| <b>Materials</b>               |      |   |             |                 |          |          |
| Pipe, PVC, 15", SDR 35         | 1722 | Materials: 15" - PVC - SDR35 - ASTM D3034   | Foot        | \$14.06         | 65       | \$913.90 |
| Steel, Plate, 3/8"             | 1375 | Flat steel plate, 3/8" thickness. Materials only.   | Square Foot | \$13.55         | 4        | \$54.20  |
| Trash Guard, metal             | 1608 | Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport | Pound       | \$2.34          | 82       | \$191.88 |
| Steel, Plate, 1/8"             | 1047 | Flat Steel Plate, 1/8" thick, materials only.   | Square Foot | \$4.65          | 49       | \$227.85 |
| <b>Mobilization</b>            |      |   |             |                 |          |          |
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.   | Each        | \$268.48        | 1        | \$268.48 |

**Practice: 587 - Structure for Water Control****Scenario: #8 - Watertight Flapgate Inflow WCS, Surface Water Control, >15 in. dia. Pipe****Scenario Description:**

A structure in a water management system that conveys water, controls the direction or rate of flow, maintains a desired water surface elevation or measures water. This practice applies wherever a permanent structure is needed as an integral part of a water-control system. A Flap/Slide Gate with a pipe of greater than 15" diameter is placed in a levee to manage water level elevation. Payment incorporates pipe, anti seep collar, trash guard, animal guard, and flap gate.

**Before Situation:**

A wetland or other area is in need of a flap gate to control the flow of water through a pipe to provide habitat for fish and wildlife. The landowner wishes to provide a way for water to flow into a managed wetland pool yet automatically prevent flow from leaving the pool when the water source inflow head becomes less than the pool head.

**After Situation:**

A WCS pipe with flap gate greater than 15" in diameter is installed. The pipe is installed through a water management embankment allowing shallow water impoundments to take on water from a higher elevation such as floodwater. When the surface of the inflow water source drops to an elevation that is lower than the wetland pool water surface, the flap gate automatically closes, preventing the loss of water from the wetland area. A wetland area is enhanced by having the ability to automatically fill with water when the hydrologic opportunity presents itself to better accommodate wildlife needs. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure:** Number of structures

**Scenario Unit:** Each

**Scenario Typical Size:** 1

**Scenario Cost:** \$4,076.45

**Scenario Cost/Unit:** \$4,076.45

**Cost Details (by category):**

| Component Name                 | ID   | Component Description   | Unit        | Price (\$/unit) | Quantity | Cost       |
|--------------------------------|------|---|-------------|-----------------|----------|------------|
| <b>Equipment/Installation</b>  |      |   |             |                 |          |            |
| Backhoe, 80 HP                 | 926  | Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.  | Hour        | \$58.80         | 6        | \$352.80   |
| <b>Labor</b>                   |      |   |             |                 |          |            |
| General Labor                  | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.  | Hour        | \$22.31         | 12       | \$267.72   |
| Skilled Labor                  | 230  | Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.   | Hour        | \$33.95         | 5        | \$169.75   |
| Equipment Operators, Heavy     | 233  | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.   | Hour        | \$27.55         | 6        | \$165.30   |
| <b>Materials</b>               |      |   |             |                 |          |            |
| Steel, Plate, 3/8"             | 1375 | Flat steel plate, 3/8" thickness. Materials only.   | Square Foot | \$13.55         | 8        | \$108.40   |
| Trash Guard, metal             | 1608 | Trash Guard, fabricated-steel, includes materials, equipment, and labor to transport and place Conical shaped trash guard for drop inlet spillway. Typically fabricated of CMP and steel. Includes materials, equipment, and labor to fabricate and transport | Pound       | \$2.34          | 155      | \$362.70   |
| Pipe, PVC, 24", PS 46          | 1254 | Pipe, PVC, PS 46, 24" Diameter - ASTM F679. Material cost only.   | Each        | \$33.13         | 65       | \$2,153.45 |
| Steel, Plate, 1/8"             | 1047 | Flat Steel Plate, 1/8" thick, materials only.   | Square Foot | \$4.65          | 49       | \$227.85   |
| <b>Mobilization</b>            |      |   |             |                 |          |            |
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.   | Each        | \$268.48        | 1        | \$268.48   |

**Practice: 587 - Structure for Water Control****Scenario: #9 - Inline WCS, Subsurface Drainage Control, <=10 in. dia. Pipe****Scenario Description:**

A subsurface drainage system on a field with a fairly flat slope (less than 2% and preferably less than 1%) outlets through a control structure which is operated with stoplogs. This allows the operator to keep the water in the soil profile when it is not critical to dry the soil. This retention time allows nutrients to be reduced by bacteria such that the nutrients do not leave with the water. A single stoplog structure may have its influence extended by buried float-activated structures which can be counted as structures also for a separate payment.

Resource Concerns: Water Quality Degradation (Nutrients). Associated Practices: 606 - Subsurface Drain; 554 - Drainage Water Management

**Before Situation:**

The discharge from a subsurface drainage system enters ditches or streams, often laden with sediment and nutrients.

**After Situation:**

The discharge from a subsurface drainage system enters ditches or streams only when the soil profile needs to be dry. The retention time in the soil profile removes nutrients. Typical affected area for a single structure is 10-20 acres. A single structure with stoplogs may have its influence extended by use of buried float-activated control structures, which may be paid for as separate structures also.

**Scenario Feature Measure: Number of Structures****Scenario Unit: Each****Scenario Typical Size: 1****Scenario Cost: \$1,663.53****Scenario Cost/Unit: \$1,663.53****Cost Details (by category):**

| Component Name  | ID   | Component Description  | Unit              | Price (\$/unit) | Quantity | Cost     |
|---|------|--|-------------------|-----------------|----------|----------|
| <b>Equipment/Installation</b>                                   |      |  |                   |                 |          |          |
| Backhoe, 80 HP  | 926  | Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.   | Hour              | \$58.80         | 3        | \$176.40 |
| <b>Labor</b>  |      |  |                   |                 |          |          |
| Supervisor or Manager   | 234  | Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.   | Hour              | \$36.46         | 3        | \$109.38 |
| General Labor   | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.                                 | Hour              | \$22.31         | 2        | \$44.62  |
| <b>Materials</b>  |      |  |                   |                 |          |          |
| Water Control Structure, Stoplog, Inline, fixed costs portion   | 2145 | Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.   | Each              | \$309.67        | 1        | \$309.67 |
| Water Control Structure, Stoplog, Inline, variable cost portion | 2146 | Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only. | Height x Diameter | \$11.96         | 48       | \$574.08 |
| Pipe, PVC, 8", SDR 35   | 994  | Materials: - 8" - PVC - SDR 35 - ASTM D3034  | Foot              | \$6.72          | 40       | \$268.80 |
| <b>Mobilization</b>   |      |  |                   |                 |          |          |
| Mobilization, small equipment                                   | 1138 | Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.   | Each              | \$180.58        | 1        | \$180.58 |

**Practice: 587 - Structure for Water Control****Scenario: #10 - Inline WCS, Subsurface Drainage Control, >10 in. dia. Pipe****Scenario Description:**

A subsurface drainage system on a field with a fairly flat slope (less than 2% and preferably less than 1%) outlets through a control structure which is operated with stoplogs. This allows the operator to keep the water in the soil profile when it is not critical to dry the soil. This retention time allows nutrients to be reduced by bacteria such that the nutrients do not leave with the water. A single stoplog structure may have its influence extended by buried float-activated structures which can be counted as structures also for a separate payment.

Resource Concerns: Water Quality Degradation (Nutrients). Associated Practices: 606 - Subsurface Drain; 554 - Drainage Water Management

**Before Situation:**

The discharge from a subsurface drainage system enters ditches or streams, often laden with sediment and nutrients.

**After Situation:**

The discharge from a subsurface drainage system enters ditches or streams only when the soil profile needs to be dry. The retention time in the soil profile removes nutrients. Typical affected area for a single structure is 10-20 acres. A single structure with stoplogs may have its influence extended by use of buried float-activated control structures, which may be paid for as separate structures also.

**Scenario Feature Measure: Number of Structures**

**Scenario Unit:** Each

**Scenario Typical Size:** 1

**Scenario Cost:** \$2,244.17

**Scenario Cost/Unit:** \$2,244.17

**Cost Details (by category):**

| Component Name  | ID   | Component Description  | Unit              | Price (\$/unit) | Quantity | Cost     |
|---|------|--|-------------------|-----------------|----------|----------|
| <b>Equipment/Installation</b>                                   |      |  |                   |                 |          |          |
| Backhoe, 80 HP  | 926  | Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.   | Hour              | \$58.80         | 3        | \$176.40 |
| <b>Labor</b>  |      |  |                   |                 |          |          |
| Supervisor or Manager   | 234  | Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.   | Hour              | \$36.46         | 3        | \$109.38 |
| General Labor   | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.                                 | Hour              | \$22.31         | 2        | \$44.62  |
| <b>Materials</b>  |      |  |                   |                 |          |          |
| Water Control Structure, Stoplog, Inline, variable cost portion | 2146 | Variable cost portion of a Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Calculate total variable costs by multiplying by the structure height x pipe diameter. Materials only. | Height x Diameter | \$11.96         | 72       | \$861.12 |
| Water Control Structure, Stoplog, Inline, fixed costs portion   | 2145 | Fixed cost portion of Water Level Control Structure, Inline stoplog type. Typically made of PVC or fiberglass materials. Fixed cost portion. Materials only.   | Each              | \$309.67        | 1        | \$309.67 |
| Pipe, PVC, dia. < 18", weight priced                            | 1323 | Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.  | Pound             | \$1.48          | 380      | \$562.40 |
| <b>Mobilization</b>   |      |  |                   |                 |          |          |
| Mobilization, small equipment                                   | 1138 | Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.   | Each              | \$180.58        | 1        | \$180.58 |

**Practice: 587 - Structure for Water Control****Scenario: #12 - Straight Pipe, Surface Water Control, <=10 in. dia. Pipe (w/o adjustable control)****Scenario Description:**

Used as an outlet for Wetland; no drop box; straight through 10" diameter PVC pipe; pipe is backfilled with #57 stone to 1' over the top of the pipe; 12" thick layer of Type D riprap is placed at the outlet end with 6" thick of #57 stone under it.

**Before Situation:**

The landowner wishes to establish a wetland area to provide habitat for fish and wildlife.

**After Situation:**

A straight pipe (principal spillway) is installed through an earth embankment to create a wetland. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure:** Feet of pipe installed

**Scenario Unit:** Foot

**Scenario Typical Size:** 30

**Scenario Cost:** \$1,294.49

**Scenario Cost/Unit:** \$43.15

**Cost Details (by category):**

| Component Name                              | ID   | Component Description  | Unit       | Price (\$/unit) | Quantity | Cost     |
|---|------|--|------------|-----------------|----------|----------|
| <b>Equipment/Installation</b>               |      |  |            |                 |          |          |
| Backhoe, 80 HP                              | 926  | Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.   | Hour       | \$58.80         | 5        | \$294.00 |
| <b>Labor</b>                                |      |  |            |                 |          |          |
| General Labor                               | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. | Hour       | \$22.31         | 5        | \$111.55 |
| Equipment Operators, Heavy                  | 233  | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.                                | Hour       | \$27.55         | 5        | \$137.75 |
| <b>Materials</b>                            |      |  |            |                 |          |          |
| Aggregate, Gravel, Graded                   | 46   | Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.   | Cubic yard | \$25.33         | 5        | \$126.65 |
| Pipe, PVC, 10", SDR 35                      | 1251 | Pipe, PVC, SDR 35, 10" Diameter - ASTM D3034. Material cost only.  | Foot       | \$10.52         | 30       | \$315.60 |
| Rock Riprap, graded, angular, material only | 2131 | Graded Rock Riprap for 12" to 24" size ranges. Includes material costs only. Shipping not included.  | Ton        | \$20.23         | 2        | \$40.46  |
| <b>Mobilization</b>                         |      |  |            |                 |          |          |
| Mobilization, medium equipment              | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.  | Each       | \$268.48        | 1        | \$268.48 |

**Practice: 587 - Structure for Water Control****Scenario: #13 - Straight Pipe, Surface Water Control, >=12 in. dia. Pipe (w/o adjustable control)****Scenario Description:**

Used as an outlet for Wetland; no drop box; straight through 12" diameter PVC pipe; pipe is backfilled with #57 stone to 1' over the top of the pipe; 12" thick layer of Type D riprap is placed at the outlet end with 6" thick of #57 stone under it.

**Before Situation:**

The landowner wishes to establish a wetland area to provide habitat for fish and wildlife.

**After Situation:**

A straight pipe (principal spillway) is installed through an earth embankment to create a wetland. Any needed re-vegetation of disturbed areas use Critical Area Planting (342). Other associated practices such as; Wetland Creation (658), Wetland Enhancement (659) Wetland Wildlife Habitat Management (644), Dike (356), and Grade Stabilization Structure (410) will use the corresponding Standard(s) as appropriate.

**Scenario Feature Measure:** Feet of pipe installed

**Scenario Unit:** Foot

**Scenario Typical Size:** 30

**Scenario Cost:** \$1,528.14

**Scenario Cost/Unit:** \$50.94

**Cost Details (by category):**

| Component Name                              | ID   | Component Description  | Unit       | Price (\$/unit) | Quantity | Cost     |
|---|------|--|------------|-----------------|----------|----------|
| <b>Equipment/Installation</b>               |      |  |            |                 |          |          |
| Backhoe, 80 HP                              | 926  | Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.   | Hour       | \$58.80         | 5        | \$294.00 |
| <b>Labor</b>                                |      |  |            |                 |          |          |
| Equipment Operators, Heavy                  | 233  | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.                                | Hour       | \$27.55         | 5        | \$137.75 |
| General Labor                               | 231  | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. | Hour       | \$22.31         | 5        | \$111.55 |
| <b>Materials</b>                            |      |  |            |                 |          |          |
| Aggregate, Gravel, Graded                   | 46   | Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.   | Cubic yard | \$25.33         | 6        | \$151.98 |
| Rock Riprap, graded, angular, material only | 2131 | Graded Rock Riprap for 12" to 24" size ranges. Includes material costs only. Shipping not included.  | Ton        | \$20.23         | 2        | \$40.46  |
| Pipe, PVC, dia. < 18", weight priced        | 1323 | Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.  | Pound      | \$1.48          | 354      | \$523.92 |
| <b>Mobilization</b>                         |      |  |            |                 |          |          |
| Mobilization, medium equipment              | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.  | Each       | \$268.48        | 1        | \$268.48 |