

Practice: 634 - Waste Transfer

Scenario: #2 - Wastewater catch basin, less than 1000 gal.

Scenario Description:

Installation of a wastewater collection system that includes materials and structures to collect liquids of a design volume less than 1000 gallons such as silage leachate, lot runoff and other contaminated liquid effluent. This may include curbs, screens, precast manholes, sumps or catch basins. The wastewater will be transferred from the collection basin to a waste storage facility. Payment includes excavation, placement of bedding as needed, placement of structure and backfill with construction of concrete inlet collection area. Transfer pump if needed must be contracted under associated practice 533 Pumping Plant.

This scenario addresses the potential for surface water and groundwater quality degradation from liquid wastewater running unchecked out of silage bunkers and off of animal feeding lots.

Before Situation:

Inadequate waste management system able to collect wastewater from an operation that may contaminate surface or groundwater resources.

After Situation:

This practice scenario is suitable where the estimated design volume for wastewater transfer is less than 1000 gallons of contaminated liquid that may flow from silage bunkers or animal production facilities. The practice scenario typically includes materials and installation of flat and formed concrete for curbs and/or gutters to collect liquids. With the installation of a precast manhole with lid or catch basin with grate.

Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling.

Scenario Feature Measure: Collection volume installed

Scenario Unit: Gallon

Scenario Typical Size: 1,000

Scenario Cost: \$5,506.01

Scenario Cost/Unit: \$5.51

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Demolition, concrete	1498	Demolition and disposal of reinforced concrete structures including slabs and walls. Includes labor and equipment.	Cubic Yard	\$16.56	2	\$33.12
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$57.34	4	\$229.36
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$70.57	4	\$282.28
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$58.80	8	\$470.40
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$417.46	2	\$834.92
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$132.13	4	\$528.52
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$27.55	12	\$330.60
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$20.89	4	\$83.56

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.31	8	\$178.48
---------------	-----	--	------	---------	---	----------

Materials

Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$17.46	5	\$87.30
Catch Basin, concrete, 60" dia.	1754	Precast 60-in diameter catch basin, 6' deep, with collar and grate cover. Materials only.	Each	\$1,998.41	1	\$1,998.41

Mobilization

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$180.58	1	\$180.58
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$268.48	1	\$268.48

Practice: 634 - Waste Transfer

Scenario: #4 - Concrete Channel, no footers

Scenario Description:

Installation of a concrete channel that consists of a slab with curb for the entire length of the channel to enable the facility manager to direct liquid waste to a collection basin and/or waste storage facility.

Water quality concerns will be addressed by preventing liquid waste from entering surface waters, and to facilitate timely land application of manure and wastewater at agronomic rates according to the CNMP. This scenario addresses the potential for surface water and groundwater quality degradation.

Before Situation:

Current facility operations are allowing liquid waste to flow uncontrolled during periods of precipitation events or cleaning operations such that water resources can be contaminated.

After Situation:

Typical installation of a 12 foot wide 100' long concrete channel that consists of a 5" thick concrete slab with curbing on each side of the slab that is 2' high, 6" thick for the entire length. The purpose is to transfer liquids or manure slurry from one area to a collection basin or waste storage facility.

Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling.

Scenario Feature Measure: Bottom surface area of concrete channel

Scenario Unit: Square Foot

Scenario Typical Size: 1,200

Scenario Cost: \$7,775.01

Scenario Cost/Unit: \$6.48

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$70.57	8	\$564.56
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$132.13	19	\$2,510.47
Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$417.46	9	\$3,757.14
Labor						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$27.55	8	\$220.40
Materials						
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$17.46	26	\$453.96
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$268.48	1	\$268.48

Practice: 634 - Waste Transfer

Scenario: #8 - Manure Flush System

Scenario Description:

Installation of a manure flush system consisting of a flushwater storage tank, flushing mechanism such as a valve, and flush water distribution. This practice scenario is suitable only where the water or wastewater supplies are available for operating a flush system to collect the animal waste deposited on the concrete surfaces. Payment includes tank, valve and distribution pipeline, site prep and concrete to support these structures.

This scenario addresses the potential for surface water and groundwater quality degradation from animal waste.

Before Situation:

An animal production facility does not have an efficient method for collecting and transferring the animal waste produced. A source of sufficient water or wastewater resources are available to design a flush system to clean the production floor and collect the waste materials deposited.

After Situation:

The design flush volume for the flush system is less than 1000 gallons. Concrete slab to support the tank and distribution pipeline is 28ft x 12 ft x 5" thick. with 40 ft of above ground 8" pipe is used for distribution.

Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling.

Scenario Feature Measure: 1000 Gallons of flush water

Scenario Unit: Gallon

Scenario Typical Size: 1,000

Scenario Cost: \$4,950.08

Scenario Cost/Unit: \$4.95

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Demolition, concrete	1498	Demolition and disposal of reinforced concrete structures including slabs and walls. Includes labor and equipment.	Cubic Yard	\$16.56	4	\$66.24
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$58.80	8	\$470.40
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$132.13	5	\$660.65
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$20.89	8	\$167.12
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.31	16	\$356.96
Materials						
Pipe, PVC, 8", SCH 40	981	Materials: - 8" - PVC - SCH 40 - ASTM D1785	Foot	\$9.72	40	\$388.80
Plug Valve, 8"	2101	8" diameter plug valve. Materials only.	Each	\$1,681.43	1	\$1,681.43
Tank, Poly enclosed Storage, 300-1000 gal	1074	Water storage tanks. Includes materials and shipping only.	Gallon	\$0.89	1000	\$890.00
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$268.48	1	\$268.48

Practice: 634 - Waste Transfer

Scenario: #9 - Wastewater Recycle System for Flush System, Pipes only

Scenario Description:

Installation of a wastewater recycle pipeline utilized with manure and wastewater flush system using recycled wastewater. Scenario is for the pipe system only to retrofit flush systems to utilize recycled water. Payment includes excavation, placement of bedding as needed, conveyance pipelines with valves and pipe backfill to transport water to the flush tank.

This scenario addresses the potential for surface water and groundwater quality degradation from animal waste.

Before Situation:

An animal production facility does not have an efficient method for collecting and transferring the animal waste produced. Wastewater however is available in a sufficient quantity to provide a flush cycle to clean the production floor and collect the waste materials deposited.

After Situation:

Supplemental piping is needed to install the recycled flush water as a means to collect the animal waste deposited on the concrete production surfaces. The pipe design for the flush volume requires 300 feet of 3 inch diameter pipe for pressure flow.

Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling.

Scenario Feature Measure: Flush - pipes

Scenario Unit: Feet

Scenario Typical Size: 300

Scenario Cost: \$2,808.34

Scenario Cost/Unit: \$9.36

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$58.80	12	\$705.60
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.26	300	\$378.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.31	8	\$178.48
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$20.89	12	\$250.68
Materials						
Pipe, PVC, 3", SCH 40	977	Materials: - 3" - PVC - SCH 40 - ASTM D1785	Foot	\$2.80	300	\$840.00
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$25.00	11	\$275.00
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$180.58	1	\$180.58

Practice: 634 - Waste Transfer

Scenario: #10 - 8 inch PVC pipeline, gravity or low pressure flow

Scenario Description:

Gravity or low pressure flow pipeline used to transfer manure or wastewater according to the CNMP. Payment includes the pipe plus clean-out risers and fittings, trench excavation and backfill, labor and equipment for installation. Typical installation applies to soils with no special bedding requirements.

This scenario addresses the transport of liquid waste to a waste storage or treatment facility to prevent a water quality resource concern of excessive nutrients/organics and harmful levels of pathogens in surface water and/or excessive nutrients/organics in ground water.

Before Situation:

There is a need to transport manure or wastewater within a waste management system.

After Situation:

Install a 100 foot long 8 inch diameter PVC gasketed IPS pipe to transfer the manure wastewater. The transfer pipeline will deliver the manure slurry according to the CNMP, thereby protecting water quality resources.

Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; 633, Waste Recycling; 635, Vegetated Treatment Area.

Scenario Feature Measure: Length of pipe installed

Scenario Unit: Feet

Scenario Typical Size: 100

Scenario Cost: \$1,523.80

Scenario Cost/Unit: \$15.24

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.23	8	\$41.84
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.85	100	\$285.00
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.31	16	\$356.96
Materials						
Pipe, PVC, 8", SDR 35	994	Materials: - 8" - PVC - SDR 35 - ASTM D3034	Foot	\$6.72	125	\$840.00

Practice: 634 - Waste Transfer

Scenario: #12 - PVC Pressure Distribution Pipeline.

Scenario Description:

Pressure flow pipeline used to transfer manure wastewater by pumping from the waste storage pond to the field where it is to be applied according to the CNMP. The pressure pipe moves the water by pumping from the intake riser location, through a buried mainline with outlet risers. Payment includes the pipe plus an inlet riser structure, clean-out risers and outlet risers plus all other valves and fittings, trench excavation and backfill, labor and a equipment for installation. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves. Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

This pipeline is part of a manure transfer system for a planned waste management or comprehensive nutrient management plan. This scenario addresses the transport of liquid waste to a waste storage or treatment facility to prevent a water quality resource concern of excessive nutrients/organics and harmful levels of pathogens in surface water and/or excessive nutrients/organics in ground water.

Before Situation:

There is a need to transport manure or wastewater within a waste management system. The pressure distribution pipeline is utilized in the land application aspect of the operation.

After Situation:

Install a 2000 foot long 8 inch diameter PVC gasketed IPS pipe that has an SDR of 21 and is water tight under pressure flow to transfer the manure wastewater. An inlet riser and is located near the pump site of the waste storage pond and designed for the desired pressure and flow for the application system. The transfer pipeline will deliver the manure slurry to the fields for agronomic nutrient utilization according to the CNMP, thereby protecting water quality resources.

Associated practices may include: 313 Waste Storage Facility for storage structures; 533, Pumping Plant; 632, Waste Separation Facility; 590 Nutrient Management for waste application; PS 633, Waste Recycling; PS 635, Vegetated Treatment Area.

Scenario Feature Measure: Length of pipe installed

Scenario Unit: Feet

Scenario Typical Size: 2,000

Scenario Cost: \$31,995.17

Scenario Cost/Unit: \$16.00

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$2.85	2000	\$5,700.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$5.23	180	\$941.40
Concrete, CIP, formless, non reinforced	36	Non reinforced concrete cast-in-placed without forms by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$132.13	4	\$528.52
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$36.46	20	\$729.20
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.31	80	\$1,784.80
Materials						
Plug Valve, 8"	2101	8" diameter plug valve. Materials only.	Each	\$1,681.43	1	\$1,681.43
Valve, sprinkler hydrant irrigation valve with riser, metal, 8" x 4" x 42"	2104	Irrigation hydrant valve assembly including saddle tee, coated metal riser and integral valve installed on a 8" dia. pipeline, 4" dia. X 42" long riser. Materials only.	Each	\$309.16	7	\$2,164.12
Pipe, PVC, 8", SDR 26	991	Materials: - 8" - PVC - SDR 26 160 psi - ASTM D2241	Foot	\$8.92	2000	\$17,840.00
Valve, Pressure Relief	1042	Materials for <2" Pressure Relief Valve	Each	\$169.16	1	\$169.16

Materials

Valve, Air Vacuum Release, Continuous	1106	Materials for <2" Automatic Air/Vacuum Relief Valve (3 - Way Air Vac)	Each	\$152.18	3	\$456.54
--	------	--	------	----------	---	----------