

Practice: 516 - Livestock Pipeline**Scenario: #1 - PVC IPS Less than 1.5 inches****Scenario Description:**

Description: Below ground installation of PVC (Iron Pipe Size) pipeline. PVC (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 1-inch to 4-inch; and typical scenario size is 1-inch. Construct 1,320 feet of 1-inch, Schedule 40, PVC Pipeline with appurtenances, installed below ground with a minimum 1.5 feet of ground cover. The scenario unit is weight of pipe material in pounds. 1,320 feet of 1-inch, Schedule 40, PVC pipe weighs 0.240 lb/ft, or a total of 317 pounds. Appurtenances include: couplings, fittings, thrust blocks, gate valves (2), air release valves (2), drain valve (1), and pressure relief valve (1), and are included in the cost of pipe material (additional 10% of pipe material quantity). Revegetation is not included.

Resource Concerns: Inadequate Livestock Water, Inefficient Energy Use.

Associated Practices: Critical Area Planting (342), Pumping Plant (533), Watering Facility (614), and Water Harvesting Catchment (636).

Before Situation:

Water supplies need to be conveyed through pipelines for use by livestock or wildlife.

After Situation:

Pipeline(s) convey and/or distribute water to storage and/or watering facilities, for use by livestock or wildlife.

Scenario Feature Measure: Length of Pipe

Scenario Unit: Linear Foot

Scenario Typical Size: 1,320

Scenario Cost: \$2,743.88

Scenario Cost/Unit: \$2.08

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.16	1320	\$1,531.20
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.46	12	\$221.52
Materials						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.40	348	\$487.20
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$251.98	2	\$503.96