

Practice: 561 - Heavy Use Area Protection**Scenario: #1 - Reinforced Concrete with sand or gravel foundation****Scenario Description:**

The stabilization of areas around facilities that are frequently and intensively used by people, animals or vehicles by surfacing with reinforced concrete on a sand or gravel foundation to provide a stable, non-eroding surface. Installation includes all materials, equipment, and labor to install this practice, The stabilized area will address the resource concerns soil erosion and water quality degradation.

Before Situation:

This practice applies to agricultural, urban, recreational and other frequently and/or intensively used areas requiring treatment to address soil erosion and water quality degradation.

After Situation:

The stabilized area is surfaced with approximately 630 square feet of approximately 8 cubic yards of welded wire mesh reinforced concrete with 8 cubic yards of sand or gravel foundation material for surfacing areas around facilities that are frequently and intensively used by people, animals or vehicles and will address soil erosion and water quality degradation. All needed roads must use Access Road (560). Any needed treatment of stream crossings must use Stream Crossing (578). Any needed vegetation of disturbed areas must use Critical Area Planting (342). Provisions to collect, store, utilize, and or treat contaminated runoff must use Sediment Basin (350), Waste Storage Facility (313), or Waste Treatment (629) as appropriate. To reduce the potential for air quality problems from particulate matter associated with heavy use areas, consider the use of Windbreak/Shelterbelt Establishment (380) or Herbaceous Wind Barriers (603).

Scenario Feature Measure: Area**Scenario Unit:** Square Foot**Scenario Typical Size:** 630**Scenario Cost:** \$1,756.74**Scenario Cost/Unit:** \$2.79**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$1.97	4	\$7.88
Concrete, CIP, slab on grade, reinforced	37	Steel reinforced concrete formed and cast-in-placed as a slab on grade by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic yard	\$158.55	8	\$1,268.40
Materials						
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic yard	\$28.56	8	\$228.48
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$251.98	1	\$251.98

Practice: 561 - Heavy Use Area Protection**Scenario: #3 - Rock/Gravel on Geotextile, 6" thick****Scenario Description:**

The stabilization of areas around facilities that are frequently and intensively used by people, animals or vehicles by surfacing with rock and or gravel on a geotextile fabric foundation to provide a stable, non-eroding surface. Installation includes all materials, equipment, and labor to install this practice, The stabilized area will address the resource concerns of soil erosion and water quality degradation.

Before Situation:

This practice applies to agricultural, urban, recreational and other frequently and/or intensively used areas requiring treatment to address soil erosion and water quality degradation.

After Situation:

The stabilized area is surfaced with approximately 630 square feet of rock, (6" deep) and or gravel on approximately 70 square yards of geotextile fabric foundation material for surfacing areas around facilities that are frequently and intensively used by people, animals or vehicles and will address soil erosion and water quality degradation. All needed roads must use Access Road (560). Any needed treatment of stream crossings must use Stream Crossing (578). Any needed vegetation of disturbed areas must use Critical Area Planting (342). Provisions to collect, store, utilize, and or treat contaminated runoff must use Sediment Basin (350), Waste Storage Facility (313), or Waste Treatment (629) as appropriate. To reduce the potential for air quality problems from particulate matter associated with heavy use areas, consider the use of Windbreak/Shelterbelt Establishment (380) or Herbaceous Wind Barriers (603).

Scenario Feature Measure: Area of Rock and or Gravel

Scenario Unit: Square Foot

Scenario Typical Size: 630

Scenario Cost: \$770.02

Scenario Cost/Unit: \$1.22

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$1.97	12	\$23.64
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.10	70	\$147.00
Materials						
Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic yard	\$28.95	12	\$347.40
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$251.98	1	\$251.98