

Practice: 655 - Forest Trails and Landings**Scenario: #3 - Trail Erosion Control w/o Vegetation, Slopes < 35%****Scenario Description:**

Rehabilitation of existing forest access trail segments on a 20% slope and a 4% grade by addressing legacy resource issues for long-term use. Typically the trail is a single lane (18-foot wide, including cut and fill), seasonal prism requiring sustained erosion control measures installed by using heavy equipment such as dozers, graders, backhoes, and/or excavators. The purpose is to hydrologically disconnect the existing trail/landing system from streams and natural drainages. This scenario includes designing and installing measures such as cross drains, rock drains, relief drains, out sloping (or changing surface drainage), rolling dips and water bars and ditch outs as needed, and applies to only those segments of the trail system that have resource concerns requiring rehabilitation. Some hand work (chainsaw) will be needed to allow the use of the equipment. Installation will be supervised. Other practices such as Stream Crossing, and Critical Area Planting, Access Road, and Structure for Water Control can be adjacent/appurtenant but not part of this practice scenario. Treatments are for long-term reduction of sediment, restoration of fish habitat, creation of fire access, and the removal of routes off unstable slopes. Resource concerns include: Excessive sedimentation in surface waters, Concentrated flow erosion, Sheet and rill erosion, and Degradation of wildlife species.

Before Situation:

Trails are delivering sediment to waterways, impacting riparian areas and wetlands and possibly affecting T&E species. The system's usefulness for access is also being compromised by inadequate erosion and drainage control systems. However rehabilitation over abandonment is an acceptable course of action.

After Situation:

Trails and landings provide access and do not adversely affect the resources concerns.

Scenario Feature Measure: Length of trail treated

Scenario Unit: Foot

Scenario Typical Size: 2,000

Scenario Cost: \$6,716.41

Scenario Cost/Unit: \$3.36

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.51	18	\$2,097.18
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.43	9	\$57.87
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$37.98	8	\$303.84
Water Bars	1500	Installation of graded trail water controlling structures such as water bars, broad based dips for erosion control. Typical cross section is 1.5 feet high with 4:1 side slopes yielding about 0.33 CY/ft of length.	Foot	\$2.29	250	\$572.50
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$68.65	18	\$1,235.70
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.79	18	\$338.22
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$22.66	36	\$815.76
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.24	8	\$297.92
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.71	2	\$997.42

Practice: 655 - Forest Trails and Landings**Scenario: #4 - Trail Erosion Control w/o Vegetation, Slopes >35%****Scenario Description:**

Rehabilitation of existing forest access trails and landings by addressing legacy resource issues such as sedimentation, for long-term use. Typically the trail is a single lane, existing 18-foot wide including cut and fill seasonal road prism on a moderately steep (45%) slope on forestland requiring sustained erosion control measures applied by using heavy equipment such as dozers, backhoes, graders, excavators, rock and rollers. The purpose is to hydrologically disconnect existing trail/landing system from the streams and natural drainages. This includes the design and installation of cross drains, rock drains, relief drains, out sloping (or changing road surface drainage), rolling dips and water bars and ditch outs as needed. This scenario applies to only those segments of the trail system that have resource concerns requiring rehabilitation. A typical water bar or rolling dip installed in this scenario is on a 75 to 100 foot spacing. Some hand work (chainsaw) will be needed to allow the use of the equipment. The work will be supervised. Other practices such as Stream Crossing, and Critical Area Planting, Access Road and Structure for Water Control can be adjacent/appurtenant but not part of this practice scenario. Resource concerns include: Excessive sedimentation in surface waters, Concentrated flow erosion, Sheet and rill erosion, and Degradation of wildlife species.

Before Situation:

Trails are delivering sediment to waterways, impacting riparian/wetlands and/or possibly affecting fish/T&E species. The usefulness of the trail/landing system is being adversely affected by erosion.

After Situation:

Trails and landings provide access and do not adversely affect the resources concerns.

Scenario Feature Measure: Length of trail treated**Scenario Unit:** Foot**Scenario Typical Size:** 500**Scenario Cost:** \$6,776.62**Scenario Cost/Unit:** \$13.55**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Water Bars	1500	Installation of graded trail water controlling structures such as water bars, broad based dips for erosion control. Typical cross section is 1.5 feet high with 4:1 side slopes yielding about 0.33 CY/ft of length.	Foot	\$2.29	150	\$343.50
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$37.98	8	\$303.84
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$127.00	16	\$2,032.00
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.43	9	\$57.87
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$194.77	8	\$1,558.16
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.24	8	\$297.92
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.79	22	\$413.38
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$22.66	28	\$634.48
Materials						
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$27.61	5	\$138.05
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$498.71	2	\$997.42

Practice: 655 - Forest Trails and Landings**Scenario: #5 - Grading and Shaping with Vegetative Establishment****Scenario Description:**

Rehabilitation of existing forest access trails and landings on a medium slope by addressing rutting, erosion, and sedimentation. Typically the trail is a single, existing 18-foot wide (including cut and fill) seasonal road prism on gently sloping terrain requiring sustained erosion control measures applied with heavy equipment such as dozers, graders, backhoes, and/or excavators. The purpose is to hydrologically disconnect the existing trail/landing system from streams and natural drainages and to establish a vegetative cover. This scenario includes designing and installation measures such as cross drains, rock drains, relief drainage, out sloping (or changing surface drainage), rolling dips and water bars and ditch outs as needed, and applies to only those segments of the trail system that have resource concerns requiring rehabilitation. It also includes seedbed preparation, seeding to a perennial improved grass and soil amendments determined to be needed. Some hand work (chainsaw) will be needed to allow the use of the equipment. Other practices such as Stream Crossing, and Critical Area Planting. Access Road and Structure for Water Control can be adjacent/appurtenant but not part of the practice scenario. Treatments are for long-term reduction of sediment, restore fish habitat, create fire access and to move routes off unstable slopes. Resource concerns include: Excessive sediment in surface waters, Concentrated and Sheet & rill flow erosion, Soil compaction, and Habitat degradation.

Before Situation:

Trail/landings are delivering sediment to waterways, impacting riparian/wetlands and/or possibly affecting fish/T&E species. The usefulness of the trail/landing system is being adversely affected by erosion.

After Situation:

A trail system is installed that provides access to the forested tract and does not cause excessive erosion or water quality concerns.

Scenario Feature Measure: Length of trail treated

Scenario Unit: Foot

Scenario Typical Size: 2,000

Scenario Cost: \$4,977.54

Scenario Cost/Unit: \$2.49

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.58	1	\$6.58
Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$57.21	16	\$915.36
Tillage, Light	945	Includes light disking (tandem) or field cultivator. Includes equipment, power unit and labor costs.	Acre	\$10.77	1	\$10.77
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$9.82	1	\$9.82
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.21	1	\$12.21
Water Bars	1500	Installation of graded trail water controlling structures such as water bars, broad based dips for erosion control. Typical cross section is 1.5 feet high with 4:1 side slopes yielding about 0.33 CY/ft of length.	Foot	\$2.29	300	\$687.00
Motor Grader, 200 HP	1782	Motor Grader or Maintainer, 200 hp. Typical of equipment with HP in range of 170-240. Equipment cost, does not include labor.	Hour	\$161.25	10	\$1,612.50
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.43	8	\$51.44
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.79	16	\$300.64
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$19.43	26	\$505.18

Materials

Potassium, K ₂ O	74	K ₂ O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.59	40	\$23.60
Phosphorus, P ₂ O ₅	73	Price per pound of P ₂ O ₅ supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.78	55	\$42.90
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$143.05	1	\$143.05
One Species, Warm Season, Introduced Perennial Grass (seed or sprigs)	2323	Introduced, warm season perennial grass seed or sprig. Includes material and shipping only.	Acre	\$64.09	1	\$64.09
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$1.00	70	\$70.00

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$261.20	2	\$522.40
--------------------------------	------	---	------	----------	---	----------

Practice: 655 - Forest Trails and Landings**Scenario: #6 - Temporary Stream Crossing****Scenario Description:**

The design and installation of a temporary stream crossing that will meet the immediate forest management/conservation needs. Afterwards the crossing will be restored and stabilized. Improperly designed and/or installed stream crossings will, in the long term, adversely affect water quality and aquatic life. Approaches will also be stabilized for the use of the crossing and stabilized afterwards as necessary. Installation will be supervised. Permanent and/or high-traffic crossings will be designed and installed according to the Stream Crossing (578) Standard. Resource concerns include: Excessive sediment in surface waters and Habitat degradation.

Before Situation:

Access to a forested tract is not available for the installation of conservation practices or removal of forest products due to the lack of a suitable stream crossing(s).

After Situation:

Access was available to address other resource concerns/management needs and the stream is restored to its previous or better condition.

Scenario Feature Measure: Number of crossings

Scenario Unit: Each

Scenario Typical Size: 1

Scenario Cost: \$1,001.72

Scenario Cost/Unit: \$1,001.72

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$116.51	2	\$233.02
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$44.09	2	\$88.18
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$37.98	1	\$37.98
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.79	2	\$37.58
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$22.66	2	\$45.32
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.24	1	\$37.24
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$261.20	2	\$522.40