

**NATURAL RESOURCES CONSERVATION SERVICE
CONSERVATION PRACTICE SPECIFICATION**

SPRING DEVELOPMENT

CODE 574

SPECIFICATIONS

SITE PREPARATION

All loose rock, sediment, encrustations, logs, and vegetation that can obstruct the free discharge off the spring shall be removed and disposed of so that they will not endanger the spring development.

CONSTRUCTION

Collection trenches, drain tiles, perforated pipe lines, sumps, and spring boxes shall be constructed to the elevation and grade shown on the plans.

Crushed rock or gravel for collection systems and sand-gravel material for filters shall be composed of clean, hard particles.

All materials used will be in good condition and meet the requirements of the applicable ASTM specifications or commercial standards.

OVERALL QUALITY AND WORKMANSHIP

Construction operations shall be carried out in such a manner and sequence that erosion and air and water pollution are minimized and held within legal limits.

All construction will be accomplished in a workmanlike manner that results in a "finished" appearance.