

STATEMENT OF WORK Grassed Waterway (412)

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables

1. Design documentation that will demonstrate that the criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client.
 - c. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06 and NE503.02(d)).
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Hydrology/hydraulics
 - ii. Outlet capacity and stability
 - iii. Seedbed preparation, soil amendments and vegetation requirements
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits.
3. Operation and maintenance plan.
4. Certification that the design meets practice standard criteria and complies with applicable laws and regulations (NEM Subpart A, 505.03(b)(2)).
5. Design modifications during installation as required.
6. Additional details for design documentation as found in Nebraska Grassed Waterway Practice Documentation Requirements for surveys, designs, and plans and specifications.

INSTALLATION

Deliverables

1. Pre-installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection.
 - a. Actual materials used
 - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements (for guidance, see NEM Subpart A, 505.03(c)(1)).
8. Installation documentation in accordance with Nebraska Grassed Waterway Practice Documentation Requirements for layout.

STATEMENT OF WORK Grassed Waterway (412)

CHECK OUT

Deliverables

1. As-built documentation.
 - a. Extent of practice units applied
 - b. Drawings
 - c. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03(c)(1)).
3. Progress reporting.
4. Check-out documentation in accordance with Nebraska Grassed Waterway Practice Documentation Requirements for compliance checking.

REFERENCES

See Nebraska Grassed Waterway Practice Documentation Requirements for references.