

**Practice: 383 - Fuel Break**

**Scenario: #1 - Dozer**

**Scenario Description:**

Fuel Break installation requires tree thinning, treating woody residue, pruning, and mowing. Thinning treatment and pruning is done by hand, treating woody residue (piling/burning, crushing, or off-site removal) and mowing are mechanized. Resource concerns are degraded plant condition - wildfire hazard, excess biomass accumulation & undesirable productivity and health.

**Before Situation:**

Forest stand is overstocked with desirable and undesirable trees. Overstocking creates conditions conducive to wildfire movement across the landscape, and severe loss/damage of the forest stand. Shrub levels are high and significantly increase wildfire risk. Tree crowns are touching, trees retain limbs down to understory vegetation creating a "ladder" for fire movement into the overstory, and understory vegetation (brush and grasses) create a significant fuel load to rate a high to severe fire hazard. The terrain is moderately to steeply sloped (1-30%), increasing difficulty as slope steepens.

**After Situation:**

Fuel Break is installed at the property line or a key locations to reduce crown fire spread. Size of fuel break is 4 acres; the width varies due to site conditions. The trees are thinned so open gaps are created in crown overstory, branches on remaining trees are pruned to 8 to 10 feet in height, all woody residue (thinned trees and pruned branches) are treated (piled/burned or lopped/scattered) so little remains in the fuel break and understory vegetation is mowed down to less than 1 foot in height. Cut stumps have been chemically treated to control sprouting.

**Scenario Feature Measure:** Area of Treatment

**Scenario Unit:** Acre

**Scenario Typical Size:** 4

**Scenario Cost:** \$6,625.68

**Scenario Cost/Unit:** \$1,656.42

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$51.54	8	\$412.32
Pruning tool, pole saw	1319	Gasoline powered pole chainsaw. Labor not included.	Hour	\$8.03	8	\$64.24
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$57.63	8	\$461.04
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$37.72	8	\$301.76
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.39	80	\$511.20
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.14	10	\$1,261.40
Pruning tools, hand tools	1318	Pruning tools, hand tools, shears, loppers, pole saw, handsaw. Material costs only. Labor not included.	Hour	\$4.77	8	\$38.16
<b>Labor</b>						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.43	8	\$179.44
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	80	\$1,777.60
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.74	12	\$512.88
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$37.38	10	\$373.80
<b>Materials</b>						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.43	4	\$25.72

**Materials**

Herbicide, Triclopyr	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.30	4	\$169.20
----------------------	-----	-----------------------------------------------------------------------------------	------	---------	---	----------

**Mobilization**

Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$174.49	1	\$174.49
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	1	\$259.43
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	\$1.03	100	\$103.00

**Practice: 383 - Fuel Break**

**Scenario: #2 - Dozer, Steep Slope**

**Scenario Description:**

Fuel Break installation requires tree thinning, treating woody residue, pruning, and brush cutting. Thinning treatment, tree pruning and brush cutting are done by hand, treating woody residue (piling/burning, crushing, or off-site removal) is mechanized and hand treatment. Resource concerns are degraded plant condition - wildfire hazard, excess biomass accumulation & undesirable productivity and health.

**Before Situation:**

The forest stand is overstocked with trees (desirable and undesirable) and is at risk of loss if a wildfire should occur. Tree crowns are touching, trees retain limbs down to understory vegetation creating a "ladder" for fire movement into the overstory, and understory vegetation (brush and grasses) create a significant fuel load to rate a high to severe fire hazard. A fuel break is implemented to reduce the risk of a crown spreading wildfire. The terrain is steep, 40+%, which significantly reduces efficiency and increases cost of installation. More cutting of trees & brush and treatment of woody residue is accomplished using labor due to very steep slopes.

**After Situation:**

Fuel Break is installed at the property line or key locations to reduce crown fire spread. Size of fuel break is 4 acres; the width varies due to site conditions. The trees are thinned so open gaps are created in crown overstory; branches on remaining trees are pruned to a minimum of 8 to 10 feet in height; all woody residue, thinned trees, pruned branches and cut brush, are treated.

**Scenario Feature Measure:** Area of Treatment

**Scenario Unit:** Acre

**Scenario Typical Size:** 4

**Scenario Cost:** \$10,641.88

**Scenario Cost/Unit:** \$2,660.47

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Pruning tools, hand tools	1318	Pruning tools, hand tools, shears, loppers, pole saw, handsaw. Material costs only. Labor not included.	Hour	\$4.77	14	\$66.78
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$126.14	10	\$1,261.40
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.39	160	\$1,022.40
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$37.72	10	\$377.20
Mechanical cutter, chopper	943	Masticator, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$130.31	10	\$1,303.10
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$57.63	14	\$806.82
Pruning tool, pole saw	1319	Gasoline powered pole chainsaw. Labor not included.	Hour	\$8.03	8	\$64.24
<b>Labor</b>						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.74	20	\$854.80
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.43	10	\$224.30
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$37.38	10	\$373.80
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	160	\$3,555.20
<b>Materials</b>						
Herbicide, Triclopyr	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.30	4	\$169.20

**Materials**

Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.43	4	\$25.72
--------------------	-----	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------	--------	---	---------

**Mobilization**

Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	\$1.03	100	\$103.00
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$174.49	1	\$174.49
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	1	\$259.43

**Practice: 383 - Fuel Break**

**Scenario: #3 - Masticator**

**Scenario Description:**

Fuel Break installation requires tree thinning, treating woody residue, pruning, and mowing. Thinning treatment and pruning is done by hand; treating woody residue (piling/burning, crushing, or off-site removal) and mowing are mostly mechanized. Resource concerns are degraded plant condition - wildfire hazard, excess biomass accumulation & undesirable productivity and health.

**Before Situation:**

The forest stand is overstocked with trees (desirable and undesirable) and is at risk of loss if a wildfire should occur. Tree crowns are touching, trees retain limbs down to understory vegetation creating a "ladder" for fire movement into the overstory, and understory vegetation (brush and grasses) create a significant fuel load to rate a high to severe fire hazard. Slope of terrain increases fire hazard. The terrain moderately sloped, 1-30+% increasing difficulty as slope steepens.

**After Situation:**

Fuel Break is installed at the property line or key locations to reduce crown fire spread. Size of fuel break is 4 acres; the width varies due to site conditions. The trees are thinned so open gaps are created in crown overstory, branches on remaining trees are pruned to 8 to 10 feet in height, all woody residue (thinned trees, pruned branches and brush) are mostly masticated but some is piled/burned, hauled of site or lopped/scattered) understory vegetation is cut down to less than 1 foot in height. Cut stumps have been chemically treated to control sprouting.

**Scenario Feature Measure:** Area of Treatment

**Scenario Unit:** Acre

**Scenario Typical Size:** 4

**Scenario Cost:** \$6,725.73

**Scenario Cost/Unit:** \$1,681.43

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Mechanical cutter, chopper	943	Masticator, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$130.31	16	\$2,084.96
Pruning tool, pole saw	1319	Gasoline powered pole chainsaw. Labor not included.	Hour	\$8.03	8	\$64.24
Pruning tools, hand tools	1318	Pruning tools, hand tools, shears, loppers, pole saw, handsaw. Material costs only. Labor not included.	Hour	\$4.77	8	\$38.16
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$57.63	8	\$461.04
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$51.54	5	\$257.70
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$37.72	8	\$301.76
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.39	60	\$383.40
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	80	\$1,777.60
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.43	5	\$112.15
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.74	12	\$512.88
<b>Materials</b>						
Herbicide, Triclopyr	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.30	4	\$169.20
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.43	4	\$25.72

**Mobilization**

**Mobilization**

Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	\$1.03	100	\$103.00
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$174.49	1	\$174.49
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	1	\$259.43

**Practice: 383 - Fuel Break**

**Scenario: #4 - Masticator, Steel Slope**

**Scenario Description:**

Fuel Break installation requires tree thinning, treating woody residue, pruning, and brush cutting. Thinning is mechanized and hand cutting, tree pruning and brush cutting are done by hand, treating woody residue (piling/burning, crushing, or off-site removal) is mechanized and some hand treatment. Resource concerns are degraded plant condition - wildfire hazard, excess biomass accumulation & undesirable productivity and health.

**Before Situation:**

The forest stand is overstocked with trees (desirable and undesirable) and is at risk of loss if a wildfire should occur. Tree crowns are touching, trees retain limbs down to understory vegetation creating a "ladder" for fire movement into the overstory, and understory vegetation (brush and grasses) create a significant fuel load to rate a high to severe fire hazard. Slope of terrain significantly increases fire hazard rating due to preheating effect. The terrain is steeply sloped, 40+%, which significantly reduces implementation efficiency. More hand cutting and treatment of woody residue is accomplished using labor due to very steep slopes.

**After Situation:**

Fuel Break is installed at the property line or a key locations to reduce crown fire spread. Size of fuel break is 4 acres; the width varies due to site conditions. The trees are thinned so open gaps are created in crown overstory, branches on remaining trees are pruned to 8 to 10 feet in height, all woody residue (thinned trees, pruned branches and brush) are mostly masticated but some is piled/burned, hauled of site or lopped/scattered) so little remains in the fuel break and understory vegetation is cut down to less than 1 foot in height. Cut stumps have been chemically treated to control sprouting.

**Scenario Feature Measure: Area of Treatment**

**Scenario Unit: Acre**

**Scenario Typical Size: 4**

**Scenario Cost: \$9,568.07**

**Scenario Cost/Unit: \$2,392.02**

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Mechanical cutter, chopper	943	Masticator, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$130.31	20	\$2,606.20
Pruning tools, hand tools	1318	Pruning tools, hand tools, shears, loppers, pole saw, handsaw. Material costs only. Labor not included.	Hour	\$4.77	14	\$66.78
Pruning tool, pole saw	1319	Gasoline powered pole chainsaw. Labor not included.	Hour	\$8.03	7	\$56.21
Chemical, spot treatment, single stem application	964	Ground applied chemical to individual plants or group of plants, e.g., backpack sprayer treatment. Equipment and labor cost included.	Hour	\$57.63	12	\$691.56
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.39	120	\$766.80
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$37.72	12	\$452.64
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$37.38	20	\$747.60
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.74	12	\$512.88
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$22.43	12	\$269.16
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	120	\$2,666.40
<b>Materials</b>						
Herbicide, Triclopyor	338	Refer to WIN-PST for product names and active ingredients. Materials and shipping	Acre	\$42.30	4	\$169.20

**Materials**

Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.43	4	\$25.72
--------------------	-----	--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	------	--------	---	---------

**Mobilization**

Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	\$1.03	100	\$103.00
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$174.49	1	\$174.49
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	1	\$259.43

**Practice: 383 - Fuel Break**

**Scenario: #5 - Hand Tools**

**Scenario Description:**

Fuel Break installation requires tree thinning, treating woody residue, pruning, and mowing. Thinning treatment, pruning, brush cutting and treating woody residue (piling/burning, crushing, or off-site removal), is done by hand. Resource concerns are degraded plant condition - wildfire hazard, excess biomass accumulation & undesirable productivity and health.

**Before Situation:**

Forest stand is overstocked with desirable and undesirable trees. Overstocking creates conditions conducive to wildfire movement across the landscape, and loss of the forest stand. Excess stocking is impacting the health of the desired forest ecosystem and wildfire hazard poses risk to humans, structures, air quality, plants and animals. Tree crowns are touching, trees retain limbs down to understory vegetation creating a "ladder" for fire movement into the overstory, and understory vegetation (brush and grasses) create a significant fuel load.

**After Situation:**

A fuel break is installed by hand cutting trees, hand pruning remaining trees, piling and burning or removal of woody residue from tree cutting and pruning. FB installation is at property lines, around structures, at roadways, or other key locations to reduce continuity of vegetation cover. Width of fuel break varies based on site conditions.

**Scenario Feature Measure:** Area of Treatment

**Scenario Unit:** Acre

**Scenario Typical Size:** 4

**Scenario Cost:** \$8,008.34

**Scenario Cost/Unit:** \$2,002.09

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$37.72	12	\$452.64
Pruning tools, hand tools	1318	Pruning tools, hand tools, shears, loppers, pole saw, handsaw. Material costs only. Labor not included.	Hour	\$4.77	10	\$47.70
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.39	240	\$1,533.60
<b>Labor</b>						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$42.74	12	\$512.88
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	240	\$5,332.80
<b>Materials</b>						
Tree Marking Paint	313	Trees to be cut through tree marking are physically identified through the application of paint on the tree. Typically one quart of paint is used to mark one acre of trees. Includes materials and shipping only.	Acre	\$6.43	4	\$25.72
<b>Mobilization</b>						
Mobilization, Material, distance > 50 miles	1043	Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i	Dollar	\$1.03	100	\$103.00

**Practice: 383 - Fuel Break**

**Scenario: #6 - Non Forest**

**Scenario Description:**

A non forest fuel break occurs outside of forestlands where brush, grass and forbs dominate. Landuses where this scenario will be applied may be range, pasture or wetlands. The fuel break area is mowed/bushhog so standing vegetation is reduced to a low height. Resource concerns are degraded plant condition - wildfire hazard.

**Before Situation:**

Wildfire movement is a concern within the designated area. Vegetation is tall, dense and continuous creating conditions conducive for fire movement across the landscape.

**After Situation:**

A fuel break is installed by shredding/mowing/bushhogging a defined width at property lines, around structures, at roadways, or other key locations to reduce continuity of vegetation cover. Width of fuel break varies based on site conditions.

**Scenario Feature Measure:** Area of Treatment

**Scenario Unit:** Acre

**Scenario Typical Size:** 4

**Scenario Cost:** \$412.32

**Scenario Cost/Unit:** \$103.08

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<i>Equipment/Installation</i>						
Mower, Bush Hog	940	Equipment and power unit costs. Labor not included.	Hour	\$51.54	8	\$412.32