

**Practice: 430 - Irrigation Pipeline**

**Scenario: #1 - PVC (Iron Pipe Size), 8 inches or less**

**Scenario Description:**

Description: Below ground installation of PVC (Iron Pipe Size) pipeline. PVC (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 24-inch; and typical scenario size is 4-inch. Construct 1/4 mile (1,320 feet) of 4-inch, SDR-26, PVC pipeline with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe material in pounds for 1,320 feet of 4-inch, (SDR-26) PVC pipe weighs 1.51lb/ft, or a total of 1993 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 1,993

**Scenario Cost:** \$7,016.74

**Scenario Cost/Unit:** \$3.52

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.39	1320	\$1,834.80
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	48	\$1,066.56
<b>Materials</b>						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.64	2193	\$3,596.52
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	2	\$518.86

**Practice: 430 - Irrigation Pipeline**

**Scenario: #2 - PVC (Iron Pipe Size) 10 inches or greater**

**Scenario Description:**

Description: Below ground installation of PVC (Iron Pipe Size) pipeline. PVC (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 24-inch; and typical scenario size is 12-inch. Construct 1/4 mile (1,320 feet) of 12-inch, Class 125 (SDR-32.5), PVC pipeline with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe material in pounds. 1,320 feet of 12-inch, Class 125 (SDR-32.5) PVC pipe weighs 9.505 lb/ft, or a total of 12,547 pounds.

Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 12,547

**Scenario Cost:** \$28,848.84

**Scenario Cost/Unit:** \$2.30

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$3.15	1320	\$4,158.00
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	48	\$1,066.56
<b>Materials</b>						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.64	13801	\$22,633.64
<b>Mobilization</b>						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$495.32	2	\$990.64

**Practice: 430 - Irrigation Pipeline**

**Scenario: #3 - PVC (Plastic Irrigation Pipe) 8" or less**

**Scenario Description:**

Description: Below ground installation of PVC (Plastic Irrigation Pipe) pipeline. PVC (PIP) is manufactured in sizes (nominal diameter) from 4-inch to 27-inch; typical practice sizes range from 4-inch to 24-inch; and typical scenario size is 6-inch. Construct 1/4 mile (1,320 feet) of 6-inch, 50 PSI (SDR-81.0), PVC PIP with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe in pounds. 1,320 feet of 6-inch, 50 PSI (SDR-81.0) PVC PIP weighs 0.99 lb/ft, or a total of 1307 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 1,307

**Scenario Cost:** \$5,778.54

**Scenario Cost/Unit:** \$4.42

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.39	1320	\$1,834.80
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	48	\$1,066.56
<b>Materials</b>						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.64	1438	\$2,358.32
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	2	\$518.86

**Practice: 430 - Irrigation Pipeline**

**Scenario: #4 - PVC (Plastic Irrigation Pipe) 10 inches or greater**

**Scenario Description:**

Description: Below ground installation of PVC (Plastic Irrigation Pipe) pipeline. PVC (PIP) is manufactured in sizes (nominal diameter) from 4-inch to 27-inch; typical practice sizes range from 4-inch to 24-inch; and typical scenario size is 12-inch. Construct 1/4 mile (1,320 feet) of 12-inch, Class 50 (SDR-81.0), PVC PIP with appurtenances, installed below ground with a minimum of 2 feet of ground cover. The unit is weight of pipe in pounds. 1,320 feet of 12-inch, Class 50 (SDR-81.0) PVC PIP weighs 3.594 lb/ft, or a total of 4,744 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 4,744

**Scenario Cost:** \$14,656.46

**Scenario Cost/Unit:** \$3.09

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$3.15	1320	\$4,158.00
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	64	\$1,422.08
<b>Materials</b>						
Pipe, PVC, dia. < 18", weight priced	1323	Polyvinyl Chloride (PVC) pressure rated pipe priced by the weight of the pipe materials for pipes with diameters less than 18". Materials only.	Pound	\$1.64	5218	\$8,557.52
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	2	\$518.86

**Practice: 430 - Irrigation Pipeline**

**Scenario: #5 - HDPE (Iron Pipe Size & Tubing) 8" or less**

**Scenario Description:**

Description: Below ground installation of HDPE (Iron Pipe Size & Tubing) pipeline. HDPE (IPS & Tubing) is manufactured in sizes (nominal diameter) from ½-inch to 24-inch; typical practice sizes range from 2-inch to 24-inch; and typical scenario size is 6-inch. Construct 1/4 mile (1,320 feet) of 6-inch, Class 130 (SDR-13.5), HDPE pipeline with appurtenances, installed below ground with a minimum 2 feet of ground cover. The unit is weight of pipe material in pounds. 1,320 feet of 8-inch, Class 130 (SDR-13.5), HDPE weighs 4.024 lb/ft, or a total of 5,312 pounds. Appurtenances include: fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 5,312

**Scenario Cost:** \$18,687.39

**Scenario Cost/Unit:** \$3.52

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.39	1320	\$1,834.80
Fuser for HDPE Pipe	1383	Fusing machine for 1" to 12" diameter HDPE pipe joints. Equipment costs only. Does not include labor.	Hour	\$22.97	16	\$367.52
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	48	\$1,066.56
<b>Materials</b>						
Pipe, HDPE, smooth wall, weight priced	1379	High Density Polyethylene (HDPE) compound manufactured into smooth wall pipe. Materials only.	Pound	\$2.55	5843	\$14,899.65
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	2	\$518.86

**Practice: 430 - Irrigation Pipeline**

**Scenario: #6 - HDPE (Iron Pipe Size & Tubing) 10" or greater**

**Scenario Description:**

Description: Below ground installation of HDPE (Iron Pipe Size & Tubing) pipeline. HDPE (IPS & Tubing) is manufactured in sizes (nominal diameter) from ½-inch to 24-inch; typical practice sizes range from 2-inch to 24-inch; and typical scenario size is 12-inch. Construct 1/4 mile (1,320 feet) of 12-inch, Class 130 (SDR-13.5), HDPE pipeline with appurtenances, installed below ground with a minimum 2 feet of ground cover. The unit is weight of pipe material in pounds. 1,320 feet of 8-inch, Class 130 (SDR-13.5), HDPE weighs 14.89 lb/ft, or a total of 19,655 pounds. Appurtenances include: fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 19,655

**Scenario Cost:** \$61,241.94

**Scenario Cost/Unit:** \$3.12

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Fuser for HDPE Pipe	1383	Fusing machine for 1" to 12" diameter HDPE pipe joints. Equipment costs only. Does not include labor.	Hour	\$22.97	16	\$367.52
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$3.15	1320	\$4,158.00
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	48	\$1,066.56
<b>Materials</b>						
Pipe, HDPE, smooth wall, weight priced	1379	High Density Polyethylene (HDPE) compound manufactured into smooth wall pipe. Materials only.	Pound	\$2.55	21620	\$55,131.00
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	2	\$518.86

**Practice: 430 - Irrigation Pipeline**

**Scenario: #7 - Surface HDPE (Iron Pipe Size & Tubing)**

**Scenario Description:**

Description: On-ground surface installation of HDPE (Iron Pipe Size & Tubing) pipeline. HDPE (IPS & Tubing) is manufactured in sizes (nominal diameter) from ½-inch to 24-inch; typical practice sizes range from 2-inch to 24-inch; and typical scenario size is 2-inch. Construct 1/4 mile (1,320 feet) of 2-inch, Class 200 (SDR-9.0), HDPE pipeline with appurtenances, installed on the ground surface. The unit is weight of pipe material in pounds. 1,320 feet of 2-inch, Class 200 (SDR-9.0), HDPE weighs 0.744 lb/ft, or a total of 982 pounds. Appurtenances include: fittings, air vents, pressure relief valves, anchors, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 15% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 982

**Scenario Cost:** \$3,561.51

**Scenario Cost/Unit:** \$3.63

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Fuser for HDPE Pipe	1383	Fusing machine for 1" to 12" diameter HDPE pipe joints. Equipment costs only. Does not include labor.	Hour	\$22.97	8	\$183.76
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	16	\$355.52
<b>Materials</b>						
Pipe, HDPE, smooth wall, weight priced	1379	High Density Polyethylene (HDPE) compound manufactured into smooth wall pipe. Materials only.	Pound	\$2.55	1129	\$2,878.95
<b>Mobilization</b>						
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$71.64	2	\$143.28

**Practice: 430 - Irrigation Pipeline**

**Scenario: #8 - HDPE (Corrugated Plastic Pipe)**

**Scenario Description:**

Description: Below ground installation of HDPE (Corrugated Plastic Pipe) pipeline. HDPE (CPP) Twin-Wall is manufactured in sizes (nominal diameter) from 4-inch to 60-inch; typical practice sizes range from 12-inch to 24-inch; and typical scenario size is 18-inch. Construct 1/8 mile (660 feet) of 18-inch, Twin-Wall, HDPE Corrugated Plastic Pipe (CPP) with a smooth interior, and appurtenances, installed below ground with a minimum 2 feet of ground cover. The unit is in weight of pipe material in pounds. 660 feet of 18-inch, Twin-Wall, HDPE CPP weighs 6.40 lb/ft, or a total of 4,224 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 4,224

**Scenario Cost:** \$12,553.30

**Scenario Cost/Unit:** \$2.97

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Trenching, Earth, 30" x 48"	1384	Trenching, earth, 30" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$3.69	660	\$2,435.40
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	64	\$1,422.08
<b>Materials</b>						
Pipe, HDPE, corrugated single wall, ≤ 12" weight priced Compound	1380	High Density Polyethylene (HDPE) compound manufactured into single wall corrugated pipe or tubing. Materials only.	Pound	\$1.76	4646	\$8,176.96
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	2	\$518.86

**Practice: 430 - Irrigation Pipeline**

**Scenario: #9 - Steel (Iron Pipe Size) 8" or less**

**Scenario Description:**

Description: Below ground installation of Steel (Iron Pipe Size) pipeline. Steel (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 18-inch; and typical scenario size is 6-inch. Construct 1/4 mile (1,320 feet) of 6-inch, Schedule 10, Galvanized Steel Pipe with appurtenances, installed below ground with a minimum feet of ground cover. The unit is the weight of pipe material in pounds. 1,320 feet of 6-inch, Schedule 10, Galvanized Steel Pipe weighs 9.289 lb/ft, for a total of 12,261 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Typical installation applies to soils with no special bedding requirements. Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use. Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 12,261

**Scenario Cost:** \$24,142.62

**Scenario Cost/Unit:** \$1.97

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Trenching, Earth, 12" x 48"	53	Trenching, earth, 12" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$1.39	1320	\$1,834.80
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	64	\$1,422.08
<b>Materials</b>						
Pipe, steel, smooth wall, galvanized, weight priced	1381	Steel manufactured into galvanized smooth wall pipe	Pound	\$1.51	13488	\$20,366.88
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	2	\$518.86

**Practice: 430 - Irrigation Pipeline**

**Scenario: #10 - Steel (Iron Pipe Size) 10" or greater**

**Scenario Description:**

Description: Below ground installation of Steel (Iron Pipe Size) pipeline. Steel (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 18-inch; and typical scenario size is 12-inch. Construct 1/4 mile (1,320 feet) of 12-inch, Schedule 10, Galvanized Steel Pipe with appurtenances, installed below ground with a minimum feet of ground cover. The unit is the weight of pipe material in pounds. 1,320 feet of 12-inch, Schedule 10, Galvanized Steel Pipe weighs 24.16 lb/ft, for a total of 31,891 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 31,891

**Scenario Cost:** \$59,780.78

**Scenario Cost/Unit:** \$1.87

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Trenching, Earth, loam, 24" x 48"	54	Trenching, earth, loam, 24" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$3.15	1320	\$4,158.00
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	96	\$2,133.12
<b>Materials</b>						
Pipe, steel, smooth wall, galvanized, weight priced	1381	Steel manufactured into galvanized smooth wall pipe	Pound	\$1.51	35080	\$52,970.80
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	2	\$518.86

**Practice: 430 - Irrigation Pipeline**

**Scenario: #11 - Surface Steel (Iron Pipe Size)**

**Scenario Description:**

Description: On-ground surface installation of Steel (Iron Pipe Size) pipeline. Steel (IPS) is manufactured in sizes (nominal diameter) from ½-inch to 36-inch; typical practice sizes range from 2-inch to 18-inch; and typical scenario size is 2-inch. Construct 1/4 mile (1,320 feet) of 2-inch, Schedule 40, Galvanized Steel Pipe with appurtenances, installed on the ground surface. The unit is weight of pipe material in pounds. 1,320 feet of 2-inch, Schedule 40, Galvanized Steel Pipe weighs 3.653 lb/ft, or a total of 4,822 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, anchors, expansion joints, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 15% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 4,822

**Scenario Cost:** \$9,439.51

**Scenario Cost/Unit:** \$1.96

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	48	\$1,066.56
<b>Materials</b>						
Pipe, steel, smooth wall, galvanized, weight priced	1381	Steel manufactured into galvanized smooth wall pipe	Pound	\$1.51	5545	\$8,372.95

**Practice: 430 - Irrigation Pipeline**

**Scenario: #12 - Steel (Corrugated Steel Pipe)**

**Scenario Description:**

Description: Below ground installation of Corrugated Steel Pipe (CSP) pipeline. Steel (CSP) is manufactured in sizes (nominal diameter) from 12-inch to 72-inch; typical practice sizes range from 12-inch to 24-inch; and typical scenario size is 18-inch. Construct 1/8 mile (660 feet) of 18-inch, 14-gauge, Galvanized Corrugated Steel Pipe (CSP) with appurtenances, installed below ground with a minimum 2 feet of ground cover. The unit is weight of pipe material in pounds. 660 feet of 18-inch, 14-gauge, Galvanized CSP weighs 18.0 lb/ft, or a total of 11,800 pounds. Appurtenances include: couplings, fittings, air vents, pressure relief valves, thrust blocks, risers, and inline valves, and are included in the cost of pipe material (additional 10% of pipe material quantity). Cost of appurtenances does not include flow meters or backflow preventers. Typical installation applies to soils with no special bedding requirements.

Resource Concerns: Inefficient Use of Irrigation Water; Inefficient Energy Use.

Associated Practices: 436 - Irrigation Reservoir; 441 - Irrigation System, Microirrigation; 442 - Irrigation System, Sprinkler; 443 - Irrigation System, Surface & Subsurface; 447 - Irrigation System, Tailwater Recovery; 533 - Pumping Plant; 634 - Waste Transfer.

**Before Situation:**

Pipeline needed to replace or supplement inefficient irrigation conveyance systems.

**After Situation:**

Pipeline installed to convey and/or distribute water to irrigation systems or reservoirs, minimizing non-beneficial water use, reducing soil erosion, and/or reducing energy use.

**Scenario Feature Measure:** Weight of Pipe

**Scenario Unit:** Pound

**Scenario Typical Size:** 11,880

**Scenario Cost:** \$15,661.46

**Scenario Cost/Unit:** \$1.32

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Trenching, Earth, 30" x 48"	1384	Trenching, earth, 30" wide x 48" depth, includes equipment and labor for trenching and backfilling	Foot	\$3.69	660	\$2,435.40
<b>Labor</b>						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.22	80	\$1,777.60
<b>Materials</b>						
Pipe, CMP, 14-12 gauge, weight priced	1589	14 and 12 gauge galvanized helical corrugated metal pipe priced by the weight of the pipe materials. Materials only.	Pound	\$0.80	13662	\$10,929.60
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$259.43	2	\$518.86