

Practice: 580 - Streambank and Shoreline Protection**Scenario: #1 - Vegetative****Scenario Description:**

Protection of streambanks consisting of conventional plantings of vegetation to stabilize and protect against scour and erosion.

The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species. Payment cost include shaping bank, critical area vegetation and erosion control fabric; a 6-foot high bank at 3(H):1(V) slope for 1000 linear feet (0.46 acres) is used for estimation purposes.

Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation.

Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484 - Mulching

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has marginally degraded streambanks that are unstable and show signs of active erosion.

Soil Erosion: The streambank is unstable.

Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures.

Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream.

Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stable against further erosion and encourages natural sediment transport and deposition. Loss of riparian areas and sediment load is reduced in the stream.

For Soil Erosion: The streambank is stable.

For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat.

For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized.

For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Scenario Feature Measure: Square Feet of Streambank/Shoreline Protected

Scenario Unit: Square Foot

Scenario Typical Size: 20,000

Scenario Cost: \$16,887.56

Scenario Cost/Unit: \$0.84

Cost Details (by category):

| Component Name | ID | Component Description | Unit | Price (\$/unit) | Quantity | Cost |
|--|-----|--|------------|-----------------|----------|------------|
| Equipment/Installation | | | | | | |
| Excavation, Common Earth, side cast, small equipment | 48 | Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor. | Cubic yard | \$2.36 | 2500 | \$5,900.00 |
| Dozer, 80 HP | 929 | Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included. | Hour | \$68.19 | 32 | \$2,182.08 |
| Seeding Operation, Broadcast, Ground | 959 | Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs. | Acre | \$12.13 | 0.46 | \$5.58 |
| Labor | | | | | | |
| General Labor | 231 | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. | Hour | \$22.22 | 224 | \$4,977.28 |
| Equipment Operators, Light | 232 | Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers | Hour | \$22.43 | 32 | \$717.76 |
| Supervisor or Manager | 234 | Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc. | Hour | \$42.74 | 56 | \$2,393.44 |

Materials

Materials

| | | | | | | |
|---|------|---|------|---------|------|---------|
| One Species, Cool Season, Annual Grass or Legume | 2311 | Cool season annual grass or legume. Includes material and shipping only. | Acre | \$39.29 | 0.46 | \$18.07 |
|---|------|---|------|---------|------|---------|

Mobilization

| | | | | | | |
|-----------------------------------|------|--|------|----------|---|----------|
| Mobilization, small equipment | 1138 | Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds. | Each | \$174.49 | 1 | \$174.49 |
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds. | Each | \$259.43 | 2 | \$518.86 |

Practice: 580 - Streambank and Shoreline Protection**Scenario: #2 - Bioengineered****Scenario Description:**

Protection of streambanks consisting of a bioengineered technique comprised of non-structural measures such as earth revetments and benches with vegetative measures to stabilize and protect the streambank against scour and erosion. Soil bioengineering is a system of living plant materials used as structural components. Adapted types of woody vegetation (shrubs and trees) are initially installed in specified configurations that offer immediate soil protection and reinforcement. In addition, soil bioengineering systems create resistance to sliding or shear displacement in a streambank as they develop roots or fibrous inclusions. Environmental benefits derived from woody vegetation include diverse and productive riparian habitats, shade, organic additions to the stream, cover for fish, and improvements in aesthetic value and water quality. Under certain conditions, soil bioengineering installations work well in conjunction with structures to provide more permanent protection and healthy function, enhance aesthetics, and create a more environmentally acceptable product. Soil bioengineering systems normally use unrooted plant parts in the form of cut branches and rooted plants. For streambanks, living systems include brushmattresses, live stakes, joint plantings, vegetated geogrids, branchpacking, and live fascines.

The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species. Payment cost include shaping bank, critical area vegetation, livestake, rootwads and revetments: a 6-foot high bank at 3(H):1(V) slope for 1000 linear feet (0.46 acres) is used for estimation purposes.

Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation.

Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484 - Mulching; 570 - Stormwater runoff control

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has moderately degraded streambanks that are unstable and show signs of active erosion.

Soil Erosion: The streambank is unstable.

Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures.

Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream.

Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stable against further erosion and encourages natural sediment transport and deposition. Loss of riparian areas and sediment load is reduced in the stream.

For Soil Erosion: The streambank is stable.

For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat.

For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized.

For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Scenario Feature Measure: Square Feet of Streambank/Shoreline Protected

Scenario Unit: Square Foot

Scenario Typical Size: 20,000

Scenario Cost: \$27,360.19

Scenario Cost/Unit: \$1.37

Cost Details (by category):

| Component Name | ID | Component Description | Unit | Price (\$/unit) | Quantity | Cost |
|--|-----|--|------------|-----------------|----------|------------|
| Equipment/Installation | | | | | | |
| Dozer, 80 HP | 929 | Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included. | Hour | \$68.19 | 16 | \$1,091.04 |
| Hydraulic Excavator, .5 CY | 930 | Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included. | Hour | \$56.82 | 32 | \$1,818.24 |
| Seeding Operation, Broadcast, Ground | 959 | Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs. | Acre | \$12.13 | 0.46 | \$5.58 |
| Excavation, Common Earth, side cast, small equipment | 48 | Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor. | Cubic yard | \$2.36 | 2500 | \$5,900.00 |

Labor

| | | | | | | |
|----------------------------|-----|--|------|---------|-----|------------|
| Supervisor or Manager | 234 | Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc. | Hour | \$42.74 | 80 | \$3,419.20 |
| Equipment Operators, Light | 232 | Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers | Hour | \$22.43 | 48 | \$1,076.64 |
| Equipment Operators, Heavy | 233 | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons. | Hour | \$37.38 | 32 | \$1,196.16 |
| General Labor | 231 | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. | Hour | \$22.22 | 384 | \$8,532.48 |

Materials

| | | | | | | |
|--|------|--|------|---------|------|------------|
| Tree, willow | 1426 | Willow tree for planting, 18" to 36" seedling. Includes materials and shipping only. | Each | \$0.67 | 5000 | \$3,350.00 |
| One Species, Cool Season, Annual Grass or Legume | 2311 | Cool season annual grass or legume. Includes material and shipping only. | Acre | \$39.29 | 0.46 | \$18.07 |

Mobilization

| | | | | | | |
|--------------------------------|------|--|------|----------|---|----------|
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds. | Each | \$259.43 | 3 | \$778.29 |
| Mobilization, small equipment | 1138 | Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds. | Each | \$174.49 | 1 | \$174.49 |

Practice: 580 - Streambank and Shoreline Protection**Scenario: #3 - Structural, >5 ft bank****Scenario Description:**

Protection of streambanks using structural measures such as riprap, concrete block, gabions, etc. to stabilize and protect banks of streams or excavated channels against scour and erosion. Additional structural measures may also include tree revetments; log, rootwad and boulder revetments; dormant post plantings; piling revetments with wire or geotextile fencing; piling revetments with slotted fencing; jacks or jack fields; rock riprap; stream jetties; stream barbs; and gabions.

The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species. Payment cost include shaping bank, critical area vegetation, geotextile, and rock rip rap; a 6-foot high bank at 3(H):1(V) slope for 1000 linear feet (0.46 acres) is used for estimation purposes. The rock toe will be 3' thick and 5' high. The bank above the riprap will be graded to a stable slope and revegetated.

Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation.

Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484 - Mulching; 570 - Stormwater runoff control

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has severely degraded streambanks that are unstable and show signs of active erosion.

Soil Erosion: The streambank is unstable.

Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures.

Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream.

Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stable against further erosion and encourages natural sediment transport and deposition. Loss of riparian areas and sediment load is reduced in the stream.

For Soil Erosion: The streambank is stable.

For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat.

For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized.

For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Scenario Feature Measure: Cubic Yards of Material

Scenario Unit: Cubic Yard

Scenario Typical Size: 1,667

Scenario Cost: \$185,458.35

Scenario Cost/Unit: \$111.25

Cost Details (by category):

| Component Name | ID | Component Description | Unit | Price (\$/unit) | Quantity | Cost |
|---|------|--|------------|-----------------|----------|-------------|
| Equipment/Installation | | | | | | |
| Excavation, common earth, wet, side cast, large equipment | 1228 | Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor. | Cubic Yard | \$4.27 | 3500 | \$14,945.00 |
| Hydraulic Excavator, 1 CY | 931 | Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included. | Hour | \$115.72 | 33 | \$3,818.76 |
| Dozer, 80 HP | 929 | Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included. | Hour | \$68.19 | 48 | \$3,273.12 |
| Earthfill, Roller Compacted | 49 | Earthfill, roller or machine compacted, includes equipment and labor | Cubic yard | \$4.39 | 2500 | \$10,975.00 |
| Seeding Operation, Broadcast, Ground | 959 | Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs. | Acre | \$12.13 | 0.12 | \$1.46 |
| Water management, Flooding & dewatering | 969 | Includes equipment, power unit and labor costs. | Acre Foot | \$239.45 | 60 | \$14,367.00 |

Labor

| | | | | | | |
|----------------------------|-----|--|------|---------|-----|------------|
| General Labor | 231 | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. | Hour | \$22.22 | 352 | \$7,821.44 |
| Equipment Operators, Heavy | 233 | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons. | Hour | \$37.38 | 48 | \$1,794.24 |
| Supervisor or Manager | 234 | Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc. | Hour | \$42.74 | 80 | \$3,419.20 |

Materials

| | | | | | | |
|--|------|---|------------|---------|------|--------------|
| Rock Riprap, Placed with geotextile | 44 | Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place | Cubic yard | \$62.26 | 1667 | \$103,787.42 |
| Steel, rebar | 1832 | Steel rebar, grade 60. Materials only. | Pound | \$0.53 | 5280 | \$2,798.40 |
| One Species, Cool Season, Annual Grass or Legume | 2311 | Cool season annual grass or legume. Includes material and shipping only. | Acre | \$39.29 | 0.46 | \$18.07 |

Mobilization

| | | | | | | |
|---|------|---|--------|----------|-------|-------------|
| Mobilization, Material, distance > 50 miles | 1043 | Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i | Dollar | \$1.03 | 17000 | \$17,510.00 |
| Mobilization, small equipment | 1138 | Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds. | Each | \$174.49 | 1 | \$174.49 |
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds. | Each | \$259.43 | 1 | \$259.43 |
| Mobilization, large equipment | 1140 | Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits. | Each | \$495.32 | 1 | \$495.32 |

Practice: 580 - Streambank and Shoreline Protection**Scenario: #4 - Structural small, banks less than 4 ft****Scenario Description:**

Protection of streambanks using structural measures such as riprap, concrete block, gabions, etc. to stabilize and protect banks of streams or excavated channels against scour and erosion. Additional structural measures may also include tree revetments; log, rootwad and boulder revetments; dormant post plantings; piling revetments with wire or geotextile fencing; piling revetments with slotted fencing; jacks or jack fields; rock riprap; stream jetties; stream barbs; and gabions.

The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species. Payment cost include shaping bank, critical area vegetation, geotextile, and rock rip rap; a 4-foot high bank at 3(H):1(V) slope for 1000 linear feet (0.21 acres) is used for estimation purposes. The rock toe will be 2' thick and 3' high. The bank above the riprap will be graded to a stable slope and revegetated.

Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation.

Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484 - Mulching; 570 - Stormwater runoff control

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has severely degraded streambanks that are unstable and show signs of active erosion.

Soil Erosion: The streambank is unstable.

Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures.

Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream.

Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stable against further erosion and encourages natural sediment transport and deposition. Loss of riparian areas and sediment load is reduced in the stream.

For Soil Erosion: The streambank is stable.

For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat.

For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized.

For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Scenario Feature Measure: Cubic Yards of Material

Scenario Unit: Cubic Yard

Scenario Typical Size: 800

Scenario Cost: \$91,071.38

Scenario Cost/Unit: \$113.84

Cost Details (by category):

| Component Name | ID | Component Description | Unit | Price (\$/unit) | Quantity | Cost |
|---|------|--|------------|-----------------|----------|------------|
| Equipment/Installation | | | | | | |
| Excavation, common earth, wet, side cast, large equipment | 1228 | Bulk excavation and side casting of wet common earth with hydraulic excavator or dragline with greater than 1 CY capacity. Includes equipment and labor. | Cubic Yard | \$4.27 | 1750 | \$7,472.50 |
| Earthfill, Roller Compacted | 49 | Earthfill, roller or machine compacted, includes equipment and labor | Cubic yard | \$4.39 | 1750 | \$7,682.50 |
| Dozer, 80 HP | 929 | Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included. | Hour | \$68.19 | 24 | \$1,636.56 |
| Seeding Operation, Broadcast, Ground | 959 | Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs. | Acre | \$12.13 | 0.21 | \$2.55 |
| Water management, Flooding & dewatering | 969 | Includes equipment, power unit and labor costs. | Acre Foot | \$239.45 | 30 | \$7,183.50 |

Labor

Labor

| | | | | | | |
|----------------------------|-----|--|------|---------|-----|------------|
| General Labor | 231 | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. | Hour | \$22.22 | 224 | \$4,977.28 |
| Equipment Operators, Heavy | 233 | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons. | Hour | \$37.38 | 24 | \$897.12 |
| Supervisor or Manager | 234 | Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc. | Hour | \$42.74 | 60 | \$2,564.40 |

Materials

| | | | | | | |
|--|------|---|------------|---------|------|-------------|
| One Species, Cool Season, Annual Grass or Legume | 2311 | Cool season annual grass or legume. Includes material and shipping only. | Acre | \$39.29 | 0.21 | \$8.25 |
| Rock Riprap, Placed with geotextile | 44 | Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place | Cubic yard | \$62.26 | 800 | \$49,808.00 |

Mobilization

| | | | | | | |
|---|------|---|--------|----------|------|------------|
| Mobilization, small equipment | 1138 | Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds. | Each | \$174.49 | 1 | \$174.49 |
| Mobilization, Material, distance > 50 miles | 1043 | Mobilization cost of materials for special cases where the distance from the supplier delivery point to the job site exceeds 50 miles. The costs for shipping by UPS or bulk freight shipping to a location within 50 miles of the job site have already been i | Dollar | \$1.03 | 8160 | \$8,404.80 |
| Mobilization, medium equipment | 1139 | Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds. | Each | \$259.43 | 1 | \$259.43 |

Practice: 580 - Streambank and Shoreline Protection**Scenario: #5 - Geotextile Wrapped****Scenario Description:**

Protection of streambanks using geotextile wrapped soil lifts and native vegetation. Coir fabric and coir logs are placed on the constructed bench to form the bankline. The coir logs are then tied into the existing bankline at either end. The soil lifts include a woven inner fabric that helps prevent fine sediments from washing out and a heavier outer fabric that provides structural support. The structure is filled with soil to the height of the coir log. Coir fabric is then pulled over the coir log and soil and wooden wedge stakes are placed to secure the fabric along the back edge. Soil and willow cuttings are placed between the lift layers and the process is repeated. Willow cuttings are placed on the top lift and a final layer of soil is placed to the height of the bank. The top layer is then seeded with a mix of native grasses and forbs. The purpose of this practice is to maintain, improve, or restore physical, chemical, and biological functions of a stream to provide diverse aquatic communities to improve habitat for desired aquatic species.

Resource Concerns: Soil Erosion - Excessive Bank Erosion from Streams, Shoreline and Water Conveyance Channels; Water Quality Degradation - Excessive Sediment in Surface Waters; Water Quality Degradation - Elevated Water Temperature; Excess/Insufficient Water - Excessive Sediment in Surface Waters; Inadequate Habitat for Fish and Wildlife- Habitat Degradation.

Associated Practices include: 560 - Access Road; 342 - Critical Area Planting; 382 - Fence; 391 - Riparian Forest Buffer; 390 - Riparian Herbaceous Cover; 395 - Stream Habitat Improvement and Management; 614 - Watering Facility; 484 - Mulching; 570 - Stormwater runoff control

Before Situation:

A stream bisects the agricultural property and has had all of the woody vegetation removed due to overgrazing or human manipulation; the stream has severely degraded streambanks that are unstable and show signs of active erosion.

Soil Erosion: The streambank is unstable.

Water Quality Degradation: The sediment load has increased in the stream resulting in elevated water temperatures.

Excess/Insufficient Water: The excessive sediment load has reduced the water conveyance capacity, storage capacity and flow within the stream.

Inadequate Habitat for Fish and Wildlife: The deficiencies in the stream's habitat limit survival, growth, reproduction, and/or diversity of aquatic organisms within the stream.

After Situation:

The streambank is stable against further erosion and encourages natural sediment transport and deposition. Loss of riparian areas and sediment load is reduced in the stream.

For Soil Erosion: The streambank is stable.

For Water Quality Degradation: The sediment load has decreased in the stream resulting in improved aquatic habitat.

For Excess/Insufficient Water: The water conveyance capacity, storage capacity and flow within the stream has been stabilized.

For Inadequate Habitat for Fish and Wildlife: The reduction in the sediment load promotes survival, growth, reproduction, and/or diversity of aquatic organisms within the stream's habitat.

Scenario Feature Measure: Square Foot of Streambank

Scenario Unit: Square Foot

Scenario Typical Size: 1,500

Scenario Cost: \$47,031.94

Scenario Cost/Unit: \$31.35

Cost Details (by category):

| Component Name | ID | Component Description | Unit | Price (\$/unit) | Quantity | Cost |
|--|-----|--|------------|-----------------|----------|-------------|
| Equipment/Installation | | | | | | |
| Hydraulic Excavator, 1 CY | 931 | Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included. | Hour | \$115.72 | 32 | \$3,703.04 |
| Seeding Operation, Broadcast, Ground | 959 | Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs. | Acre | \$12.13 | 0.25 | \$3.03 |
| Earthfill, Dumped and Spread | 51 | Earthfill, dumped and spread without compaction effort, includes equipment and labor | Cubic yard | \$3.61 | 193 | \$696.73 |
| Earthfill, Roller Compacted | 49 | Earthfill, roller or machine compacted, includes equipment and labor | Cubic yard | \$4.39 | 2923 | \$12,831.97 |
| Excavation, Common Earth, side cast, small equipment | 48 | Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor. | Cubic yard | \$2.36 | 2923 | \$6,898.28 |

Labor

Labor

| | | | | | | |
|----------------------------|-----|--|------|---------|----|------------|
| Supervisor or Manager | 234 | Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc. | Hour | \$42.74 | 16 | \$683.84 |
| Equipment Operators, Heavy | 233 | Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons. | Hour | \$37.38 | 32 | \$1,196.16 |
| General Labor | 231 | Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. | Hour | \$22.22 | 64 | \$1,422.08 |

Materials

| | | | | | | |
|---|------|---|-------------|------------|------|-------------|
| Mulching, straw or hay | 1214 | Use of straw or hay for temporary ground cover. Includes application and methods necessary to keep in place such as tacking or crimping. Includes materials, equipment and labor. | Acre | \$3,733.92 | 0.25 | \$933.48 |
| Aggregate, Gravel, Graded | 46 | Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel. | Cubic yard | \$35.94 | 30 | \$1,078.20 |
| Cuttings, woody, medium size | 1308 | Woody cuttings, live stakes or whips typically 1/4" to 1" diameter and 24" to 48" long. Includes materials and shipping only. | Each | \$0.49 | 6300 | \$3,087.00 |
| Rock Riprap, graded, angular, material and shipping | 1200 | Graded Rock Riprap for all gradation ranges. Includes materials and delivery only. | Ton | \$24.54 | 462 | \$11,337.48 |
| Geotextile, non-woven, light weight | 1209 | Non-woven less than 8 ounce/square yard geotextile with staple anchoring. Materials and shipping only. | Square Yard | \$1.13 | 2350 | \$2,655.50 |
| One Species, Cool Season, Annual Grass or Legume | 2311 | Cool season annual grass or legume. Includes material and shipping only. | Acre | \$39.29 | 0.25 | \$9.82 |

Mobilization

| | | | | | | |
|-------------------------------|------|--|------|----------|---|----------|
| Mobilization, large equipment | 1140 | Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits. | Each | \$495.32 | 1 | \$495.32 |
|-------------------------------|------|--|------|----------|---|----------|