Scenario: #1 - Lop and Scatter, light

# **Scenario Description:**

Treating an area of forest slash or following a juniper chaining to reduce hazardous fuels and the risk of insect and disease, improve organic matter and reduce erosion while improving water quality. Typically done by hand and light equipment. Resource concerns include: Wildfire hazard from excessive biomass accumulation and potential Excessive plant pest pressure.

## **Before Situation:**

Woody material resulting from a silvicultural practice such as pruning or a light thinning operation is causing both fire hazard and pest issues. Up to 100 trees and/or slash per acre needing treatment, or majority of small (less than 3 inches) material.

## **After Situation:**

Fire and pest issues are reduced with slash spread out and in contact with the ground. Additional benefits include reduced soil movement. The soil is protected and/or enhanced.

Scenario Feature Measure: Acres treated

Scenario Unit: Acres

Scenario Typical Size: 40

Scenario Cost: \$2,168.24 Scenario Cost/Unit: \$54.21

Cost Details (by category): Price **Component Name Component Description** Unit **Quantity Cost** (\$/unit) Equipment/Installation Chainsaw 937 Equipment and power unit costs. Labor not included. Hour \$6.76 72 \$486.72 Truck, Pickup 939 Equipment and power unit costs. Labor not included. Hour \$39.91 \$319.28 Labor General Labor \$18.92 72 231 Labor performed using basic tools such as power tool, Hour \$1,362.24 shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.

Practice: 384 - Woody Residue Treatment Scenario: #2 - Lop and Scatter, medium

# **Scenario Description:**

Treating an area of forest slash or following a juniper chaining to reduce hazardous fuels and the risk of insect and disease, improve organic matter and reduce erosion while improving water quality. Typically done by hand and light equipment. Resource concerns include: Wildfire hazard from excessive biomass accumulation and potential Excessive plant pest pressure.

## **Before Situation:**

Woody material resulting from a silvicultural practice such as pruning or a light thinning operation is causing both fire hazard and pest issues. Up to 100-300 trees and/or slash per acre needing treatment, or majority of 3-6 inch material.

## **After Situation:**

Fire and pest issues are reduced with slash spread out and in contact with the ground. Additional benefits include reduced soil movement. The soil is protected and/or enhanced.

Scenario Feature Measure: Acres treated

Scenario Unit: Acres

Scenario Typical Size: 40

Scenario Cost: \$3,606.32 Scenario Cost/Unit: \$90.16

Cost Details (by category): Price **Component Name Component Description** Unit **Quantity Cost** (\$/unit) Equipment/Installation Chainsaw 937 Equipment and power unit costs. Labor not included. Hour \$6.76 128 \$865.28 Truck, Pickup 939 Equipment and power unit costs. Labor not included. Hour \$39.91 \$319.28 Labor General Labor \$18.92 128 231 Labor performed using basic tools such as power tool, Hour \$2,421.76 shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.

Scenario: #3 - Lop and Scatter, heavy

# **Scenario Description:**

Treating an area of forest slash or following a juniper chaining to reduce hazardous fuels and the risk of insect and disease, improve organic matter and reduce erosion while improving water quality. Typically done by hand and light equipment. Resource concerns include: Wildfire hazard from excessive biomass accumulation and potential Excessive plant pest pressure.

## **Before Situation:**

Woody material resulting from a silvicultural practice such as pruning or a light thinning operation is causing both fire hazard and pest issues. Greater than 300 trees and/or slash per acre needing treatment, or majority of greater than 6 inch material.

## **After Situation:**

Fire and pest issues are reduced with slash spread out and in contact with the ground. Additional benefits include reduced soil movement. The soil is protected and/or enhanced.

Scenario Feature Measure: Acres treated

Scenario Unit: Acres

Scenario Typical Size: 40

Scenario Cost: \$5,455.28 Scenario Cost/Unit: \$136.38

Cost Details (by category): Price **Component Name Component Description** Unit **Quantity Cost** (\$/unit) Equipment/Installation Truck, Pickup 939 Equipment and power unit costs. Labor not included. Hour \$39.91 8 \$319.28 Chainsaw 937 Equipment and power unit costs. Labor not included. Hour \$6.76 200 \$1,352.00 Labor General Labor \$18.92 200 \$3,784.00 231 Labor performed using basic tools such as power tool, Hour shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.

Scenario: #4 - Piling and Burning

# **Scenario Description:**

Reducing woody waste created during forestry, agroforestry and horticultural activities by gathering, piling, and burning (under appropriate weather conditions) to remove piles to achieve management objectives. Does not include transport from property to a commercial facility. Resource concerns include reducing potential Excessive plant pest pressure, and Wildfire hazard from excessive biomass accumulation.

## **Before Situation:**

Woody residue causes management issues including resource access, fire hazard and sites for harboring pests.

## **After Situation:**

Fire and pest issues are reduced.

Scenario Feature Measure: Acres treated

Scenario Unit: Acres

Scenario Typical Size: 20

Scenario Cost: \$3,151.74 Scenario Cost/Unit: \$157.59

Cost Details (by category): Price **Component Name Component Description** Unit **Quantity Cost** (\$/unit) Equipment/Installation Log skidder 942 Equipment and power unit costs. Labor not included. Hour \$137.90 10 \$1,379.00 Chainsaw 937 Equipment and power unit costs. Labor not included. Hour \$6.76 40 \$270.40 Labor Equipment Operators, Light 232 Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Hour \$19.19 10 \$191.90 Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers \$18.92 \$756.80 General Labor Hour 40 231 Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. Mobilization \$276.82 1139 Equipment with 70-150 HP or typical weights between \$553.64 Mobilization, medium Each 2 14,000 and 30,000 pounds. equipment

Practice: 384 - Woody Residue Treatment Scenario: #5 - Chipping and hauling off-site

# **Scenario Description:**

Reducing woody waste created during forestry, agroforestry and horticultural activities by gathering, chipping, and hauling off site to achieve management objectives. Does not include transport from property to a commercial facility. Resource concerns include potential Emissions of particulate matter, potential Excessive plant pest pressure, and Wildfire hazard from excessive biomass accumulation.

## **Before Situation:**

Woody residue causes management issues including resource access, fire hazard and sites for harboring pests.

# **After Situation:**

Fire and pest issues are reduced. Air and energy resources are conserved.

Scenario Feature Measure: Acres treated

Scenario Unit: Acres

**Scenario Typical Size:** 20

Scenario Cost: \$5,013.42 Scenario Cost/Unit: \$250.67

Cost Details (by category): Price **Component Name Component Description** Unit **Quantity Cost** (\$/unit) Equipment/Installation \$137.90 Log skidder 942 Equipment and power unit costs. Labor not included. Hour 10 \$1,379.00 Chainsaw 937 Equipment and power unit costs. Labor not included. Hour \$6.76 10 \$67.60 Brush Chipper, 6" capacity 938 Brush Chipper, 6" capacity, typically 35 HP. Includes \$23.73 30 \$711.90 Hour chipper and power unit. Labor not included. Truck, dump, 8 CY 1401 Dump truck for moving bulk material. Typically capacity is Hour \$62.55 20 \$1,251.00 12 ton or 8 cubic yards. Includes equipment only. Labor \$191.90 Equipment Operators, Light 232 Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Hour \$19.19 10 Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers General Labor 231 Labor performed using basic tools such as power tool, \$18.92 60 \$1,135.20 Hour shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc. Mobilization \$276.82 Mobilization, medium 1139 Equipment with 70-150 HP or typical weights between Each \$276.82 1 14,000 and 30,000 pounds. equipment

Practice: 384 - Woody Residue Treatment
Scenario: #6 - Forest Slash Treatment - Heavy

# **Scenario Description:**

Treating an area of significant woody plant residues to reduce hazardous fuels and the risk of insect and disease, improve organic matter, decrease unwanted habitat, and reduce erosion while improving water quality. Slash is to be lopped/treated/crushed within a foot of the ground or moved off site to meet state fire hazard reduction standards. Typically heavy equipment are used such as masticators, mulchers, drum choppers, etc. Hand work with chainsaws are used on steep slopes. Resource concerns include potential Emission of particulate matter, Wildfire hazard from excessive biomass accumulation, Excessive plant pest pressure, and Habitat degradation.

## **Before Situation:**

Heavy woody material (difficult to walk through) resulting from silvicultural/management operations caused both fire hazard, access, potential harm to humans and animals, and pest issues.

#### After Situation

Fire, access, and pest issues are reduced with slash spread out and in contact with the ground. An additional benefit is reduced soil movement.

Scenario Feature Measure: Acres treated

Scenario Unit: Acres

Scenario Typical Size: 40

Scenario Cost: \$17,677.75 Scenario Cost/Unit: \$441.94

<b>Cost Details (by category</b>	):			Price		
Component Name	ID	Component Description	Unit	(\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$39.91	40	\$1,596.40
Mechanical cutter, chopper		Masticator, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$137.90	40	\$5,516.00
Heavy mechanical site prep, drum chopping		Mechanical operations that pushing trees and vegetation and crushing them with a water filled roller chopper. Requires heavy equipment such as dozers. Includes equipment, power unit and labor costs.	Acre	\$161.02	40	\$6,440.80
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.76	40	\$270.40
Labor						
General Labor		Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.92	80	\$1,513.60
Equipment Operators, Light		Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$19.19	80	\$1,535.20
Mobilization						
Mobilization, medium equipment		Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$276.82	1	\$276.82
Mobilization, large equipment		Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$528.53	1	\$528.53

Scenario: #7 - Restoration/conservation treatment following catastrophic events

# **Scenario Description:**

The use of a combination of hand (chainsaw) and heavy equipment similar to those used in logging to treat slash resulting from catastrophic events such as fire, wind, severe pest outbreak, ice storm, etc. This scenario will remove/treat the larger material the size of which is consistent with the large equipment used. Resource concerns include: Excessive plant pest pressure, Potential emissions of particulate matter, Wildfire hazard from excessive biomass accumulation, and Habitat degradation.

# **Before Situation:**

A large amount of slash and woody residue is created as a result of a non-silvicultural event such as a wind storm, wildfire, ice storm, pest outbreak, etc. Because the slash and residue is created by a catastrophic event that can cause tree-lodging, snags, broken tops, etc.; treatment is both difficult and dangerous. The presence of this material causes adverse effects on the forest include limiting access for management purposes, increasing the wildfire hazard, increasing the risk of potential harm to humans and livestock, and providing harboring sites for pests.

# **After Situation:**

The material resulting from the catastrophic event is reduced to a level that will minimize the resource concerns.

**Scenario Feature Measure:** Acres of affected forest

Scenario Unit: Acres

Scenario Typical Size: 20

Scenario Cost: \$15,964.44 Scenario Cost/Unit: \$798.22

Cost Details (by category	<b>/</b> ):			Price		
Component Name	ID	Component Description	Unit	(\$/unit)	Quantity	Cost
Equipment/Installation						
Log skidder	942	Equipment and power unit costs. Labor not included.	Hour	\$137.90	40	\$5,516.00
Truck, dump, 8 CY		Dump truck for moving bulk material. Typically capacity is 12 ton or 8 cubic yards. Includes equipment only.	Hour	\$62.55	40	\$2,502.00
Track Loader, 95HP	935	Equipment and power unit costs. Labor not included.	Hour	\$95.08	40	\$3,803.20
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.76	80	\$540.80
Labor				·		
General Labor		Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.92	80	\$1,513.60
Equipment Operators, Light		Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$19.19	80	\$1,535.20
Mobilization						
Mobilization, medium equipment		Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$276.82	2	\$553.64

Scenario: #8 - Orchard/Vineyard prunings/removals

# **Scenario Description:**

Slash created from orchard/vineyard prunings is chipped or mulched and removed from the site in order to accomplish one or more purposes: reducing wildfire fuels and insect/disease substrate; improving access; and/or reducing potential risk to livestock and humans. Air emission reductions are achieved by chipping or shredding the materials in lieu of burning them. Material may be incorporated in the soil, used as a dust suppressant on unpaved roads or traffic areas. Resource concerns include Wildfire hazard from excessive biomass accumulation and Emissions of particulate matter.

## **Before Situation:**

Wood waste is either burned, creating an air quality issue, or left in place creating a wildfire hazard, an impediment to access, or a potential site for harboring pests. Energy conservation was not implemented.

## **After Situation:**

Treatment of pruning residue results in the reduction in air pollutants, energy conservation occurred, improvement in access, and the reduction of sites that can harbor pests.

Scenario Feature Measure: Acres of orchard/vineyard with slash created from pruning

Scenario Unit: Acre

Scenario Typical Size: 20

Scenario Cost: \$4,414.05 Scenario Cost/Unit: \$220.70

<b>Cost Details (by category</b>	):			Price		
Component Name	ID	Component Description	Unit	(\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, dump, 8 CY	1401	Dump truck for moving bulk material. Typically capacity is 12 ton or 8 cubic yards. Includes equipment only.	Hour	\$62.55	16	\$1,000.80
Brush Chipper, 6" capacity		Brush Chipper, 6" capacity, typically 35 HP. Includes chipper and power unit. Labor not included.	Hour	\$23.73	16	\$379.68
Skidsteer, 80 HP		Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$46.33	16	\$741.28
Labor						
Equipment Operators, Light		Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$19.19	48	\$921.12
General Labor		Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.92	48	\$908.16
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$276.82	1	\$276.82
Mobilization, small equipment		Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$186.19	1	\$186.19

Scenario: #9 - Woody residue/silvicultural slash treatment- light

# **Scenario Description:**

Treating an area of forest slash to reduce hazardous fuels and the risk of insect and disease, improve organic matter and reduce erosion while improving water quality. Slash is treated with both hand (cutting, lopping, etc.) and mechanically (masticating, chipping, etc.). Typically done by hand and light equipment. Resource concerns include: Wildfire hazard from excessive biomass accumulation and potential Excessive plant pest pressure.

# **Before Situation:**

Woody material resulting from a silvicultural practice such as pruning or a light thinning operation is causing both fire hazard and pest issues.

# **After Situation:**

Fire and pest issues are reduced with slash spread out and in contact with the ground. Additional benefits include reduced soil movement. The soil is protected and/or enhanced.

Scenario Feature Measure: Acres treated

Scenario Unit: Acres

Scenario Typical Size: 40

Scenario Cost: \$9,336.59 Scenario Cost/Unit: \$233.41

<b>Cost Details (by category</b>	):			Price		
Component Name	ID	Component Description	Unit	(\$/unit)	Quantity	Cost
Equipment/Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$39.91	40	\$1,596.40
Mechanical cutter, chopper		Masticator, flail shredder, hydro axe, brush cutter, etc. Equipment and power unit costs. Labor not included.	Hour	\$137.90	40	\$5,516.00
Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$6.76	20	\$135.20
Labor	•			·		
General Labor		Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.92	60	\$1,135.20
Equipment Operators, Light		Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$19.19	40	\$767.60
Mobilization						
Mobilization, small equipment		Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$186.19	1	\$186.19