Practice: 607 - Surface Drainage, Field Ditch

Scenario: #1 - Field Drainage Ditch

Scenario Description:

This scenario is the construction of a surface drain, field ditch. Typical construction dimensions are 4' bottom x 2.5' deep x 1320' length with a side slope of 3:1. Excess water is either reused in an Irrigation System, Tailwater Recovery (447) system, or conveyed to a receiving water body.

Resource concerns: Excess/Insufficient Water - Inefficient Use of Irrigation Water and Water Quality Degradation - Excessive Sediment in Surface Waters.

Associated Conservation Practices: 608-Surface Drain, Main or Lateral; 587 -Structure For Water Control; 554 - Drainage Water Management

Before Situation:

Excess water has no outlet and backs up into the fields causing damage or loss of the crop.

After Situation:

An earthen ditch that follows the natural slope of the land at the low end of the field will be constructed to carry excess water to an outlet.

Scenario Feature Measure: Volume of Earth Excavated

Scenario Unit: Cubic Yard

Scenario Typical Size: 1,406

Scenario Cost: $3,592.12 **Scenario Cost/Unit:** $2.55

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price ($/unit)	Quantity	Cost
Equipment/Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	$2.29	1406	$3,219.74
Mobilization						
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	$186.19	2	$372.38