

Practice: 606 - Subsurface Drain

Scenario: #1 - Corrugated Plastic Pipe (CPP), Single-Wall, = 6 inch

Scenario Description: Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline, using a drainage plow. HDPE (CPP) Single-Wall is manufactured in sizes (nominal diameter) from 3-inch to 24-inch; typical practice sizes range from 3-inch to 12-inch; and typical scenario size is 5-inch. Construct 2,000 feet of 5-inch, Single-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth 5 feet. The unit is in feet of pipe. The typical number of mainline connections for 2,000 feet of subsurface drainline is a total of 3 each. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management.

Before Situation: Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.).

After Situation: The drainage modifications result in reduced plant stress due to excessive wetness caused by a seasonal high water table, or improved drainage water quality due to system retrofit enabling drainage water management.

Scenario Feature Measure: Feet of Pipe

Scenario Unit: Foot

Scenario Typical Size: 2000

Total Scenario Cost: \$7,590.80

Scenario Cost/Unit: \$3.80

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$471.90	2	\$943.80
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$247.16	2	\$494.33

Materials

Drainage Lateral Connection	1458	Connect 3"-6" drainage lateral to main drain, includes excavation to 6' depth, install tee on main line, connect lateral, and backfill. Includes material cost for tee.	Each	\$28.47	3	\$85.41
Pipe, HDPE, 5", PCPT, Single Wall	1271	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 5" diameter - ASTM F405. Material cost only.	Foot	\$0.71	2000	\$1,426.27

Equipment Installation

Trenching, tile line plowing, earth, 60"	1457	Plowing in 3"-15" CPP drain line into earth, 60" depth, includes equipment and labor for trenching, laying, and backfilling.	Foot	\$2.32	2000	\$4,641.00
--	------	--	------	--------	------	------------

Practice: 606 - Subsurface Drain

Scenario: #2 - Enveloped Corrugated Plastic Pipe (CPP), Single-Wall, = 6 inch

Scenario Description: Description: Below ground installation of perforated HDPE (Corrugated Plastic Pipe) pipeline with Sand-Gravel envelope, using a drainage trencher. HDPE (CPP) Single-Wall is manufactured in sizes (nominal diameter) from 3-inch to 24-inch; typical practice sizes range from 3-inch to 12-inch; and typical scenario size is 5-inch. Construct 2,000 feet of 5-inch, Single-Wall, perforated HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth of 5 feet, and surrounded with a sand-gravel envelope. The unit is in feet of pipe. The typical volume sand-gravel for 2,000 feet of 12"wide x 12" high envelope is 64 cubic yards. The typical number of mainline connections for 2,000 feet of subsurface drainline is a total of 3 each. Resource Concerns: Excess Water (seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management.

Before Situation: Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.).

After Situation: The drainage modifications result in reduced plant stress due to excessive wetness caused by a seasonal high water table, or improved drainage water quality due to system retrofit enabling drainage water management.

Scenario Feature Measure: Weight of Pipe

Scenario Unit: Foot

Scenario Typical Size: 2000

Total Scenario Cost: \$9,209.39

Scenario Cost/Unit: \$4.60

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Materials

Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$23.39	64	\$1,496.68
Drainage Lateral Connection	1458	Connect 3"-6" drainage lateral to main drain, includes excavation to 6' depth, install tee on main line, connect lateral, and backfill. Includes material cost for tee.	Each	\$28.47	3	\$85.41
Pipe, HDPE, 5", PCPT, Single Wall	1271	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 5" diameter - ASTM F405. Material cost only.	Foot	\$0.71	2000	\$1,426.27

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$39.75	8	\$318.01
----------------------------	-----	---	------	---------	---	----------

Equipment Installation

Track Loader, 95HP	935	Equipment and power unit costs. Labor not included.	Hour	\$85.18	8	\$681.41
Trenching, Earth, 12" x 60"	1459	Trenching, earth, 12" wide x 60" depth, includes equipment and labor for trenching, laying 3"-6" CPP drain line with envelope, and backfilling.	Foot	\$1.88	2000	\$3,763.50

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$471.90	2	\$943.80
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$247.16	2	\$494.33

Practice: 606 - Subsurface Drain

Scenario: #3 - Corrugated Plastic Pipe (CPP), Single-Wall, = 8 inch

Scenario Description: Description: Below ground installation of HDPE (Corrugated Plastic Pipe) pipeline, using a drainage plow. HDPE (CPP) Single-Wall is manufactured in sizes (nominal diameter) from 3-inch to 24-inch; typical practice sizes range from 3-inch to 12-inch; and typical scenario size is 10-inch. Construct 1,000 feet of 10-inch, Single-Wall, HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth 5 feet. The unit is in feet of pipe. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 607 - Surface Drain, Field Ditch; 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management.

Before Situation: Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.).

After Situation: The drainage modifications result in reduced plant stress due to excessive wetness caused by a seasonal high water table, or improved drainage water quality due to system retrofit enabling drainage water management.

Scenario Feature Measure: Feet of Pipe

Scenario Unit: Foot

Scenario Typical Size: 1000

Total Scenario Cost: \$7,239.50

Scenario Cost/Unit: \$7.24

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$471.90	2	\$943.80
-------------------------------	------	--	------	----------	---	----------

Materials

Pipe, HDPE, 10", PCPT, Single Wall	1273	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 10" diameter - ASTM F667. Material cost only.	Foot	\$3.98	1000	\$3,975.20
------------------------------------	------	---	------	--------	------	------------

Equipment Installation

Trenching, tile line plowing, earth, 60"	1457	Plowing in 3"-15" CPP drain line into earth, 60" depth, includes equipment and labor for trenching, laying, and backfilling.	Foot	\$2.32	1000	\$2,320.50
--	------	--	------	--------	------	------------

Practice: 606 - Subsurface Drain

Scenario: #4 - Corrugated Plastic Pipe (CPP), Twin-Wall, = 8 inch

Scenario Description: Description: Below ground installation of HDPE (Corrugated Plastic Pipe) pipeline, using a drainage plow. HDPE (CPP) Twin-Wall is manufactured in sizes (nominal diameter) from 4-inch to 60-inch; typical practice sizes range from 8-inch to 15-inch; and typical scenario size is 12-inch. Construct 1,000 feet of 12-inch, Twin-Wall, HDPE Corrugated Plastic Pipe (CPP), installed below ground to a minimum depth 5 feet. The unit is in weight of pipe material in pounds. 1,000 feet of 12-inch, Twin-Wall, HDPE CPP weighs 3.20 lb/ft, or a total of 3,200 pounds. Resource Concerns: Excess Water (Seasonal High Water Table); Degraded Plant Condition; Water Quality Degradation (Nutrients). Associated Practices: 607 - Surface Drain, Field Ditch; 608 - Surface Drain, Main or Lateral; 587 - Structure for Water Control, 533 - Pumping Plant; and 554 - Drainage Water Management.

Before Situation: Before installation soil conditions are excessively wet in the spring due to poor internal soil drainage. Excess soil water is causing crop stress and delay of field operations (seed bed preparation, planting, etc.).

After Situation: The drainage modifications result in reduced plant stress due to excessive wetness caused by a seasonal high water table, or improved drainage water quality due to system retrofit enabling drainage water management.

Scenario Feature Measure: Feet of Pipe

Scenario Unit: Foot

Scenario Typical Size: 1000

Total Scenario Cost: \$12,481.67

Scenario Cost/Unit: \$12.48

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$24.26	16	\$388.24
---------------	-----	--	------	---------	----	----------

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$247.16	2	\$494.33
--------------------------------	------	---	------	----------	---	----------

Equipment Installation

Trenching, Earth, 24" x 60"	1460	Trenching, earth, 24" wide x 60" depth, includes equipment and labor for trenching and backfilling.	Foot	\$3.68	1000	\$3,675.75
-----------------------------	------	---	------	--------	------	------------

Materials

Pipe, HDPE, corrugated double wall, LTE-12", soil tight, weight priced	1587	High Density Polyethylene (HDPE) compound manufactured into double wall corrugated pipe LTE-12" diameter. Materials only.	Pound	\$2.48	3200	\$7,923.36
--	------	---	-------	--------	------	------------

Practice: 606 - Subsurface Drain

Scenario: #5 - Secondary Main Retrofit

Scenario Description: An agricultural field has existing patterned tile system installed at 75 foot spacings. The field is 75 acres in size: 2475' x 1320', with a single main line at the low end of the field (2475'). The laterals are installed perpendicular to the topographic contours. The field has 3.5 feet of fall in the 1/4 mile length of the laterals, so a secondary main will be needed to allow drainage water management to be implemented on the higher half of the field.

Before Situation: The patterned tile drainage system allows free flow of drainage water to a receiving ditch. Drainage water carries nitrogen and phosphorus out of the soil and these nutrients pollute the receiving waters.

After Situation: A 12 inch diameter secondary mainline is retrofitted to the drainage system, located halfway up the field and relatively parallel to the topographic contours. This new mainline is hooked to each individual lateral and continued to a stable outlet. A Drainage Water practice must be completed along with the mainline; typically Structures for Water Control (587) installed at two foot vertical intervals so that water can be retained in the field. This scenario also applies to systems where the secondary main is used to connect drain lines that formerly each exited separately to the ditch, with a structure that distributes the drainage water into the subsurface soil at a vegetated buffer (772) OR a Denitrifying Bioreactor (747) might be installed at the outlet. In combination or singly, one of these practices must be installed with the secondary main.

Scenario Feature Measure: Feet of Pipe

Scenario Unit: Foot

Scenario Typical Size: 3135

Total Scenario Cost: \$24,229.99

Scenario Cost/Unit: \$7.73

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$471.90	1	\$471.90
-------------------------------	------	--	------	----------	---	----------

Materials

Drainage Lateral Connection	1458	Connect 3"-6" drainage lateral to main drain, includes excavation to 6' depth, install tee on main line, connect lateral, and backfill. Includes material cost for tee.	Each	\$28.47	32	\$911.04
Pipe, HDPE, 12", PCPT, Single Wall	1274	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 12" diameter - ASTM F667. Material cost only.	Foot	\$4.97	3135	\$15,572.28

Equipment Installation

Trenching, tile line plowing, earth, 60"	1457	Plowing in 3"-15" CPP drain line into earth, 60" depth, includes equipment and labor for trenching, laying, and backfilling.	Foot	\$2.32	3135	\$7,274.77
--	------	--	------	--------	------	------------