

Practice: 658 - Wetland Creation

Scenario: #1 - Wetland Creation, Wildlife Pond

Scenario Description: A wetland is created on a flat mineral upland at a location where surface runoff may be intercepted and ponded by excavation. Resource concerns are 22 - INDEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

Before Situation: The site is in cropland on an upland, non floodplain site (interfluve).

After Situation: An excavation with an average depth of 12" has created a shallow depression in a broad swale which intercepts surface runoff. The excavated material has been spread on adjacent areas. The INADEQUATE HABITAT FOR FISH AND WILDLIFE resource concern has been addressed with the provision of seasonal open water for terrestrial, aquatic, and waterfowl species.

Scenario Feature Measure: Acres of Wetland

Scenario Unit: Acre

Scenario Typical Size: 5

Total Scenario Cost: \$18,953.74

Scenario Cost/Unit: \$3,790.75

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$2.23	8067	\$18,009.94
--	----	---	------------	--------	------	-------------

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$471.90	2	\$943.80
-------------------------------	------	--	------	----------	---	----------