PracticeName	PracticeCode	Soil Quality Degradation -Organic Matter Depletion - - Organic Matter Depletion	Soil Quality Degradation -Compaction - - Compaction	Soil Quality Degradation -Subsidence - - Subsidence	Soil Quality Degradation -Concentration of Salts or Other Chemicals - - Concentration of Salts or Other Chemicals
Access Control	472	1	4	0	0
Access Road	560	0	2	0	0
Agrichemical Handling Facility	309	0	0	0	0
Air Filtration and Scrubbing	371	0	0	0	0
Alley Cropping	311	5	2	0	1
Amendments for the Treatment of Agricultural Waste	591	1	0	0	0
Anaerobic Digestor, Controlled Temperature	366	0	0	0	0
Animal Mortality Facility	316	0	0	0	0
Animal Trails and Walkways	575	0	0	0	0
Anionic Polyacrylamide (PAM) Erosion Control	450	0	0	0	0
Aquaculture Ponds	397	0	0	0	0
Aquatic Organism Passage	396	0	0	0	0
Bedding	310	-1	-1	0	1
Bivalve Aquaculture Gear and Biofouling Control	400	0	0	0	0
Brush Management	314	0	0	0	0
Channel Stabilization	584	0	0	0	0
Clearing and Snagging	326	0	0	0	0
Combustion System Improvement	372	0	0	0	0
Composting Facility	317	0	0	0	0
Conservation Cover	327	5	3	0	2
Conservation Crop Rotation	328	4	1	0	2
Constructed Wetland	656	0	0	0	0
Contour Buffer Strips	332	2	0	0	0
Contour Farming	330	2	0	0	0
Contour Orchard and Other Fruit Area	331	2	0	0	0
Cover Crop	340	2	2	0	1
Critical Area Planting	342	5	2	0	1
Cross Wind Ridges	588	1	0	0	0
Cross Wind Trap Strips	589C	2	0	0	0
Dam	402	0	0	0	-1
Dam, Diversion	348	0	0	0	0
Deep Tillage	324	-4	5	-1	2
Dike	356	0	0	0	0
Diversion	362	0	0	0	0
Drainage Water Management	554	2	-1	2	0
Dry Hydrant	432	0	0	0	0
DUST CONTROL FROM ANIMAL ACTIVITY ON OPEN LOT SURFACES	375	0	0	0	0
Dust Control on Unpaved Roads and Surfaces	373	0	0	0	-1
Early Successional Habitat Development/Management	647	0	0	0	0
Farmstead Energy Improvement	374	0	0	0	0
Feed Management	592	0	0	0	0
Fence	382	0	1	0	0
Field Border	386	4	2	0	0
Filter Strip	393	5	5	0	0
Firebreak	394	-2	-2	0	0
Fish Raceway or Tank	398	0	0	0	0
Fishpond Management	399	0	0	0	0
Forage and Biomass Planting	512	1	2	0	0
Forage Harvest Management	511	1	3	0	0
Forest Site Preparation	490	-2	-1	0	0
Forest Stand Improvement	666	1	-2	0	0
Forest Trails and Landings	655	-1	1	0	0
Fuel Break	383	-4	-2	0	0

Grade Stabilization Structure	410	0	0	0	0
Grassed Waterway	412	3	0	0	-1
Grazing Land Mechanical Treatment	548	1	0	0	0
Heavy Use Area Protection	561	0	-1	0	0
Hedgerow Planting	422	2	1	0	0
Herbaceous Weed Control	315	0	0	0	0
Herbaceous Wind Barriers	603	2	0	0	0
Hillside Ditch	423	0	0	0	0
Integrated Pest Management	595	2	2	0	0
Irrigation Canal or Lateral	320	0	0	0	0
Irrigation Ditch Lining	428	0	0	0	0
Irrigation Field Ditch	388	0	0	0	0
Irrigation Land Leveling	464	-2	-2	0	-1
Irrigation Pipeline	430	0	0	0	0
Irrigation Storage Reservoir	436	0	0	0	0
Irrigation System, Microirrigation	441	0	0	0	1
Irrigation System, Sprinkler	442	0	-1	0	2
Irrigation System, Surface and Subsurface	443	0	-1	0	0
Irrigation System, Tailwater Recovery	447	0	-1	0	-1
Irrigation Water Conveyance, Ditch and Canal Lining, Flexible Membrane	428B	0	0	0	0
Irrigation Water Conveyance, Ditch and Canal Lining, Galvanized Steel	428C	0	0	0	0
Irrigation Water Conveyance, Ditch and Canal Lining, Nonreinforced Concrete	428A	0	0	0	0
Irrigation Water Conveyance, Pipeline, Aluminum Tubing	430AA	0	0	0	0
Irrigation Water Conveyance, Pipeline, Asbestos-Cement	430BB	0	0	0	0
Irrigation Water Conveyance, Pipeline, High-Pressure, Underground, Plastic	430DD	0	0	0	0
Irrigation Water Conveyance, Pipeline, Low-Pressure, Underground, Plastic	430EE	0	0	0	0
Irrigation Water Conveyance, Pipeline, Nonreinforced Concrete	430CC	0	0	0	0
Irrigation Water Conveyance, Pipeline, Reinforced Plastic Mortar	430GG	0	0	0	0
Irrigation Water Conveyance, Pipeline, Steel	430FF	0	0	0	0
Irrigation Water Management	449	1	0	0	2
Land Clearing	460	-3	-1	0	0
Land Reclamation, Landslide Treatment	453	2	0	0	0
Land Reclamation, Toxic Discharge Control	455	0	0	0	2
Land Reconstruction, Abandoned Mined Land	543	3	1	0	4
Land Reconstruction, Currently Mined Land	544	3	1	0	4
Land Smoothing	466	-2	-2	0	-1
Lined Waterway or Outlet	468	0	0	0	0
Livestock Pipeline	516	0	0	0	0
Mine Shaft and Adit Closing	457	0	0	2	0
Mole Drain	482	-2	1	-2	2
Monitoring Well	353	0	0	0	0
Mulching	484	2	0	0	2
Multi-Story Cropping	379	5	2	1	1
Nutrient Management	590	2	-2	0	2
Obstruction Removal	500	1	-1	0	0
Open Channel	582	0	0	0	0
Pond	378	0	0	0	-1
Pond Sealing or Lining, Bentonite Sealant	521C	0	0	0	1
Pond Sealing or Lining, Compacted Clay Treatment	521D	0	0	0	1
Pond Sealing or Lining, Flexible					

Membrane	521A	0	0	0	1
Pond Sealing or Lining, Soil Dispersant	521B	0	0	0	0
Precision Land Forming	462	-2	-1	0	1
Prescribed Burning	338	1	0	-1	-1
Prescribed Grazing	528	4	2	0	2
Pumping Plant	533	0	0	2	0
Range Planting	550	4	4	0	1
Recreation Area Improvement	562	1	1	0	0
Recreation Land Grading and Shaping	566	1	0	0	0
Residue and Tillage Management, Mulch Till	345	2	1	0	1
Residue and Tillage Management, No-Till/Strip Till/Direct Seed	329	2	2	0	1
Residue and Tillage Management, Ridge Till	346	2	2	0	1
Residue Management, Seasonal	344	1	0	0	1
Restoration and Management of Declining Habitats	643	0	0	0	-1
Riparian Forest Buffer	391	4	4	0	1
Riparian Herbaceous Cover	390	4	4	0	2
Road/Trail/Landing Closure and Treatment	654	5	2	0	0
Rock Barrier	555	0	0	0	0
Roof Runoff Structure	558	0	0	0	0
Roofs and Covers	367	0	0	0	0
Row Arrangement	557	1	0	0	1
Salinity and Sodic Soil Management	610	0	0	0	0
Seasonal High Tunnel System for Crops	798	1	0	0	0
Sediment Basin	350	0	0	0	0
Shallow Water Management for Wildlife	646	1	0	0	0
Silvopasture Establishment	381	4	0	0	0
Sinkhole and Sinkhole Area Treatment	527	0	0	0	2
Solid/Liquid Waste Separation Facility	632	1	0	0	0
Spoil Spreading	572	1	-1	0	0
Spring Development	574	0	-1	0	0
Stormwater Runoff Control	570	0	1	0	0
Stream Crossing	578	0	0	0	0
Stream Habitat Improvement and Management	395	0	0	0	0
Streambank and Shoreline Protection	580	0	0	0	0
Stripcropping	585	2	0	0	0
Structure for Water Control	587	0	0	0	0
Subsurface Drain	606	-2	2	-2	2
Surface Drainage, Field Ditch	607	-2	1	-1	2
Surface Drainage, Main or Lateral	608	0	0	0	0
Surface Roughening	609	0	0	0	0
Terrace	600	1	-1	0	0
Trails and Walkways	568	0	2	0	0
Tree/Shrub Establishment	612	4	2	0	1
Tree/Shrub Pruning	660	-1	0	0	0
Underground Outlet	620	0	0	0	0
Upland Wildlife Habitat Management	645	0	0	0	0
Vegetated Treatment Area	635	3	3	0	-2
Vegetative Barrier	601	0	0	0	-2
Vertical Drain	630	0	0	0	0
Waste Facility Closure	360	0	0	0	2
Waste Recycling	633	2	0	0	0
Waste Storage Facility	313	1	1	0	0
Waste Transfer	634	0	-1	0	0
Waste Treatment	629	1	1	0	0
Waste Treatment Lagoon	359	1	1	0	0
Water and Sediment Control Basin	638	0	0	0	0
Water Harvesting Catchment	636	0	0	0	0
Water Well	642	0	0	0	1

Watering Facility	614	0	0	0	0
Waterspreading	640	1	0	0	1
Well Decommissioning	351	0	0	0	0
Well Water Testing	355	0	0	0	0
Wetland Creation	658	2	0	0	0
Wetland Enhancement	659	1	0	0	0
Wetland Restoration	657	1	0	0	0
Wetland Wildlife Habitat Management	644	0	0	0	0
Windbreak/Shelterbelt Establishment	380	4	2	0	1
Windbreak/Shelterbelt Renovation	650	4	2	0	1
Woody Residue Treatment	384	-1	-2	0	0

RenderExcel