

**STATEMENT OF WORK**  
**Contour Buffer Strip (332)**  
**New York State**

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

Items marked with an asterisk (\*) will be delivered to the Designated Conservationist.

## DESIGN

---

### Deliverables:

1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
  - a. Practice purpose(s) as identified in the conservation plan
  - b. List of required permits to be obtained by the client
  - c. List all required and/or facilitating practices
  - d. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
    - i. Row grade, width of tilled strip and width of vegetated strip
    - ii. Vegetative species selection
    - iii. Spacing and arrangement of strips
    - iv. Erosion calculations
    - v. Slope length
    - vi. Outlet stability
    - vii. Wildlife considerations
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits. Plans and specifications shall be developed in accordance with the requirements of the conservation practice standard for Contour Buffer Strips (Code 332).
3. **\*Operation and maintenance plan.**
4. **\*In cases where the practice location has changed, a statement to NRCS notifying the agency of the change in location as well as a map showing the new practice location. The statement will include the landowner's name, program name, contract number and practice name.**
5. **\*Signed *Warranty of Technical Services Provided* form indicating compliance with practice standard criteria and applicable laws and regulations.**
6. Design modifications during installation as required.

## INSTALLATION

---

### Deliverables

1. Delay of installation until TSP receives written verification from NRCS that all NEPA requirements have been satisfied for this practice.
2. Pre-installation conference with client.
3. Verification that client has obtained required permits.
4. Staking and layout according to plans and specifications including applicable layout notes.
5. Installation guidance as needed.

**STATEMENT OF WORK  
Contour Buffer Strip (332)  
New York State**

6. Facilitate and implement required design modifications with client and original designer.
7. **\*Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.**
8. **\*Signed *Warranty of Technical Services Provided* form indicating compliance with practice standard criteria and applicable laws and regulations.**

## **CHECK OUT**

---

### **Deliverables**

1. **\*Records of installation.**
  - a. **Actual row grade applied, actual width of tilled strip and actual width of vegetated strip**
  - b. **Extent of practice units applied.**
  - c. **Actual materials used.**
2. **\*Signed *Warranty of Technical Services Provided* form indicating compliance with practice standard criteria and applicable laws and regulations.**
3. Progress reporting.

## **REFERENCES**

---

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard Contour Buffer Strips - 332
- NRCS National Agronomy Manual
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook