

STATEMENT OF WORK
Lined Waterway or Outlet (468)
Ohio Template

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documents that demonstrate criteria in practice standard have been met and are compatible with planned and applied practices.
2. Practice purpose(s) as identified in the conservation plan.
 - a. List of required permits to be obtained by the client.
 - b. Compliance with NRCS national and state utility safety policy (NEM part 503-Safety, Section 503.00 through 503.22).
 - c. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Hydrology/hydraulics.
 - ii. Type of Liner.
 - iii. Outlet capacity and stability.
 - iv. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits. Engineering drawings shall meet the requirements stated in NEM 541.00 through 541.09, and Ohio supplement (OH541.00 (b)(4), pages 1 through 6) for the applicable practice.
3. Operation and maintenance plan.
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations (NEM Subpart A, 505.03(b)(2)).
5. Design modifications during installation as required.

INSTALLATION

Deliverables

1. Pre-installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection.
 - a. Actual materials used.
 - b. Inspection records.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.

STATEMENT OF WORK
Lined Waterway or Outlet (468)
Ohio Template

7. Certification that the installation process and materials meets design and permit requirements.

CHECK OUT

Deliverables

1. As-built documentation.
 - a. Extent of practice units applied.
 - b. Drawings.
 - c. Final quantities.
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03(c)(1)).
3. Progress reporting.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Lined Waterway or Outlet - 468, Ohio FOTG:
http://efotg.nrcs.usda.gov/efotg_locator.aspx?map=OH
- NRCS National Engineering Manual (NEM): <http://www.info.usda.gov/CED/ftp/CED/NEM.html>
- Ohio NRCS supplements to the NEM:
<http://www.oh.nrcs.usda.gov/intranet/NEM/supplements.html>
- NRCS National Environmental Compliance Handbook:
http://policy.nrcs.usda.gov/scripts/lpsiis.dll/H/H_190_610_Content.htm
- NRCS Cultural Resources Handbook:
http://policy.nrcs.usda.gov/scripts/lpsiis.dll/H/H_190_601_Content.htm