

STATEMENT OF WORK
Silvopasture Establishment 381
Oklahoma

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN

Deliverables:

1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan
 - b. List of required permits to be obtained by the client
 - c. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
 - i. Determination of appropriate method, intensity and timing to establish tree density for establishing Silvopasture.
 - ii. Mitigation of erosion, runoff, soil compaction and soil displacement to acceptable levels
 - iii. Required establishment and management of forages for successful implementation.
 - iv. Written plans and specifications including sketches and drawings shall be provided to the client which adequately describe the requirements to install the practice and/or obtain necessary permits.
2. Documentation of needed operation and maintenance.
3. Certification that the design meets practice standard criteria and comply with applicable laws and regulations.
4. Design modifications during installation as required.

Note: Job Sheet 381 01 – Silvopasture Establishment is available for design.

INSTALLATION

Deliverables

1. Pre-application conference with client.
2. Verification that client has obtained required permits if required or documentation if no permit is required.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Application guidance as needed.
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the application process and materials meet design and permit requirements.

Note: Job Sheet 381 01 – Silvopasture Establishment is available for design.

CHECK OUT

Deliverables

1. Records of application.
 - a. Extent of practice units applied
 - b. Method of site preparation
 - c. Specie(s) planted
 - d. Number of tree rows per set
 - e. Within row spacing
 - f. Spacing between rows
 - g. Alley width
2. Certification that the application meets NRCS standards and specifications and is in compliance with permits.
3. Progress reporting.

Note: OK-381-CERT available for documentation of checkout and certification.

REFERENCES

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard –Silvopasture Establishment – 381.
- NRCS National Forestry Handbook (NFH), Part 636.4
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Handbook