

STATEMENT OF WORK
Riparian Herbaceous Cover (390)
Oklahoma

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN**Deliverables:**

1. Design documents that demonstrate criteria in practice standard have been met and are compatible with planned and applied practices
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client
 - c. List of facilitating practices (i.e. Streambank and Shoreline Protection – 580, Fence – 382)
 - d. Practice standard criteria related computations and analyses to develop plans and specifications including but not limited to:
 - i. Determination of widths and lengths and adapted species to be planted, retained, and/or naturally reestablished
 - ii. Protective measures for planted species including use exclusion
 - iii. Required seedbed condition and preparation methods
 - iv. Soil and seed amendments needed
 - v. Variety or origin and amount of each species to be planted
 - vi. Planting dates and depths and description of planting equipment
 - vii. Instructions as needed for placing different seed types (i.e. fluffy, large, small, slick and dense) in suitable drill boxes
2. Written plans and specifications including sketches and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits. Plans and specifications shall be developed in accordance with the requirements of conservation practice standard Riparian Herbaceous Cover (390).
3. Operation and maintenance plan
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations
5. Design modifications during installation as required

Note: Refer to the Range Planting (550) standard and Job Sheet 550 01 for guidance on seeding rates, mixtures and establishment. Refer to the standard for Use Exclusion (472) and Prescribed Grazing (528) when livestock are present.

INSTALLATION**Deliverables**

1. Pre-application conference with client and contractor
2. Verification that client has obtained required permits
3. Staking and layout according to plans and specifications including applicable layout notes
4. Application inspection
 - a. Actual materials used
 - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation
7. Certification that the application process and materials meets design and permit requirements

Note: Prepare an OK-ECS-Worksheet 04 if needed and provide a copy to the landuser. Refer to the standard for Use Exclusion (472) and Prescribed Grazing (528) when livestock are present.

CHECK OUT**Deliverables**

1. Records of application
 - a. Purpose of buffer
 - b. Specie(s) planted and rate
 - c. Width of buffer
2. Certification that the application meets NRCS standards and specifications and is in compliance with permits

STATEMENT OF WORK
Riparian Herbaceous Cover (390)
Oklahoma

3. Progress reporting

Note: Certify any plantings that were established on the OK-ECS-Worksheet 04.

REFERENCES

- Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Riparian Herbaceous Cover – 390
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Procedures Handbook
- NRCS National Biology Manual
- NRCS National Biology Handbook