

Practice: 484 - Mulching

Scenario #1 - Natural Material, Full Coverage

Scenario Description:

Application of natural materials such as hay mulch (straw, grass hay) or other state approved natural material to reduce erosion and facilitate the establishment of vegetative cover. Mulch provides full coverage and is typically used with critical area planting. Assumes 125 bales/acre (3 bales/1000 sq ft)

Before Situation:

Typical scenario ranges from a 0.1 to 1.0 acre disturbed site around a newly constructed structural practice. The potential for soil erosion is high and mulch is needed to stabilize the soil and facilitate the establishment of vegetative cover.

After Situation:

Natural mulch materials have been applied to areas needing mulch. Erosion and sedimentation is reduced, water and soil quality is protected, and moisture is managed to aid in establishment of permanent vegetation.

Feature Measure: Area Covered by Mulch

Scenario Unit:: Acre

Scenario Typical Size: 1

Total Scenario Cost: \$386.20

Scenario Cost/Unit: \$386.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Tractor, agricultural, 60 HP	963	Agricultural tractor with horsepower range of 50 to 90. Equipment and power unit costs. Labor not included.	Hour	\$20.48	1	\$20.48
Mulcher, straw blower	1305	Straw bale mulcher/blower to mechanically spread small or large straw bales. Labor not included.	Hour	\$36.96	1	\$36.96
Labor						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$21.53	1	\$21.53
Materials						
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$122.89	2.5	\$307.23

Practice: 484 - Mulching

Scenario #2 - Natural Material, Tree and Shrub

Scenario Description:

Application of straw mulch or other state approved natural material (such as wood chips, compost, or hay) to reduce erosion, moderate soil temperature and suppress weeds. Typically used to provide partial coverage (either in-row or between rows) to suppress weeds. Payment based on total acres mulched, assuming 3-5 ft. swatch and 10-12 ft. row spacing.

Before Situation:

Site conditions vary. Typically scenarios include new tree and shrub plantings, irrigated orchards or vineyards, or annual and perennial specialty crops. Water quantity and soil moisture is a concern.

After Situation:

Straw or other natural mulch is applied in rows by hand or by mechanized means. Soil moisture is conserved, energy use associated with irrigation is decreased, and weed growth is suppressed.

Feature Measure: Total Acres Mulched

Scenario Unit:: Acre

Scenario Typical Size: 10

Total Scenario Cost: \$1,054.43

Scenario Cost/Unit: \$105.44

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$18.01	20	\$360.20
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$19.35	20	\$387.00
Materials						
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$122.89	2.5	\$307.23

Practice: 484 - Mulching

Scenario #3 - Erosion Control Blanket Herbaceous Planting

Scenario Description:

Installation of erosion control blanket on critical areas with steep slopes, grassed waterways or diversions.. Blanket is typically made of coconut coir, wood fiber, straw and is typically covered on both sides with polypropylene netting. Used to help control erosion and establish vegetative cover.

Before Situation:

A newly constructed practice is installed that will experience concentrated flows of water and has potential for erosion before permanent vegetation can be established.

After Situation:

The erosion control blanket is placed on concentrated flow areas and secured with ground staples. Soil erosion is minimized and vegetative cover is established.

Feature Measure: Area Covered by Mulch

Scenario Unit:: Square Foot

Scenario Typical Size: 5000

Total Scenario Cost: \$861.01

Scenario Cost/Unit: \$0.17

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
Equipment Installation						
Truck, Pickup	939	Equipment and power unit costs. Labor not included.	Hour	\$18.01	1	\$18.01
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$19.35	8	\$154.80
Materials						
Erosion Control Blanket, biodegradable	1213	Biodegradable erosion control blanket, typically a composite of natural fibers with reinforcing polymer netting. Materials and shipping only.	Square Yard	\$1.24	555	\$688.20

Practice: 484 - Mulching

Scenario #4 - Synthetic Material

Scenario Description:

Installation of geotextile, biodegradable plastic, polyethylene plastic, or other state approved synthetic mulch to conserve soil moisture, moderate soil temperature, suppress weed growth and provide erosion control. Payment based on actual area covered by mulching material.

Before Situation:

Site conditions vary. Typically scenarios include new tree and shrub plantings, irrigated orchards or vineyards, or annual and perennial specialty crops. Water quantity and soil moisture is a concern.

After Situation:

Synthetic mulch is applied in rows with a mulch layer or by other mechanized means. Soil moisture is conserved, energy use associated with irrigation is decreased, and weed growth is suppressed.

Feature Measure: Area Covered by Mulch

Scenario Unit:: Acre

Scenario Typical Size: 1

Total Scenario Cost: \$10,551.20

Scenario Cost/Unit: \$10,551.20

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.18	4840	\$10,551.20
-------------------	----	--	-------------	--------	------	-------------

Practice: 484 - Mulching

Scenario #5 - Weed Barrier, Tree and Shrub Planting

Scenario Description:

Weed barrier fabric or other suitable natural or synthetic mulch is installed with a new tree and shrub planting. Typically used to prevent weed competition during the installation of conservation practices. Rate is per tree/shrub and assumes 1 square yard of weed barrier fabric and 5 staples/tree.

Before Situation:

Site conditions vary. Typical scenario is an installation of 100 native trees and shrubs to enhance wildlife habitat. Sites are often remote and trees may not be planted in rows, requiring each tree to be mulched individually

After Situation:

Weed barrier fabric squares are installed with 5 sod staples each, around individual trees and shrubs to control weed competition. Weeds are controlled and tree/shrub growth is minimally influenced by weed competition.

Feature Measure: Number of Trees Mulched

Scenario Unit:: Each

Scenario Typical Size: 100

Total Scenario Cost: \$218.00

Scenario Cost/Unit: \$2.18

Cost Details:

Component Name	ID	Description	Unit	Cost	QTY	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.18	100	\$218.00
-------------------	----	--	-------------	--------	-----	----------