

Practice: 521C - Pond Sealing or Lining, Bentonite Sealant

Scenario #1 - Bentonite Treatment, Uncovered

**Scenario Description:**

Construction of a compacted soil liner, treated with bentonite, to reduce seepage from waste storage impoundment structures. Practice implementation includes incorporation of the bentonite with the soil under proper moisture conditions, compaction to the designed liner thickness. Practice implementation may require filter compatibility with the subgrade (graded filter or geotextile).

**Before Situation:**

In-place soils at site exhibit seepage rates in excess of acceptable limits. Soils are suitable for treatment with bentonite.

**After Situation:**

Water conservation and environmental protection provided by limiting seepage losses from waste storage impoundments.

**Feature Measure:** Volume of Liner Material

**Scenario Unit::** Cubic Yard

**Scenario Typical Size:** 1613

**Total Scenario Cost:** \$62,028.58

**Scenario Cost/Unit:** \$38.46

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$3.81	1613	\$6,145.53
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$47.69	6	\$286.14
<b>Labor</b>						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$21.53	6	\$129.18
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.55	8	\$324.40
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$102.60	2	\$205.20
<b>Materials</b>						
Bentonite	41	Bentonite, includes materials (50# bag)	Each	\$20.94	2613.5	\$54,726.69
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$211.44	1	\$211.44

Practice: 521C - Pond Sealing or Lining, Bentonite Sealant

Scenario #2 - Bentonite Treatment, Covered

**Scenario Description:**

Construction of a compacted soil liner, treated with bentonite, to reduce seepage from waste storage impoundment structures. Practice implementation includes incorporation of the bentonite with the soil under proper moisture conditions, compaction to the designed liner thickness, and placement of soil cover over the treated liner. Practice implementation may require filter compatibility with the subgrade (graded filter or geotextile).

**Before Situation:**

In-place soils at site exhibit seepage rates in excess of acceptable limits. Soils are suitable for treatment with bentonite.

**After Situation:**

Water conservation and environmental protection provided by limiting seepage losses from waste storage impoundments.

**Feature Measure:** Volume of Liner Material (includes

**Scenario Unit::** Cubic Yard

**Scenario Typical Size:** 1613

**Total Scenario Cost:** \$68,177.92

**Scenario Cost/Unit:** \$42.27

**Cost Details:**

Component Name	ID	Description	Unit	Cost	QTY	Total
<b>Equipment Installation</b>						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic Yard	\$3.81	3227	\$12,294.87
Tractor, agricultural, 120 HP	962	Agricultural tractor with horsepower range of 90 to 140. Equipment and power unit costs. Labor not included.	Hour	\$47.69	6	\$286.14
<b>Labor</b>						
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$21.53	6	\$129.18
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.55	8	\$324.40
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$102.60	2	\$205.20
<b>Materials</b>						
Bentonite	41	Bentonite, includes materials (50# bag)	Each	\$20.94	2613.5	\$54,726.69
<b>Mobilization</b>						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$211.44	1	\$211.44