

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #1 - Stream Habitat Enhancement

Scenario Description: This scenario describes the implementation of a stream habitat improvement and management project where restoration is necessary to increase habitat and functionality of the stream. A combination of structures, excavation, channel shaping, and woody materials are considered based on natural channel design concepts. A local stream assessment with technical specialists (such as the Stream Visual Assessment Protocol) should be conducted in order to document habitat components (such as large wood, pools) are not currently present in the stream or are limited for aquatic species. A project design for restoration of the stream channel (channel shaping, boulder placement, wood, wood structures, etc) will be based on assessment of (a) the target stream reach characteristics and (b) those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Large rocks/boulders placed in the stream channel will mimic geologic material sizes typically present in the watershed or observed in intact, reference stream reaches in the MLRA where the project is located. Rock boulder sizes should also reflect the geomorphic setting of the stream reach. Large wood placed into the stream under this scenario should be similar in species, age, and size (diameter) as trees found in the surrounding riparian area, to the extent possible. Stream restoration components including wood, boulders and/or boulder clusters will be placed in the stream to create pool habitat and hydraulic complexity with close review & approval of a fish habitat biologist onsite during the planning and implementation of the project. This scenario involves restoring a 300 foot stretch of the stream. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species.

Before Situation: In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol or onsite technical specialist assessment. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream habitat components, such as large wood and off-channel refuge habitat. Bank and floodplain instability are present due to altered stream hydraulics due to degradation of the stream channel.

After Situation: Stream habitat within the project reach is improving as a result of completing a stream restoration based on natural channel design in the channel and/or along the stream bank. Pool habitat in the reach is improved, and hiding cover, food availability and refuge habitat for all stream species is improving.

Scenario Feature Measure: The entire reach of the impacted stream

Scenario Unit: Foot

Scenario Typical Size: 300

Total Scenario Cost: \$10,417.15

Scenario Cost/Unit: \$34.72

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	8	\$246.57
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	16	\$355.11
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$104.89	8	\$839.11
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$44.78	8	\$358.21

Equipment Installation

Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$126.00	8	\$1,007.99
---------------------------	-----	--	------	----------	---	------------

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$541.06	2	\$1,082.13
-------------------------------	------	--	------	----------	---	------------

Materials

Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes materials and delivery (up to 100 miles) only.	Ton	\$34.32	25	\$857.94
---------	------	---	-----	---------	----	----------

Cuttings, woody, large size	1309	Woody pole cuttings or posts 2" to 6" in diameter and 6' long. Includes materials and shipping only.	Each	\$18.38	300	\$5,515.14
One Species, Native Forb, Moderate/High Cost	2331	Native forb. Includes material and shipping only.	Acre	\$658.33	0.1	\$65.83
Root Wad	2045	Tree stump buried into the streambank with the roots left exposed. Includes material only.	Ton	\$8.91	10	\$89.13

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #2 - Riparian Zone Improvement-Forested

Scenario Description: This scenario describes fish and wildlife habitat improvement and/or management actions focused on the community structure and function of forested riparian zone plant communities. The planned activity meets the 395 standard, and facilitating practice standards, especially Codes 390 and 391, utilized in combination to satisfy all requirements specific to habitats needed for the stream and riparian species for which the practice is being implemented. Implementation will improve instream and riparian habitat complexity, water quality, hiding and resting cover, and/or increased food availability for desired riparian and stream species. Because species and habitats differ dramatically within and across regions and/or MLRAs, up to 12 riparian plant community-specific scenarios may be required across the US. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

Before Situation: Riparian quality and quantity are at risk as determined by the NRCS Stream Visual Assessment Protocol score of less than 5 for those elements. The site does not have adequate food, cover, and/or connectivity for riparian wildlife, and contributes insufficient amounts of organic matter and/or large woody material for stream species food and cover. The site's riparian vegetation is compromised by human activities and/or access of vehicles, people, and/or livestock is not controlled adequately to protect riparian functions and stream habitat quality. Nutrients are transported to surface waters through runoff or soil erosion or to ground water from leaching in quantities that degrade water quality and limit use of intended purposes. Soil quality may be reduced due to compaction. Riparian vegetation quality and/or quantity is compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream and riparian habitat components.

After Situation: Revegetation/reforestation of the riparian zone is completed and the vegetation community is under close management to insure long-term survival and ecological succession of the plant community. The quality and quantity of the riparian zone components of the site are managed to support a diverse vegetation community suitable for the site, the species that depend on it for habitat, and the functions it performs or will eventually perform as the vegetation matures. These functions include: stream temperature moderation thru shading, recruitment of instream large wood and/or non-woody organic matter, riparian habitat for terrestrial insects and other riparian-dependent species, streambank integrity, and filtration of contaminants from surface run-off into the stream.

Scenario Feature Measure: acres

Scenario Unit: Acre

Scenario Typical Size: 2

Total Scenario Cost: \$20,905.62

Scenario Cost/Unit: \$10,452.81

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	24	\$739.72
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	40	\$887.76
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$34.38	160	\$5,500.86
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$104.89	40	\$4,195.53
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$44.78	40	\$1,791.06

Materials

Compost	265	A mixture of decaying organic matter, as from leaves and manure, used to improve soil structure and provide nutrients.	Ton	\$53.63	1	\$53.63
Cuttings, woody, large size	1309	Woody pole cuttings or posts 2" to 6" in diameter and 6' long. Includes materials and shipping only.	Each	\$18.38	200	\$3,676.76
One Species, Native Forb, Moderate/High Cost	2331	Native forb. Includes material and shipping only.	Acre	\$658.33	2	\$1,316.67
Tree shelter, wire mesh	1557	5 feet tall, Woven Wire mesh, 6"x 6" opening or smaller, 10 gauge wire (minimum) , cage placed around seedling for animal protection. Materials only.	Each	\$2.32	200	\$463.54

Tree, willow	1426	Willow tree for planting, 18" to 36" seedling. Includes materials and shipping only.	Each	\$0.67	200	\$133.80
--------------	------	--	------	--------	-----	----------

Equipment Installation

Backhoe, 80 HP	926	Wheel mounted backhoe excavator with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$62.09	16	\$993.46
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$73.26	8	\$586.05

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$283.39	2	\$566.78
--------------------------------	------	---	------	----------	---	----------

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #3 - Instream wood placement

Scenario Description: This scenario involves placement of large wood (logs, root wads, log structures) into a stream channel in order to improve aquatic habitat that currently does not meet quality criteria for stream species habitat. A stream assessment (i.e. Stream Visual Assessment Protocol) should be conducted in order to document habitat components lacking for aquatic species (i.e. large wood, pools). A project design for wood placement will be based on assessment of the target stream reach characteristics and those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Large wood and root wads placed into the stream will mimic genus, age, and size of mature trees found in intact, reference riparian areas in the MLRA where the project is located. Large wood/trees with rootwads intact should be placed in streams to create pool habitat according to NRCS engineering specifications and with close review & approval of a fish habitat biologist. Boulders placed to provide ballast shall only be used if the geomorphic setting and project design demand this component. The planned activity will meet the current 395 standard, and facilitating practice standards utilized, including timing of work windows required for protected aquatic and riparian species, and protecting/restoring vegetation and substrates of/to areas impacted by heavy equipment. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of project implementation. Monitoring records demonstrating implementation of this scenario will address resource concerns for stream species of concern are required. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

Before Situation: In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5 overall. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream and riparian habitat components, such as large wood.

After Situation: Stream habitat within the project reach is improving as a result of placing logs, root wads, and/or wood structures in the channel and/or along the stream bank. Pool habitat in the reach is improved, and hiding cover, food availability and refuge habitat for all stream species is improving.

Scenario Feature Measure: Bankfull width x reach length

Scenario Unit: Acre

Scenario Typical Size: 1

Total Scenario Cost: \$16,486.81

Scenario Cost/Unit: \$16,486.81

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Materials

Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$32.13	30	\$963.84
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$26.95	15	\$404.22
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	\$31.70	20	\$633.95
Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes materials and delivery (up to 100 miles) only.	Ton	\$34.32	40	\$1,372.71
Compost	265	A mixture of decaying organic matter, as from leaves and manure, used to improve soil structure and provide nutrients.	Ton	\$53.63	1	\$53.63
Cuttings, woody, large size	1309	Woody pole cuttings or posts 2" to 6" in diameter and 6' long. Includes materials and shipping only.	Each	\$18.38	300	\$5,515.14
Log, un-anchored	2035	Price of log picked up at the Mill. Includes material only.	Ton	\$40.58	30	\$1,217.49
Root Wad	2045	Tree stump buried into the streambank with the roots left exposed. Includes material only.	Ton	\$8.91	20	\$178.25
Steel, rebar	1832	Steel rebar, grade 60. Materials only.	Pound	\$0.53	50	\$26.51

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	24	\$739.72
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	32	\$710.21

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$44.78	8	\$358.21
-----------------------	-----	--	------	---------	---	----------

Equipment Installation

Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$182.17	16	\$2,914.71
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$107.14	8	\$857.15

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$541.06	1	\$541.06
-------------------------------	------	--	------	----------	---	----------

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #4 - Instream rock placement

Scenario Description: This scenario describes the implementation of a stream habitat improvement and management project that places individual boulders or boulder clusters, or rock structures in or adjacent to the stream channel as habitat components. A project design for boulder placement will be based on assessment of the target stream reach characteristics and those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Large rocks/boulders placed in the stream channel will mimic geologic material sizes typically present in the watershed or observed in intact, reference stream reaches in the MLRA where the project is located. Boulders should be placed in streams to create pool habitat and hydraulic complexity according to NRCS engineering specifications and with close review & approval of a fish habitat biologist onsite during implementation of the project design. Spawning gravel placement should be placed to restore spawning area substrates potentially disturbed by rock placement. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, spawning habitat, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of stream habitat assessment, and project implementation. Records demonstrating implementation of this scenario will address resource concerns for stream species of concern will be required.

Before Situation: In this stream reach, habitat for fish, aquatic insects and other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5 overall. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may be also compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream and riparian habitat components, such as large wood, leaf matter, and shade. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

After Situation: Stream habitat within the project reach is improving as a result of placing boulders or constructing rock structures in the channel and/or along the stream bank. Hydraulic complexity of the habitat in the reach is increased, and hiding cover, food availability and refuge habitat for stream species is improving. Streambank vegetation is increasing and contributing to stability of the streambanks.

Scenario Feature Measure: Bankfull width x reach length

Scenario Unit: Acre

Scenario Typical Size: 1

Total Scenario Cost: \$14,650.42

Scenario Cost/Unit: \$14,650.42

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Materials

Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$32.13	120	\$3,855.35
Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$26.95	20	\$538.96
Aggregate, Sand, Graded, Washed	45	Sand, typical ASTM C33 gradation, includes materials, equipment and labor to transport and place	Cubic Yard	\$31.70	30	\$950.93
Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes materials and delivery (up to 100 miles) only.	Ton	\$34.32	60	\$2,059.07
Cuttings, woody, large size	1309	Woody pole cuttings or posts 2" to 6" in diameter and 6' long. Includes materials and shipping only.	Each	\$18.38	100	\$1,838.38

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	24	\$739.72
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	16	\$355.11

Equipment Installation

Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$182.17	16	\$2,914.71
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$107.14	8	\$857.15

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$541.06	1	\$541.06
-------------------------------	------	--	------	----------	---	----------

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #6 - Fish Barrier

Scenario Description: This scenario describes the implementation of a stream habitat improvement and management project where practices are focused on the stream channel. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in protecting native aquatic fauna in the reach from competition or harrassment from non-native fish. This action may also increase food availability for fish and other stream species located above the constructed barrier. Payment for implementation is to defray the costs of stream habitat assessment above the barrier, and project implementation. Records demonstrating implementation of this scenario will address resource concerns for aquatic and riparian species of concern will be required. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

Before Situation: In this stream corridor, native aquatic species are at risk as determined by the state fish and wildlife agency. NRCS Stream Visual Assessment Protocol for the reach being protected by a barrier meets quality criteria and provides habitat for native species of concern, as determined by a Stream Visual Assessment Protocol score of greater than 5 .

After Situation: Native fish inhabiting areas upstream of the newly constructed concrete barrier will not be adversely affected by interactions with non-native species/competitors.

Scenario Feature Measure: Each

Scenario Unit: Cubic Yard

Scenario Typical Size: 5

Total Scenario Cost: \$34,921.82

Scenario Cost/Unit: \$6,984.36

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Equipment Installation

Concrete, CIP, formed reinforced	38	Steel reinforced concrete formed and cast-in-placed in formed structures such as walls or suspended slabs by chute placement. Typical strength is 3000 to 4000 psi. Includes materials, labor and equipment to transport, place and finish.	Cubic Yard	\$429.82	60	\$25,789.44
Hydraulic Excavator, 2 CY	932	Track mounted hydraulic excavator with bucket capacity range of 1.5 to 2.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$182.17	10	\$1,821.70
Truck, Concrete Pump	1211	Concrete pump, normally truck mounted. Use this item in association with other concrete components when job requires placement by other than normal chutes. Include drive and setup time in quantity; therefore, do not include mobilization. Includes equipment and operator.	Hour	\$136.96	36	\$4,930.40

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	10	\$308.22
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	10	\$221.94
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$34.38	10	\$343.80

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$541.06	2	\$1,082.13
-------------------------------	------	--	------	----------	---	------------

Materials

Plywood, 3/4 inch, untreated	1833	Untreated 4' x 8' sheets of 3/4 inch exterior grade plywood. Includes materials only.	Each	\$26.87	15	\$402.99
Steel, rebar	1832	Steel rebar, grade 60. Materials only.	Pound	\$0.53	40	\$21.21

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #7 - Cribbing Mudsill 10 section

Scenario Description: This scenario describes the implementation of a stream habitat improvement and management project where practices are focused on instream habitat improvement with a combination of rock AND wood structures to build a mudsill. A stream assessment (i.e. Stream Visual Assessment Protocol) should be conducted in order to document habitat components (such as large wood, pools) are not currently present in the stream or are limited for aquatic species. A project design for placement of habitat structures (boulders, boulder clusters, wood, wood structures) will be based on assessment of (a) the target stream reach characteristics and (b) those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. The bank is sloped back, logs set on rocks parallel to stream, boards set on top perpendicular to make shelter below pool level. Rock placed on top and then filled and sloped, protected with fabric .Rock boulder sizes should also reflect the geomorphic setting of the stream reach. Large wood placed into the stream under this scenario should be similar in species, age, and size (diameter) as trees found in the surrounding riparian area, to the extent possible. Wood, boulders and/or boulder clusters will be placed in the stream to create pool habitat and hydraulic complexity according to NRCS engineering specifications and with close review & approval of a fish habitat biologist onsite during the planning and implementation of the project. This scenario involves restoring one acre of stream. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of project implementation. Records demonstrating implementation of this scenario will address resource concerns for stream species of concern will be required. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

Before Situation: In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream habitat components, such as large wood and off-channel refuge habitat.

After Situation: Stream habitat within the project reach is improving as a result of placing a 10' section of mudsill along the stream bank. Pool habitat in the reach is improved, and hiding cover, food availability and refuge habitat for all stream species is improving.

Scenario Feature Measure: Each 10' Section

Scenario Unit: Each

Scenario Typical Size: 1

Total Scenario Cost: \$823.99

Scenario Cost/Unit: \$823.99

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	2	\$61.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	2	\$44.39
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$44.78	1	\$44.78

Equipment Installation

Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.84	1	\$4.84
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$126.00	1	\$126.00
Truck, dump, 8 CY	1401	Dump truck for moving bulk material. Typically capacity is 12 ton or 8 cubic yards. Includes equipment only.	Hour	\$63.76	1	\$63.76

Materials

Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes materials and delivery (up to 100 miles) only.	Ton	\$34.32	2	\$68.64
Dimension Lumber, untreated	1045	Untreated dimension lumber with nominal thickness equal or less than 2". Includes lumber and fasteners.	Board Foot	\$0.79	100	\$78.72
Erosion Control Blanket,	1213	Biodegradable erosion control blanket, typically a composite of	Square Yard	\$1.24	14	\$17.37

biodegradable		natural fibers with reinforcing polymer netting. Materials and shipping only.				
Log, un-anchored	2035	Price of log picked up at the Mill. Includes material only.	Ton	\$40.58	2	\$81.17
Rock Riprap, graded, angular, material and shipping	1200	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$31.12	4	\$124.49

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$541.06	0.2	\$108.21
-------------------------------	------	--	------	----------	-----	----------

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #8 - Mdstream Structure - 10 Boulders or 3 mid str log structures

Scenario Description: This scenario describes the implementation of a stream habitat improvement and management project where practices are focused on instream habitat improvement with a combination of rock AND wood structures. This scenario involves placement of large wood and rock structures into a stream channel in order to improve aquatic habitat that currently does not meet quality criteria for stream species habitat. A stream assessment (i.e. Stream Visual Assessment Protocol) should be conducted in order to document habitat components (such as large wood, pools) are not currently present in the stream or are limited for aquatic species. A project design for placement of habitat structures (boulders, boulder clusters, wood, wood structures) will be based on assessment of (a) the target stream reach characteristics and (b) those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Large rocks/boulders placed in the stream channel will mimic geologic material sizes typically present in the watershed or observed in intact, reference stream reaches in the MLRA where the project is located. Rock boulder sizes should also reflect the geomorphic setting of the stream reach. Large wood placed into the stream under this scenario should be similar in species, age, and size (diameter) as trees found in the surrounding riparian area, to the extent possible. Wood, boulders and/or boulder clusters will be placed in the stream to create pool habitat and hydraulic complexity according to NRCS engineering specifications and with close review & approval of a fish habitat biologist onsite during the planning and implementation of the project. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of project implementation. Records demonstrating implementation of this scenario will address resource concerns for stream species of concern will be required. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

Before Situation: In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream habitat components, such as large wood and off-channel refuge habitat.

After Situation: Stream habitat within the project reach is improving as a result of placing boulders in groups of 10 or constructing 3 log mid stream structures or some combination in the channel. Hydraulic complexity of the habitat in the reach is increased, and hiding cover, food availability and refuge habitat for stream species is improving. Streambank vegetation is increasing and contributing to stability of the streambanks.

Scenario Feature Measure: Each group

Scenario Unit: Each

Scenario Typical Size: 1

Total Scenario Cost: \$554.56

Scenario Cost/Unit: \$554.56

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	1.5	\$46.23
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	2	\$44.39

Equipment Installation

Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.84	2	\$9.68
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$126.00	1	\$126.00
Truck, dump, 8 CY	1401	Dump truck for moving bulk material. Typically capacity is 12 ton or 8 cubic yards. Includes equipment only.	Hour	\$63.76	0.5	\$31.88

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$541.06	0.2	\$108.21
-------------------------------	------	--	------	----------	-----	----------

Materials

Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes materials and delivery (up to 100 miles) only.	Ton	\$34.32	2.5	\$85.79
---------	------	---	-----	---------	-----	---------

Log, un-anchored	2035	Price of log picked up at the Mill. Includes material only.	Ton	\$40.58	2	\$81.17
Steel, rebar	1832	Steel rebar, grade 60. Materials only.	Pound	\$0.53	40	\$21.21

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #9 - Deflector, Rock <= 80 ton

Scenario Description: This scenario describes the implementation of a stream habitat improvement and management project where practices are focused on instream habitat improvement with a combination of rock AND wood structures. This scenario involves placement of large rock deflector (<= 80tons) with or without log structures into a stream channel in order to improve aquatic habitat that currently does not meet quality criteria for stream species habitat. A stream assessment (i.e. Stream Visual Assessment Protocol) should be conducted in order to document habitat components (such as large wood, pools) are not currently present in the stream or are limited for aquatic species. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Rock deflectors, generally more than one, will be placed in the stream to create pool habitat and hydraulic complexity according to NRCS engineering specifications and with close review & approval of a fish habitat biologist onsite during the planning and implementation of the project. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of project implementation. Records demonstrating implementation of this scenario will address resource concerns for stream species of concern will be required. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

Before Situation: In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream habitat components, such as large wood and off-channel refuge habitat.

After Situation: Stream habitat within the project reach is improving as a result of placing a 60 ton rock deflector with several logs into the channel from the stream bank. Stream habitat in the reach is improved, and hiding cover, food availability and refuge habitat for all stream species is improving.

Scenario Feature Measure: Each structure

Scenario Unit: Each

Scenario Typical Size: 1

Total Scenario Cost: \$3,098.82

Scenario Cost/Unit: \$3,098.82

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	2.5	\$77.05
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$24.55	1	\$24.55
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	2	\$44.39
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$44.78	1	\$44.78

Equipment Installation

Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.84	1	\$4.84
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$126.00	2	\$252.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$49.40	1	\$49.40
Truck, dump, 8 CY	1401	Dump truck for moving bulk material. Typically capacity is 12 ton or 8 cubic yards. Includes equipment only.	Hour	\$63.76	0.5	\$31.88

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$541.06	1	\$541.06
-------------------------------	------	--	------	----------	---	----------

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$283.39	1	\$283.39
--------------------------------	------	---	------	----------	---	----------

Materials

Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$26.95	5	\$134.74
Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes materials and delivery (up to 100 miles) only.	Ton	\$34.32	15	\$514.77
Log, un-anchored	2035	Price of log picked up at the Mill. Includes material only.	Ton	\$40.58	4	\$162.33
Rock Riprap, graded, angular, material and shipping	1200	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$31.12	30	\$933.65

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #10 - Deflector, Rock > 80 ton

Scenario Description: This scenario describes the implementation of a stream habitat improvement and management project where practices are focused on instream habitat improvement with a combination of rock AND wood structures. This scenario involves placement of large rock deflector (> 80tons) with or without log structures into a stream channel in order to improve aquatic habitat that currently does not meet quality criteria for stream species habitat. A stream assessment (i.e. Stream Visual Assessment Protocol) should be conducted in order to document habitat components (such as large wood, pools) are not currently present in the stream or are limited for aquatic species. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Rock deflectors, generally more than one, will be placed in the stream to create pool habitat and hydraulic complexity according to NRCS engineering specifications and with close review & approval of a fish habitat biologist onsite during the planning and implementation of the project. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of project implementation. Records demonstrating implementation of this scenario will address resource concerns for stream species of concern will be required. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

Before Situation: In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream habitat components, such as large wood and off-channel refuge habitat.

After Situation: Stream habitat within the project reach is improving as a result of placing a rock deflector into the channel from the stream bank. Stream habitat in the reach is improved, and hiding cover, food availability and refuge habitat for all stream species is improving.

Scenario Feature Measure: Each Large Rock/Rocklog

Scenario Unit: Each

Scenario Typical Size: 1

Total Scenario Cost: \$5,003.95

Scenario Cost/Unit: \$5,003.95

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	3.5	\$107.88
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$24.55	3	\$73.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	3	\$66.58
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$44.78	1	\$44.78

Equipment Installation

Chainsaw	937	Equipment and power unit costs. Labor not included.	Hour	\$4.84	2	\$9.68
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$126.00	3	\$378.00
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$49.40	3	\$148.21
Truck, dump, 8 CY	1401	Dump truck for moving bulk material. Typically capacity is 12 ton or 8 cubic yards. Includes equipment only.	Hour	\$63.76	0.5	\$31.88

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$541.06	1	\$541.06
-------------------------------	------	--	------	----------	---	----------

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$283.39	1	\$283.39
--------------------------------	------	---	------	----------	---	----------

Materials

Aggregate, river rock	1834	Well graded, rounded mineral substrates derived from local riverine settings. Includes materials and local delivery	Ton	\$26.95	20	\$538.96
Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes materials and delivery (up to 100 miles) only.	Ton	\$34.32	40	\$1,372.71
Log, un-anchored	2035	Price of log picked up at the Mill. Includes material only.	Ton	\$40.58	4	\$162.33
Rock Riprap, graded, angular, material and shipping	1200	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$31.12	40	\$1,244.86

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #11 - Defector Group of 3 Root Wads

Scenario Description: This scenario describes the implementation of a stream habitat improvement and management project where practices are focused on instream habitat improvement with a combination of rock AND wood structures. This scenario involves placement of large wood structures, called root wads, supported by boulders in order to improve aquatic habitat that currently does not meet quality criteria for stream species habitat. A stream assessment (i.e. Stream Visual Assessment Protocol) should be conducted in order to document habitat components (such as large wood, pools) are not currently present in the stream or are limited for aquatic species. A project design for placement of habitat structures (boulders, boulder clusters, wood, wood structures) will be based on assessment of (a) the target stream reach characteristics and (b) those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Rock boulder sizes should also reflect the geomorphic setting of the stream reach. Large wood root wads placed into the stream under this scenario should be similar in species, age, and size (diameter) as trees found in the surrounding riparian area, to the extent possible. Wood, boulders and/or boulder clusters will be placed in the stream to create pool habitat and hydraulic complexity according to NRCS engineering specifications and with close review & approval of a fish habitat biologist onsite during the planning and implementation of the project. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of project implementation. Records demonstrating implementation of this scenario will address resource concerns for stream species of concern will be required. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

Before Situation: In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream habitat components, such as large wood and off-channel refuge habitat.

After Situation: Stream habitat within the project reach is improving as a result of placing a group of 3 root wads anchored with boulders protruding along the stream bank. Pool habitat in the reach is improved, and hiding cover, food availability and refuge habitat for all stream species is improving.

Scenario Feature Measure: Each group of 3

Scenario Unit: Each

Scenario Typical Size: 1

Total Scenario Cost: \$2,729.06

Scenario Cost/Unit: \$2,729.06

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	12	\$369.86
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	6	\$133.16

Equipment Installation

Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$126.00	6	\$755.99
Truck, dump, 12 CY	1215	Dump truck for moving bulk material. Typically capacity is 16 ton or 12 cubic yards. Includes equipment only.	Hour	\$107.14	6	\$642.86

Mobilization

Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$541.06	1	\$541.06
-------------------------------	------	--	------	----------	---	----------

Materials

Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes materials and delivery (up to 100 miles) only.	Ton	\$34.32	6	\$205.91
Root Wad	2045	Tree stump buried into the streambank with the roots left exposed. Includes material only.	Ton	\$8.91	9	\$80.21

Practice: 395 - Stream Habitat Improvement and Management

Scenario: #12 - Cross Vane Rock or Rock/log

Scenario Description: This scenario describes the implementation of a stream habitat improvement and management project where practices are focused on instream habitat improvement with a combination of rock AND wood structures. This scenario involves placement of rocks or a combination of rocks and logs across the entire stream channel in order to improve aquatic habitat that currently does not meet quality criteria for stream species habitat. Shape typically forms a "V" shape pointing upstream called a cross vane. A stream assessment (i.e. Stream Visual Assessment Protocol) should be conducted in order to document habitat components (such as large wood, pools) are not currently present in the stream or are limited for aquatic species. A project design for placement of a cross vane will be based on assessment of (a) the target stream reach characteristics and (b) those of a suitable reference reach. These characteristics include channel geometry, channel slope, stream bottom substrate size and composition, and the geomorphic setting influencing the channel form, pattern and profile. Rock boulder sizes should also reflect the geomorphic setting of the stream reach. Large wood placed into the stream under this scenario should be similar in species, age, and size (diameter) as trees found in the surrounding riparian area, to the extent possible. The planned activity will meet the current 395 standard, and facilitating practice standards utilized. Implementation will result in the improvement of instream habitat complexity, hiding and resting cover, and/or increased food availability for fish and other stream species. Payment for implementation is to defray the costs of project implementation. Records demonstrating implementation of this scenario will address resource concerns for stream species of concern will be required. Associated Practices: Critical Area Planting (342) and Streambank and Shoreline Protection (580)

Before Situation: In this stream reach, habitat for fish, aquatic insects and/or other stream species is sub-optimal as determined by the NRCS Stream Visual Assessment Protocol score of less than 5. The site does not have adequate food, cover, and perhaps habitat connectivity for desired species. Riparian vegetation quality and/or quantity may also be compromised to the extent that the riparian area and floodplain are not functioning to provide necessary stream habitat components, such as large wood and off-channel refuge habitat.

After Situation: Stream habitat within the project reach is improving as a result of placing a 30' long rock or rock log cross vane across the entire channel. Pool habitat in the reach is improved, and hiding cover, food availability and refuge habitat for all stream species is improving.

Scenario Feature Measure: Each Cross vane

Scenario Unit: Each

Scenario Typical Size: 1

Total Scenario Cost: \$3,070.23

Scenario Cost/Unit: \$3,070.23

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$30.82	4	\$123.29
Equipment Operators, Light	232	Includes: Skid Steer Loaders, Hydraulic Excavators <50 HP, Trenchers <12", Ag Equipment <150 HP, Pickup Trucks, Forklifts, Mulchers	Hour	\$24.55	4	\$98.18
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$22.19	4	\$88.78
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$44.78	4	\$179.11

Equipment Installation

Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$126.00	4	\$503.99
Skidsteer, 80 HP	933	Skidsteer loader with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$49.40	4	\$197.62

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$283.39	2	\$566.78
--------------------------------	------	---	------	----------	---	----------

Materials

Boulder	1761	Rock boulders (approximately 5 ft dia. 6.67 Tons) Includes	Ton	\$34.32	6	\$205.91
---------	------	--	-----	---------	---	----------

		materials and delivery (up to 100 miles) only.				
Log, un-anchored	2035	Price of log picked up at the Mill. Includes material only.	Ton	\$40.58	4	\$162.33
Rock Riprap, graded, angular, material and shipping	1200	Graded Rock Riprap for all gradation ranges. Includes materials and delivery only.	Ton	\$31.12	30	\$933.65
Steel, rebar	1832	Steel rebar, grade 60. Materials only.	Pound	\$0.53	20	\$10.61