

Practice: 672 - Building Envelope Improvement

Scenario: #1 - Building Envelope - Attic Insulation

Scenario Description: Install a minimum of R-7 insulation in addition to existing attic or ceiling to reduce heat transfer. Increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate.

Before Situation: A poultry house with an inefficient building envelope with limited attic insulation.

After Situation: A more effective and efficient building envelope can be created through addition of, or increased, attic insulation. Associated practices/activities: 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Scenario Feature Measure: Area of Attic Insulated

Scenario Unit: Square Foot

Scenario Typical Size: 20000

Total Scenario Cost: \$16,272.00

Scenario Cost/Unit: \$0.81

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Materials

Insulation, Fiberglass or cellulose, R-15	1196	Fiberglass or cellulose insulation R-15, includes materials, equipment and labor to install.	Square Foot	\$0.81	20000	\$16,272.00
---	------	--	-------------	--------	-------	-------------

Practice: 672 - Building Envelope Improvement

Scenario: #2 - Building Envelope - Wall Insulation

Scenario Description: Enclose both sidewalls and endwalls from ceiling to floor in one of two manners: 1) metal exterior, 3.5" fiberglass batts (R-11), vapor barrier, & interior plywood or OSB sheathing, or 2) closed-cell polyurethane foam application (minimum 1" thickness (R-7) of 2.5 lbs/cu.ft. or higher density, (3.0 or higher density preferred) with a form of physical protective barrier on lower 2' (may be 6 lbs/cu.ft. or higher density 1/8" thick foam, or treated lumber). Based on a 40' x 400' poultry house.

Before Situation: A poultry house with an inefficient building envelope with limited wall insulation.

After Situation: A more effective and efficient building envelope can be created through addition of, or increased, insulation. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Scenario Feature Measure: Area of Attic Insulated

Scenario Unit: Square Foot

Scenario Typical Size: 4500

Total Scenario Cost: \$8,924.18

Scenario Cost/Unit: \$1.98

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Materials

Insulation, Panel, R-11 with sheathing	1197	Insulated wall panel typically 3.5" fiberglass batts (R-11), vapor barrier and OSB sheathing, or equal, includes materials, equipment and labor to install.	Square Foot	\$1.98	4500	\$8,924.18
--	------	---	-------------	--------	------	------------

Practice: 672 - Building Envelope Improvement

Scenario: #3 - Building Envelope - Sealant

Scenario Description: A typical scenario is sealing the gaps between walls, gables, ceiling, etc. in a poultry house or greenhouse. Sealing is performed by a professional contractor, not merely use of spray foam from a can. The unit basis of payment in this scenario is each house based on 60' x 500' poultry house with an assumed need of sealant to seal 2400 linear feet of gap.

Before Situation: An agricultural facility with an inefficient building envelope with gaps between walls, ceiling, etc. for a total of 2400 linear feet.

After Situation: A more effective and efficient building envelope can be created through interior sealing of the exterior walls at the footer plate, eaves, ridge cap, and gable ends. The sealant reduces seasonal heat loss and heat gain due to infiltration which reduces the respective need for heating and cooling equipment to operate. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Scenario Feature Measure: Perimeter of heated structure

Scenario Unit: Foot

Scenario Typical Size: 2400

Total Scenario Cost: \$4,124.95

Scenario Cost/Unit: \$1.72

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Materials

Sealant	1150	Greenhouse and building gap sealant. Performed by a professional contractor spraying the areas with an approved sealant for poultry production facilities. Includes materials, equipment and labor to install.	Foot	\$1.72	2400	\$4,124.95
---------	------	--	------	--------	------	------------

Practice: 672 - Building Envelope Improvement

Scenario: #4 - Building Envelope - Greenhouse Screens

Scenario Description: The mechanical energy screen system consists of a drive motor, support cables, controls, and shade material, which may be woven, knitted, or non-woven strips of aluminum fiber, polyethylene, nylon or other synthetic material. The screen provides a means to better control solar heat gain and heat transfer during night or cold weather conditions to reduce energy use. Screens and similar devices may also be used to divide internal areas and allow for differentiated heating, ventilation, or cooling system operation to reduce energy use.

Before Situation: Heating and cooling of an existing greenhouse, or similar structure with conditioned spaces, is inefficient due to poorly regulated heat transfer. A need to regulate an entire space for uniform conditions when some portions have differing, intermittent requirements can also reduce efficiency.

After Situation: The greenhouse is fitted with a mechanically controlled energy screen installed truss-to-truss or gutter-to-gutter, with side screens as necessary, reducing heat loss in the greenhouse. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Scenario Feature Measure: Area of Screen

Scenario Unit: Square Foot

Scenario Typical Size: 25000

Total Scenario Cost: \$49,785.81

Scenario Cost/Unit: \$1.99

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$34.38	16	\$550.09
---------------	-----	---	------	---------	----	----------

Materials

Thermal blanket 10,001 - 50,000 square foot	1148	Thermal blanket greenhouse screens: mechanical energy screen system consists of a drive motor, support cables, controls, and shade material, which may be woven, knitted, or non-woven. Size Range is 10,001 to 50,000 square feet. Materials only.	Square Foot	\$1.97	25000	\$49,235.73
---	------	---	-------------	--------	-------	-------------

Practice: 672 - Building Envelope Improvement

Scenario: #5 - Greenhouse - Insulate Unglazed Walls

Scenario Description: A typical scenario is the installation insulation in green house to address energy loss. The insulation can be either of the cellulose or bubble type (or equivalent). The increased insulation reduces seasonal heat loss and heat gain which reduces the respective need for heating and cooling equipment to operate.

Before Situation: Green house with standard glazing, plastic or polycarbonate walls and no insulation. Heating and cooling of an existing greenhouse is inefficient due to excessive heat loss.

After Situation: The greenhouse is fitted with insulation installed truss-to-truss or gutter-to-gutter and/or non glazed endwalls and/or sidewalls, reducing heat loss and gain in the greenhouse. Associated practices/activities: may include 122-AgEMP - HQ and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Scenario Feature Measure: Square Feet of insulation

Scenario Unit: Square Foot

Scenario Typical Size: 25000

Total Scenario Cost: \$7,634.79

Scenario Cost/Unit: \$0.31

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Labor

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$34.38	16	\$550.09
---------------	-----	---	------	---------	----	----------

Materials

Insulation, Greenhouse, Reflective Bubble	2410	Double bubble reflective insulation with aluminum foil on both sides. Includes materials and shipping only.	Square Foot	\$0.28	25000	\$7,084.70
---	------	---	-------------	--------	-------	------------

Practice: 672 - Building Envelope Improvement

Scenario: #6 - Spray Foam Insulation

Scenario Description: Spray foam insulation is installed to the thickness to the appropriate R value in the walls and the ceilings of a walk-in refrigeration unit. Insulation standards are set by the American Society of Heating, Refrigeration, and Air Conditioning Engineers (ASHRAE) for walk-in coolers. Only coolers used to support on-farm production and storage can be insulated. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612. Payment is based on 1" of insulation material at R-7 value. Additional inches may be required to meet R-25.

Before Situation: A walk-in refrigeration unit does not meet the minimum insulation value and results in air leaks and energy inefficiency.

After Situation: An application of 1 inch of closed-cell spray foam insulation is installed with a value of R-7. Additional applications of spray foam insulation may be needed to achieve R-25 value, which is the minimum insulation value from ASHRAE standards. The typical application is for a walk-in refrigeration unit 116 feet long by 62 feet wide and 20 feet high. The spray foam insulation is installed on both the walls and ceilings to prevent air leaks and increase energy efficiency. Local building code may require a thermal and/or ignition barrier for all exposed applications. Ceiling applications in climate zones 5 or higher need to address moisture concerns.

Scenario Feature Measure: Square foot of surface area of walls and ceilings

Scenario Unit: Square Foot

Scenario Typical Size: 14312

Total Scenario Cost: \$32,749.43

Scenario Cost/Unit: \$2.29

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Materials

Insulation, polyurethane, R-7, with sheathing skirt	1198	Closed-cell polyurethane foam insulation (minimum 1" thickness (R-7) with a protective sheathing barrier on lower 2 feet of wall height. Includes materials, equipment and labor to install.	Square Foot	\$2.29	14312	\$32,749.43
---	------	--	-------------	--------	-------	-------------

Practice: 672 - Building Envelope Improvement

Scenario: #70 - Wall Insulation Only

Scenario Description: Increase insulation value to R-15 by adding insulation to side walls. Based on a 40' x 400' poultry house with 40 feet of cooling pad per house per side. Square footage does not include vents, fans, or door areas.

Before Situation: A poultry house with an inefficient building envelope with limited wall insulation.

After Situation: A more effective and efficient building envelope can be created through addition of, or increased, insulation. Associated practices/activities: may include 128-AgEMP and 374-Farmstead Energy Improvement. The resource concern is inefficient use of energy in the farm operation which increases dependence on non-renewable energy sources and can be addressed through improved energy efficiency. Any improvements are based on a Type 2 energy audit meeting the requirements of ASABE S612.

Scenario Feature Measure: Area of Wall Insulated

Scenario Unit: Square Foot

Scenario Typical Size: 2642

Total Scenario Cost: \$2,149.53

Scenario Cost/Unit: \$0.81

Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

Materials

Insulation, Fiberglass or cellulose, R-15	1196	Fiberglass or cellulose insulation R-15, includes materials, equipment and labor to install.	Square Foot	\$0.81	2642	\$2,149.53
---	------	--	-------------	--------	------	------------