

**Practice: 658 - Wetland Creation****Scenario: #1 - Wetland Creation****Scenario Description:**

A wetland is created on a flat mineral upland at a location where surface runoff may be intercepted and ponded by excavation. Resource concerns are 22 - INADEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

**Before Situation:**

The site is in cropland on an upland, non floodplain site (interfluvial).

**After Situation:**

An excavation with an average depth of 12" has created a shallow depression in a broad swale which intercepts surface runoff. The excavated material has been spread on adjacent areas. The INADEQUATE HABITAT FOR FISH AND WILDLIFE resource concern has been addressed with the provision of seasonal open water for terrestrial, aquatic, and waterfowl species.

**Scenario Feature Measure:** Acres of Wetland

**Scenario Unit:** Acre

**Scenario Typical Size:** 5

**Scenario Cost:** \$19,636.22

**Scenario Cost/Unit:** \$3,927.24

**Cost Details (by category):**

| Component Name                                       | ID   | Component Description   | Unit       | Price (\$/unit) | Quantity | Cost        |
|--|------|---|------------|-----------------|----------|-------------|
| <b>Equipment/Installation</b>                        |      |   |            |                 |          |             |
| Excavation, Common Earth, side cast, small equipment | 48   | Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor. | Cubic yard | \$2.30          | 8067     | \$18,554.10 |
| <b>Mobilization</b>                                  |      |   |            |                 |          |             |
| Mobilization, large equipment                        | 1140 | Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.                  | Each       | \$541.06        | 2        | \$1,082.12  |