

# CONSTRUCTION SPECIFICATION

## TRAILS AND WALKWAYS

**1. SCOPE**

The work shall consist of furnishing materials and installing all components of the trails and walkways as outlined in this specification and the drawings.

**2. MATERIALS**

All materials used shall conform to the quality and grade noted on the plans, set forth in Section 8, or as otherwise listed below:

WEARING SURFACE, BINDER COURSE, and BASE COURSE aggregate shall meet the requirements and gradation specified in Section 8 or on the drawings.

GEOTEXTILE shall meet the requirements as outlined in the following table or as otherwise set forth in Section 8 or on the drawings:

<b>Requirements for Nonwoven Geotextiles</b>		
<b>Property</b>	<b>Test Method</b>	<b>Value</b>
Tensile Strength	ASTM D4632 Grab Test	115 lbs
Elongation at Failure	ASTM D 4632	> 50%
Puncture	ASTM D 4833	40 lbs
Apparent opening size	ASTM D 4751	#40 max.
Permittivity	ASTM D 4491	0.10 secs <sup>-1</sup>
Ultraviolet light (%residual tensile strength)	ASTM D 4355 150 Hr Exposure	70%

PIPE shall meet the requirements specified in Section 8 or on the drawings.

WOOD PRODUCTS shall be Douglas Fir, Southern Yellow Pine, or as otherwise

specified on the drawings or in Section 8. They shall be treated with preservatives in accordance with the American Wood Preservers Association (AWPA) Standard C16, "Wood Used on Farms, Pressure Treatment." Each piece shall bear the AWPA stamp of quality. In the absence of such a stamp, the Contractor or material supplier shall provide written certification that the pressure treated wood products meet the designated quality criteria.

FASTENERS for wood structures shall be stainless steel, galvanized, or otherwise protected from corrosion due to contact with moisture and soil.

**3. FOUNDATION PREPARATION**

All trees, brush, fences, manure, and rubbish shall be cleared within the trail or walkway area, including any associated drainage control features and borrow areas. All stumps and roots larger than two inch diameter shall be removed down to the subgrade elevation. All material removed by clearing operations shall be disposed of as directed by the Owner or his/her Representative.

Topsoil shall be stripped and stockpiled in a convenient location for use on disturbed areas to facilitate seeding.

Mineral soil shall be excavated and placed as fill as shown on the drawings to establish a uniform, stable subgrade. Wet soil, mud, and topsoil shall not be used as fill. The fill material shall be compacted as specified in Section 8 or on the drawings.

Borrow material shall be taken from the designated borrow area as needed after excavation of the trail or walkway is complete. The borrow area shall be final graded to drain freely and blend into the surrounding undisturbed area.

Excess excavated material shall be disposed of in the designated spoil area, which shall be graded to blend into the surrounding undisturbed area.

Geotextile or base course material shall be

set on undisturbed soil or non-yielding compacted material. Over-excavation must be corrected as noted on the drawings, or as directed by the Engineer or his/her designated Representative.

**4. DRAINAGE STRUCTURES**

Culverts, subsurface drains, and swales shall be installed as shown on the drawings. Surface and subsurface drainage structures shall be adequately removing water from the foundation to allow for proper placement of base and surface materials.

**5. GEOTEXTILE**

Where specified in Section 8 or on the drawings, geotextile shall be installed on the prepared subgrade. The geotextile shall be placed, overlapped and anchored as recommended by the manufacturer, unless otherwise specified in Section 8 or on the drawings.

Vehicles and heavy equipment shall not be operated directly on top of the geotextile. Base course or surface material shall be placed on the geotextile ahead of the construction equipment.

**6. E&S CONTROL**

E&S control measures shall be as set forth in the E&S Plan, and as otherwise detailed in the drawings.

Vegetation shall be established as set forth in Construction Specification PA 342, and/or as set forth in Section 8 and the drawings.

**7. SURFACING**

Where specified in Section 8 or on the drawings, the base and binder course shall be placed on the trail or walkway to the specified grades and thickness. The material shall be wetted and compacted by rollers or other construction equipment approved by the Engineer.

Surface material shall be placed to the grades and thicknesses set forth in Section 8 or on the drawings. The material shall be compacted by rollers or other construction equipment approved by the Engineer. The finished surface shall be smooth and free of projecting stones.

Vegetation shall be established in accordance with Construction Specification PA342.

The surface material in or adjacent to surface water control devices and other structures shall be compacted using manually directed tamping equipment.

**8. ADDITIONAL CONDITIONS WHICH APPLY TO THIS PROJECT ARE:**