PIKE

- HIGHLY ERODIBLE LAND CLASSES -
1 = HIGHLY ERODIBLE LAND
2 = POTENTIALLY HIGHLY ERODIBLE
3 = NOT HIGHLY ERODIBLE

HIGHLY ERODIBLE AND
POTENTIALLY HIGHLY ERODIBLE
LAND CACULATOR VER 1.1

MUID	MAP SYMBOL	SOIL NAME	*	%	C VALUE	WIND EROSIION I VALUE	HEL CLASS	R VALUE	K VALUE	T VALUE	WATER EROSION SLOPE-MIN.	PERCEN SLOPE--MAX.	LENGTH MIN.	LENGTH MAX.	LS-MIN.	VALUE MAX.	ST/RK	HE CLA
103AT	AT	ATHERTON	1	100	0.8			150	0.37	5	0	3	100	400	0.069	0.435	0.721	3
103BRA	BRA	BRACEVILLE	1	100	0.8			150	0.2	3	0	3	100	400	0.069	0.435	0.800	3
103BRB2	BRB2	BRACEVILLE	1	100	0.8			150	0.2	3	3	8	100	400	0.287	1.982	0.800	2
103CAB2	CAB2	CATTARAUGUS	1	100	0.8			150	0.28	3	3	12	100	400	0.287	3.607	0.571	2
103CAC2	CAC2	CATTARAUGUS	1	100	0.8			150	0.28	3	12	20	100	400	1.804	8.157	0.571	1
103CEB	CEB	CATTARAUGUS	1	100	0.8			150	0.24	3	0	12	100	400	0.069	3.607	0.667	2
103CED	CED	CATTARAUGUS	1	100	0.8			150	0.24	3	12	30	100	400	1.804	15.905	0.667	1
103CGB	CGB	CATTARAUGUS	1	100	0.8			150	0.24	3	0	12	100	400	0.069	3.607	0.667	2
103CGD	CGD	CATTARAUGUS	1	100	0.8			150	0.24	3	12	30	100	400	1.804	15.905	0.667	1
103CHB	CHB	CHENANGO	1	100	0.8			150	0.24	3	3	12	100	400	0.287	3.607	0.667	2
103CHC	CHC	CHENANGO	1	100	0.8			150	0.24	3	12	20	100	400	1.804	8.157	0.667	1
103CHD	CHD	CHENANGO	1	100	0.8			150	0.24	3	20	30	100	400	4.078	15.905	0.667	1
103CLA	CLA	CHENANGO	1	100	0.8			150	0.24	3	0	3	100	400	0.069	0.435	0.667	3
103CLB2	CLB2	CHENANGO	1	100	0.8			150	0.24	3	3	12	100	400	0.287	3.607	0.667	2
103CMB	CMB	CHENANGO	1	100	0.8			150	0.24	3	0	12	100	400	0.069	3.607	0.667	2
103CMC	CMC	CHENANGO	1	100	0.8			150	0.24	3	12	20	100	400	1.804	8.157	0.667	1
103CMD	CMD	CHENANGO	1	100	0.8			150	0.24	3	20	30	100	400	4.078	15.905	0.667	1
103CNB2	CNB2	CULVERS	1	100	0.8			150	0.28	3	2	8	100	400	0.201	1.982	0.571	2
103CNC2	CNC2	CULVERS	1	100	0.8			150	0.28	3	8	15	100	400	0.991	5.119	0.571	1
103CUB	CUB	CULVERS	1	100	0.8			150	0.24	3	0	8	100	400	0.069	1.982	0.667	2
103CUD	CUD	CULVERS	1	100	0.8			150	0.24	3	8	25	100	400	0.991	11.780	0.667	1
103CVB	CVB	CULVERS	1	100	0.8			150	0.24	3	0	8	100	400	0.069	1.982	0.667	2
103CVC	CVC	CULVERS	1	100	0.8			150	0.24	3	8	25	100	400	0.991	11.780	0.667	1
103DEB	DEB	DEKALB	1	100	0.8			150	0.17	2	0	12	100	400	0.069	3.607	0.627	2
103DED	DED	DEKALB	1	100	0.8			150	0.17	2	12	30	100	400	1.804	15.905	0.627	1
103DEF	DEF	DEKALB	1	100	0.8			150	0.17	2	30	80	100	400	7.953	66.755	0.627	1
103DSB	DSB	DEKALB	1	50	0.8			150	0.17	2	0	12	100	400	0.069	3.607	0.627	2
103DSB	DSB	SWARTSWOOD	2	30	0.8			150	0.17	3	0	12	100	400	0.069	3.607	0.941	2
103DSD	DSD	DEKALB	1	50	0.8			150	0.17	2	12	30	100	400	1.804	15.905	0.627	1
103DSD	DSD	SWARTSWOOD	2	30	0.8			150	0.17	3	12	30	100	400	1.804	15.905	0.941	1
103DSF	DSF	DEKALB	1	50	0.8			150	0.17	2	30	80	100	400	7.953	66.755	0.627	1
103DSF	DSF	SWARTSWOOD	2	30	0.8			150	0.17	3	30	80	100	400	7.953	66.755	0.941	1
103HO	HO	HOLLY	1	100	0.8	48		150	0.28	5	0	3	100	400	0.069	0.435	0.952	3
103MAB	MAB	MANLIUS	1	100	0.8			150	0.28	3	0	12	100	400	0.069	3.607	0.571	2
103MAD	MAD	MANLIUS	1	100	0.8			150	0.28	3	12	30	100	400	1.804	15.905	0.571	1
103MLB	MLB	MANLIUS	1	100	0.8			150	0.2	3	0	12	100	400	0.069	3.607	0.800	2
103MLD	MLD	MANLIUS	1	100	0.8			150	0.2	3	12	30	100	400	1.804	15.905	0.800	1
103MLF	MLF	MANLIUS	1	100	0.8			150	0.2	3	30	50	100	400	7.953	35.646	0.800	1
103MNB2	MNB2	MARDIN	1	100	0.8			150	0.24	3	2	8	100	400	0.201	1.982	0.667	2
103MNC2	MNC2	MARDIN	1	100	0.8			150	0.24	3	8	15	100	400	0.991	5.119	0.667	1
103MOB	MOB	MARDIN	1	100	0.8			150	0.24	3	0	8	100	400	0.069	1.982	0.667	2
103MOC	MOC	MARDIN	1	100	0.8			150	0.24	3	8	25	100	400	0.991	11.780	0.667	1
103MR	MR	MIDDLEBURY	1	100	0.8			150	0.28	5	0	3	100	400	0.069	0.435	0.952	3
103MSB2	MSB2	MORRIS	1	100	0.8			150	0.28	4	3	8	100	400	0.287	1.982	0.762	2
103MTB	MTB	MORRIS	1	100	0.8			150	0.24	4	0	8	100	400	0.069	1.982	0.889	2
103MTC	MTC	MORRIS	1	100	0.8			150	0.24	4	8	15	100	400	0.991	5.119	0.889	1
103MU	MU	MUCK	1	100	0.8			150			0	3	100	400	0.069	0.435	ERROR	ERRO
103NOA	NOA	NORWICH	1	100	0.8			150	0.24	3	0	3	100	400	0.069	0.435	0.667	3
103NRB	NRB	NORWICH	1	100	0.8			150	0.24	3	0	8	100	400	0.069	1.982	0.667	2
1030AB2	OAB2	OQUAGA	1	100	0.8			150	0.28	3	3	12	100	400	0.287	3.607	0.571	2
1030EB	OEB	OQUAGA	1	100	0.8			150	0.2	3	0	12	100	400	0.069	3.607	0.800	2
1030ED	OED	OQUAGA	1	100	0.8			150	0.2	3	12	30	100	400	1.804	15.905	0.800	1
1030EF	OEF	OQUAGA	1	100	0.8			150	0.2	3	30	80	100	400	7.953	66.755	0.800	1
1030VB	OVB	OQUAGA	1	100	0.8			150	0.2	3	0	12	100	400	0.069	3.607	0.800	2
1030VD	OVD	OQUAGA	1	100	0.8			150	0.2	3	12	30	100	400	1.804	15.905	0.800	1
103PA	PA	PAPAKATING	1	100	0.8	48		150	0.28	5	0	3	100	400	0.069	0.435	0.952	3
103PE	PE	PEAT	1	100	0.8			150			0	3	100	400	0.069	0.435	ERROR	ERRO
103PS	PS	PEAT	1	100	0.8			150			0	3	100	400	0.069	0.435	ERROR	ERRO
103RH	RH	RED HOOK	1	100	0.8			150	0.32	3	0	3	100	400	0.069	0.435	0.500	3

103RH	RH	RED HOOK	1	100	0.8			150	0.32	3	0	3	100	400	0.069	0.435	0.500	3
103RV	RV	RIVERWASH	1	100	0.8			150	0.43	5	0	3	100	400	0.069	0.435	0.620	3
103RWE	RWE	RUSHTOWN	1	100	0.8			150	0.17	3	25	45	100	400	5.890	30.400	0.941	1
103SC	SC	STONY AND COBBLY A	1	100	0.8			150	0.43	5	0	3	100	400	0.069	0.435	0.620	3
103SMD	SMD	STONY LAND	1	100	0.8		0	150			15	25	100	400	2.559	11.780	ERROR	ERRO
103SSF	SSF	STONY LAND	1	100	0.8		0	150			25	80	100	400	5.890	66.755	ERROR	ERRO
103STB2	STB2	SWARTSWOOD	1	100	0.8			150	0.2	3	3	12	100	400	0.287	3.607	0.800	2
103STC2	STC2	SWARTSWOOD	1	100	0.8			150	0.2	3	12	20	100	400	1.804	8.157	0.800	1
103SWB	SWB	SWARTSWOOD	1	100	0.8			150	0.17	3	0	12	100	400	0.069	3.607	0.941	2
103SWD	SWD	SWARTSWOOD	1	100	0.8			150	0.17	3	12	30	100	400	1.804	15.905	0.941	1
103TA	TA	TIOGA	1	100	0.8			150	0.37	5	0	3	100	400	0.069	0.435	0.721	3
103TGA	TGA	TIOGA	1	100	0.8			150	0.37	5	0	3	100	400	0.069	0.435	0.721	3
103TGB	TGB	TIOGA	1	100	0.8			150	0.37	5	3	12	100	400	0.287	3.607	0.721	2
103TO	TO	TIOGA	1	100	0.8			150	0.37	5	0	3	100	400	0.069	0.435	0.721	3
103TSA	TSA	TUGHILL	1	100	0.8			150	0.24	3	0	3	100	400	0.069	0.435	0.667	3
103TTA	TTA	TUGHILL	1	100	0.8			150	0.17	3	0	3	100	400	0.069	0.435	0.941	3
103TUB	TUB	TUNKHANNOCK	1	100	0.8			150	0.24	3	3	12	100	400	0.287	3.607	0.667	2
103TUC	TUC	TUNKHANNOCK	1	100	0.8			150	0.24	3	12	20	100	400	1.804	8.157	0.667	1
103TUD	TUD	TUNKHANNOCK	1	100	0.8			150	0.24	3	20	30	100	400	4.078	15.905	0.667	1
103VCA	VCA	VOLUSIA	1	100	0.8			150	0.24	3	0	3	100	400	0.069	0.435	0.667	3
103VCB2	VCB2	VOLUSIA	1	100	0.8			150	0.24	3	3	8	100	400	0.287	1.982	0.667	2
103VUB	VUB	VOLUSIA	1	100	0.8			150	0.24	3	0	8	100	400	0.069	1.982	0.667	2
103VUD	VUD	VOLUSIA	1	100	0.8			150	0.24	3	8	25	100	400	0.991	11.780	0.667	1
103WUB	WUB	WURTSBORO	1	100	0.8			150	0.24	3	0	8	100	400	0.069	1.982	0.667	2
103WUC	WUC	WURTSBORO	1	100	0.8			150	0.24	3	8	25	100	400	0.991	11.780	0.667	1