

**STATEMENT OF WORK**  
**Wetland Enhancement (659)**  
**South Carolina**

**These deliverables apply to this individual practice. For other planned practice deliverables, refer to those specific Statements of Work.**

## **DESIGN**

---

### **Deliverables:**

1. Design documentation that will demonstrate that the criteria in the NRCS practice standard have been met and are compatible with other planned and applied practices.
  - a. Practice purpose(s) as identified in the conservation plan
  - b. List of required permits to be obtained by the client
  - c. Impacts on adjacent properties and structures
  - d. Compliance with NRCS national and state utility safety policy (NEM, Part 503-Safety, Subpart A - Engineering Activities Affecting Utilities 503.00 through 503.06)
  - e. List of facilitating practices
  - f. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
    - i. Compliance with Wetland Functional Assessment and Hydric Soils Determination
    - ii. Hydrology/Hydraulics
    - iii. Structural including hazard class as appropriate
    - iv. Vegetation
2. Written plans and specifications including sketches and drawings shall be provided to the client which adequately describes the requirements to install the practice and obtain necessary permits.
3. Design Report and Inspection Plan as appropriate (NEM, Part 511, Subpart B - Documentation, 511.11 and Part 512, Subpart D - Quality Assurance Activities, 512.30 through 512.32).
4. An Operation and Maintenance Plan for the project.
5. Certifications that the design meets practice standard criteria and complies with applicable laws and regulations [NEM, Subpart A, 505.03(b)(2)].
6. Design modifications during installation, as required.

## **INSTALLATION**

---

### **Deliverables**

1. Pre-Installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
  - a. Actual materials used.
  - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meet design and permit requirements.

## **CHECK OUT**

---

### **Deliverables**

1. As-Built documentation.
  - a. Extent of practice units applied
  - b. Drawings
  - c. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits [NEM, Subpart A, 505.03 (c) (1)].
3. Progress reporting.

**STATEMENT OF WORK**  
**Wetland Enhancement (659)**  
**South Carolina**

**REFERENCES**

---

- NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard - Wetland Enhancement, 659.
- NRCS National Engineering Manual (NEM)
- NRCS Engineering Field Handbook (EFH), Part 210, Chapter 13, Wetland Restoration, Enhancement, or Creation
- NRCS National Environmental Compliance Handbook
- NRCS Cultural Resources Procedures Handbook
- NRCS National Biology Manual
- NRCS National Biology Handbook
- National Food Security Act Manual
- Wetland Functional Assessment for Southeastern Depression Wetlands and Mineral Flats