

Practice: 412 - Grassed Waterway**Scenario: #1 - GWW < 1000ft long****Scenario Description:**

Typical practice is 500' long, 12' bottom, 8:1 side slopes, 1.5' depth, half excavation. A grass waterway that is a shaped or graded channel and is established with suitable vegetation to carry surface water at a non-erosive velocity to a stable outlet. This practice addresses Concentrated Flow Erosion (Classic Gully & Ephemeral Erosion) and Excessive Sediment in surface waters. Waterway area measured from top of bank to top of bank. Costs include excavation and associated work to construct the overall shape and grade of the waterway.

Before Situation:

The field has a small gully which is cutting deeper into the field as time goes on, so it needs to be stopped or controlled. Excessive sedimentation and soil erosion as a result from ephemeral or classic gully erosion. Gully has formed in field as a result of excessive runoff and poor cropping techniques. Grassed waterway is also commonly installed to convey runoff from concentrated flows, terraces, diversions, or water control structures or similar practices to a suitable, stable outlet.

After Situation:

Installed grassed waterway is 500' long, 12' bottom, 8:1 side slopes, 1.5' depth. The practice is installed using a dozer. If erosion control blankets or mulching for seedbed establishment/protection are needed, use conservation practice Mulching (484). Drainage tile, if needed, will be installed according to Subsurface Drain (606). Outlets, if needed will be installed using Structure for Water Control (587). If inlet Structures are needed with the drainage tile, then those will be installed using Underground Outlet (620).

Scenario Feature Measure: Square Foot of Waterway

Scenario Unit: Square Foot

Scenario Typical Size: 18,000

Scenario Cost: \$982.07

Scenario Cost/Unit: \$0.05

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.53	334	\$511.02
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.06	0.4	\$4.82
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$9.69	0.4	\$3.88
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.50	0.4	\$2.60
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.01	3	\$111.03
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.41	1	\$18.41
Materials						
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.54	20	\$10.80
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.72	20	\$14.40
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$49.09	0.21	\$10.31
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.85	20	\$17.00

Materials

Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	\$49.65	0.4	\$19.86
--	------	--	------	---------	-----	---------

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$257.94	1	\$257.94
--------------------------------	------	---	------	----------	---	----------

Practice: 412 - Grassed Waterway**Scenario: #2 - GWW > 1,000ft long****Scenario Description:**

Typical practice is 1,500' long, 12' bottom, 8:1 side slopes, 1.5' depth, half excavation. A grass waterway that is a shaped or graded channel and is established with suitable vegetation to carry surface water at a non-erosive velocity to a stable outlet. This practice addresses Concentrated Flow Erosion (Classic Gully & Ephemeral Erosion) and Excessive Sediment in surface waters. Waterway area measured from top of bank to top of bank. Costs include excavation and associated work to construct the overall shape and grade of the waterway.

Before Situation:

The field has a small gully which is cutting deeper into the field as time goes on, so it needs to be stopped or controlled. Excessive sedimentation and soil erosion as a result from ephemeral or classic gully erosion. Gully has formed in field as a result of excessive runoff and poor cropping techniques. Grassed waterway is also commonly installed to convey runoff from concentrated flows, terraces, diversions, or water control structures or similar practices to a suitable, stable outlet.

After Situation:

Installed grassed waterway is 1,500' long, 12' bottom, 8:1 side slopes, 1.5' depth. The practice is installed using a dozer. If erosion control blankets or mulching for seedbed establishment/protection are needed, use conservation practice Mulching (484). Drainage tile, if needed, will be installed according to Subsurface Drain (606). Outlets, if needed will be installed using Structure for Water Control (587). If inlet Structures are needed with the drainage tile, then those will be installed using Underground Outlet (620).

Scenario Feature Measure: Acre of Waterway**Scenario Unit: Acre****Scenario Typical Size: 1****Scenario Cost: \$2,230.66****Scenario Cost/Unit: \$2,230.66****Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$9.69	1.25	\$12.11
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.53	1000	\$1,530.00
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.06	1.25	\$15.08
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.50	1.25	\$8.13
Labor						
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.41	5	\$92.05
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.01	1	\$37.01
Materials						
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	\$49.65	1.25	\$62.06
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.85	50	\$42.50
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.72	60	\$43.20
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.54	60	\$32.40

Materials

Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$49.09	2	\$98.18
-----------	----	--	-----	---------	---	---------

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$257.94	1	\$257.94
--------------------------------	------	---	------	----------	---	----------

Practice: 412 - Grassed Waterway**Scenario: #3 - GWW with geotextile or stone checks****Scenario Description:**

Typical practice is 1,200' long, 12' bottom, 8:1 side slopes, 1.5' depth, half excavation. A grass waterway that is a shaped or graded channel and is established with suitable vegetation to carry surface water at a non-erosive velocity to a stable outlet. Fabric or stone checks are installed every 100 feet along the length of the waterway perpendicular to waterflow and are 2/3 the waterway top width to reduce maintenance and provide temporary protection until vegetation is established. Fabric Checks are installed 18" deep with 12" laid over on the surface. (Alternatively, rock checks could be installed). This practice addresses Concentrated Flow Erosion (Classic Gully & Ephemeral Erosion) and Excessive Sediment in surface waters. Waterway area measured from top of bank to top of bank. Seeding area is 20% greater than waterway area to account for disturbed areas. Costs include excavation and associated work to construct the overall shape and grade of the waterway.

Before Situation:

The field has a small gully which is cutting deeper into the field as time goes on, so it needs to be stopped or controlled. Excessive sedimentation and soil erosion as a result from ephemeral or classic gully erosion. Gully has formed in field as a result of excessive runoff and poor cropping techniques. Grassed waterway is also commonly installed to convey runoff from concentrated flows, terraces, diversions, or water control structures or similar practices to a suitable, stable outlet.

After Situation:

Installed grassed waterway is 1,200' long, 12' bottom, 8:1 side slopes, 1.5' depth. Fabric checks are installed every 100 feet along the length of the waterway. The practice is installed using a dozer. Fabric or stone checks are installed with small backhoe and labor. If erosion control blankets or mulching for seedbed establishment/protection are needed, use conservation practice Mulching (484). Drainage tile, if needed, will be installed according to Subsurface Drain (606). Outlets, if needed will be installed using Structure for Water Control (587). If inlet Structures are needed with the drainage tile, then those will be installed using Underground Outlet (620).

Scenario Feature Measure: Acre of Waterway**Scenario Unit: Acre****Scenario Typical Size: 1****Scenario Cost: \$2,645.02****Scenario Cost/Unit: \$2,645.02****Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.50	1	\$6.50
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.06	1	\$12.06
Excavation, common earth, large equipment, 50 ft	1222	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$1.53	800	\$1,224.00
Earthfill, Manually Compacted	50	Earthfill, manually compacted, includes equipment and labor	Cubic yard	\$4.85	33	\$160.05
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$9.69	1	\$9.69
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$1.99	33	\$65.67
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$37.01	2	\$74.02
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$18.41	12	\$220.92
Materials						
Geotextile, non-woven, light weight	1209	Non-woven less than 8 ounce/square yard geotextile with staple anchoring. Materials and shipping only.	Square Yard	\$1.13	132	\$149.16

Materials

Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.85	40	\$34.00
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.72	50	\$36.00
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$49.09	1.5	\$73.64
Four Species Mix, Cool Season, Introduced Perennial (2 grasses, 2 legumes)	2317	Cool season grass and legume mix. Includes material and shipping only.	Acre	\$49.65	1	\$49.65
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.54	50	\$27.00

Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$257.94	1	\$257.94
Mobilization, small equipment	1138	Equipment <70 HP but can't be transported by a pick-up truck or with typical weights between 3,500 to 14,000 pounds.	Each	\$173.49	1	\$173.49
Mobilization, very small equipment	1137	Equipment that is small enough to be transported by a pick-up truck with typical weights less than 3,500 pounds. Can be multiple pieces of equipment if all hauled simultaneously.	Each	\$71.23	1	\$71.23