

**Practice: 560 - Access Road**

**Scenario: #1 - New 6" gravel road in level terrain**

**Scenario Description:**

Newly Constructed gravel road with min. 6 inch thick compacted gravel surface in relatively level ground. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, surface material, vegetation of disturbed areas and all equipment, labor and incidental materials necessary to install the practice.

**Before Situation:**

An agricultural enterprise which requires, but does not have, a fixed travel way for equipment and vehicles for various resource activities and where use of equipment and vehicles within the enterprise without a defined access road would result in compaction, excessive sediment and turbidity in surface water, reduced visibility, and emissions of fugitive dust. This scenario is applicable where the resource activity areas consist of level terrain lands.

**After Situation:**

The road will be 14 feet wide with 6 inch gravel surfacing at the top. It is 90% on original ground with 10% on fill with an average fill height of 1 foot. Typical side slopes 2:1. A properly constructed, well defined access road will greatly reduce sheet, rill and wind erosion, eliminate compaction in land use areas where it is harmful, reduce emissions of particulate matter (PM) and PM precursors and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). All seeding or revegetation of disturbed areas is provided. Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).

**Scenario Feature Measure:** Length of Roadway

**Scenario Unit:** Feet

**Scenario Typical Size:** 1,000

**Scenario Cost:** \$12,560.39

**Scenario Cost/Unit:** \$12.56

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic yard	\$3.03	60	\$181.80
Mulcher, straw blower	1305	Straw bale mulcher/blower to mechanically spread small or large straw bales. Labor not included.	Hour	\$45.90	0.7	\$32.13
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$20.39	0.6	\$12.23
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.06	0.1	\$1.21
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$9.69	0.7	\$6.78
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.80	24	\$1,627.20
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$3.69	60	\$221.40
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.11	1670	\$3,523.70
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.50	0.7	\$4.55
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$25.02	1	\$25.02

**Labor**

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$22.84	24	\$548.16
----------------------------	-----	---	------	---------	----	----------

**Materials**

Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.72	35	\$25.20
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$118.54	1.4	\$165.96
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$32.72	0.1	\$3.27
Three Species Mix, Cool Season, Introduced Perennial Grass	2315	Cool season, introduced grass mix. Includes material and shipping only.	Acre	\$46.58	0.6	\$27.95
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$49.09	1.1	\$54.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.54	35	\$18.90
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.85	28	\$23.80
Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$20.15	275	\$5,541.25

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$257.94	2	\$515.88
--------------------------------	------	---	------	----------	---	----------

**Practice: 560 - Access Road**

**Scenario: #2 - Rehabilitation of existing gravel road in level terrain**

**Scenario Description:**

Repair and rehabilitation of gravel road with min. 6 inch thick compacted gravel surface on existing alignment in level terrain. The extent of construction work over an existing alignment is assumed to average 50% of the work for a new installation. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, surface material, vegetation of disturbed areas and all equipment, labor and incidental materials necessary to install the practice.

**Before Situation:**

An agricultural enterprise with an existing access road which is beyond its useful lifespan, can no longer be used as intended without rehabilitation. If left in its current condition, it will result in continued compaction, excessive sediment in surface water and emissions of fugitive dusts. This scenario is applicable where the resource activity areas with an existing but dilapidated access road consist of level terrain lands.

**After Situation:**

The damaged portions of the road will be repaired to a full 14 feet width with a 6" gravel surface at the top, mostly in original ground. Less than 10% of the total is in fill with an average height of 1' and typical side slopes 2:1. A properly repaired access road will greatly reduce or eliminate compaction in land use areas where it is harmful, reduce emissions of fugitive dust and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport and improving drainage of irrigated lands. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). All seeding or revegetation of disturbed areas is provided. Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).

**Scenario Feature Measure:** Length of Roadway

**Scenario Unit:** Feet

**Scenario Typical Size:** 1,000

**Scenario Cost:** \$6,133.12

**Scenario Cost/Unit:** \$6.13

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic yard	\$3.03	30	\$90.90
Dozer, 80 HP	929	Track mounted Dozer with horsepower range of 60 to 90. Equipment and power unit costs. Labor not included.	Hour	\$67.80	8	\$542.40
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.06	0.07	\$0.84
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$3.69	30	\$110.70
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.11	835	\$1,761.85
<b>Labor</b>						
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$22.84	8	\$182.72
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$25.02	3	\$75.06
<b>Materials</b>						
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$32.72	0.07	\$2.29
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$118.54	0.15	\$17.78

**Materials**

Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$20.15	140	\$2,821.00
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.54	3.5	\$1.89
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.85	2.8	\$2.38
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.72	3.5	\$2.52
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$49.09	0.1	\$4.91

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$257.94	2	\$515.88
--------------------------------	------	---	------	----------	---	----------

**Practice: 560 - Access Road**

**Scenario: #3 - New 6" gravel road in sloped terrain**

**Scenario Description:**

Newly Constructed gravel road with min. 6 inch thick compacted gravel surface on sloped ground. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, surface material, vegetation of disturbed areas and all equipment, labor and incidental materials necessary to install the practice.

**Before Situation:**

An agricultural enterprise which requires, but does not have, a fixed travelway for equipment and vehicles for various resource activities and where use of equipment and vehicles within the enterprise without a defined access road would result in compaction, excessive sediment and turbidity in surface water, reduced visibility, and emissions of fugitive dust. This scenario is applicable where the resource activity areas consist of land areas with sloped terrain.

**After Situation:**

The road will be 14 feet wide with 6 inch gravel surfacing at the top. Seventy percent will be on original ground with 15% in embankment less than 2 feet in depth (average 1 foot) and 15% in excavation less than 2 feet in height (average 1 ft) with typical side slopes 2:1. The excavation is assumed to be 80% common earth and 20% rock excavation. A properly constructed, well defined access road will greatly reduce sheet, rill and wind erosion, eliminate compaction in land use areas where it is harmful, reduce emissions of particulate matter (PM) and PM precursors and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). All revegetation of disturbed areas is provided. Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).

**Scenario Feature Measure:** Length of Roadway

**Scenario Unit:** Feet

**Scenario Typical Size:** 1,000

**Scenario Cost:** \$15,784.76

**Scenario Cost/Unit:** \$15.78

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Lime application	953	Lime application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$9.69	0.6	\$5.81
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$1.99	72	\$143.28
Excavation, Rock, Ripping	47	Excavation, rock, mechanical ripping, includes equipment and labor	Cubic yard	\$4.17	18	\$75.06
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.11	1670	\$3,523.70
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic yard	\$3.03	90	\$272.70
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$3.69	90	\$332.10
Fertilizer, ground application, dry bulk	950	Dry bulk fertilizer application performed by ground equipment. Includes equipment, power unit and labor costs.	Acre	\$6.50	0.6	\$3.90
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.06	0.1	\$1.21
Seeding Operation, No Till/Grass Drill	960	No Till drill or grass drill for seeding. Includes equipment, power unit and labor costs.	Acre	\$20.39	0.5	\$10.20
Dozer, 200 HP	928	Track mounted Dozer with horsepower range of 160 to 250. Equipment and power unit costs. Labor not included.	Hour	\$188.08	24	\$4,513.92

**Labor**

**Labor**

Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$25.02	1	\$25.02
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$22.84	24	\$548.16

**Materials**

Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$20.15	275	\$5,541.25
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$118.54	1.2	\$142.25
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$49.09	0.9	\$44.18
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.54	30	\$16.20
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.72	30	\$21.60
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.85	24	\$20.40
Three Species Mix, Cool Season, Introduced Perennial Grass	2315	Cool season, introduced grass mix. Includes material and shipping only.	Acre	\$46.58	0.6	\$27.95

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$257.94	2	\$515.88
--------------------------------	------	---	------	----------	---	----------

**Practice: 560 - Access Road**

**Scenario: #4 - Rehabilitation of existing gravel road in sloped terrain**

**Scenario Description:**

Repair and rehabilitation of gravel road with min. 6 inch thick compacted gravel surface on existing alignment in sloped terrain. The extent of construction work over an existing alignment is assumed to average 40% of the work for a new installation. A properly constructed, well defined access road will address resource concerns related with compaction, emissions of fugitive dust, and excessive sediment in surface water. It also improves the plant productivity, vigor and health and substantially reduces the chance of wild fire hazards. Short term air quality deterioration may result if proper dust control measures are not implemented during the practice installation. Costs include excavation, shaping, grading, surface material, vegetation of disturbed areas and all equipment, labor and incidental materials necessary to install the practice.

**Before Situation:**

An agricultural enterprise with an existing access road which is beyond its useful lifespan, can no longer be used as intended without rehabilitation. If left in its current condition, it will result in continued compaction, excessive sediment in surface water and emissions of fugitive dust. This scenario is applicable where the resource activity areas with an existing but dilapidated access road consist of land with steep sloped terrain.

**After Situation:**

The damaged portions of the road will be repaired to a full 14 feet width with a 6" gravel surface at the top. Approximately 85% of the road surface will need some regrading for 50% of the surface. The areas previously cut to install this road need no additional cut. The 15% of the road that has fill material will need to be refilled for 50% of the area. A properly repaired access road will greatly reduce or eliminate compaction in land use areas where it is harmful, reduce emissions of fugitive dust and also reduce excessive sediment in surface water by reducing uncontrolled sediment transport and improving drainage of irrigated lands. Planned grades will include all dips and water bars. If clearing and grubbing of land in the alignment area is required, use Land Clearing (460). Pipe culverts installed as part of access road should be covered by either Structures for Water Control (587) or Stream Crossings (578) depending on the type of structure. Earthfill embankment above the culvert structure would still be covered by this Practice. Diversions constructed as part of access road should be covered by Diversion (362). All seeding or revegetation of disturbed areas is provided. Dust control must be addressed under Dust Control on Unpaved Roads and Surfaces (373).

**Scenario Feature Measure:** Length of Roadway

**Scenario Unit:** Feet

**Scenario Typical Size:** 1,000

**Scenario Cost:** \$6,606.64

**Scenario Cost/Unit:** \$6.61

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Geotextile, woven	42	Woven Geotextile Fabric. Includes materials, equipment and labor	Square Yard	\$2.11	835	\$1,761.85
Seeding Operation, Broadcast, Ground	959	Broadcast seed via ground operation. May require post tillage operation to incorporate seed. Includes equipment, power unit and labor costs.	Acre	\$12.06	0.07	\$0.84
Dozer, 140 HP	927	Track mounted Dozer with horsepower range of 125 to 160. Equipment and power unit costs. Labor not included.	Hour	\$125.42	8	\$1,003.36
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$3.69	45	\$166.05
Earthfill, Dumped and Spread	51	Earthfill, dumped and spread without compaction effort, includes equipment and labor	Cubic yard	\$3.03	45	\$136.35
<b>Labor</b>						
Skilled Labor	230	Labor requiring a high level skill set: Includes carpenters, welders, electricians, conservation professionals involved with data collection, monitoring, and or record keeping, etc.	Hour	\$25.02	3.5	\$87.57
Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$22.84	8	\$182.72
<b>Materials</b>						
Straw	1237	Small grain straw (non organic and certified organic). Includes materials only.	Ton	\$118.54	0.15	\$17.78
One Species, Cool Season, Introduced Perennial Grass	2313	Introduced, cool season perennial grass. Includes material and shipping only.	Acre	\$32.72	0.07	\$2.29

**Materials**

Aggregate, Gravel, Ungraded, Quarry Run	1099	Includes materials, equipment and labor	Cubic yard	\$20.15	135	\$2,720.25
Lime, ENM	75	Fertilizer: Limestone Spread on field.	Ton	\$49.09	0.1	\$4.91
Nitrogen (N), Ammonium Nitrate	69	Price per pound of N supplied by Ammonium Nitrate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.85	2.8	\$2.38
Potassium, K2O	74	K2O supplied by Muriate Of Potash. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.54	3.5	\$1.89
Phosphorus, P2O5	73	Price per pound of P2O5 supplied by Superphosphate. Price is not per pound of total product applied, no conversion is needed.	Pound	\$0.72	3.5	\$2.52

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$257.94	2	\$515.88
--------------------------------	------	---	------	----------	---	----------