WORKSHEET FOR HIGHLY ERODIBLE LAND CLASSIFICATION
DYER COUNTY, TENNESSEE SEPT. 1988 (HCD)
R FACTOR-260 SL-50/200

SYMBOL	MAP UNIT NAME	K VALUE	T VALUE	MIN SLOPE	MAX SLOPE	LOW LS	HIGH LS	MIN LS	HEL CLASS
Ad	Adler silt loam, rarely fld.	0.43	5	0.0%	2.0%	0.060	0.247	0.358	NHEL
Ag	Alligator clay, occas. fld.	0.32	5	0.0%	2.0%	0.060	0.247	0.481	NHEL
At	Alligator-Crevasse complex, occas. fld.								NHEL
	Alligator part	0.32	5	0.0%	2.0%	0.060	0.247	0.481	
	Crevasse part	0.17	5	0.0%	2.0%	0.060	0.247	0.905	
Bd	Birds silt loam, occas. fld.	0.43	5	0.0%	2.0%	0.060	0.247	0.358	NHEL
Bo	Bosket sandy loam, rarely fld.	0.24	5	0.0%	2.0%	0.060	0.247	0.641	NHEL
Bs	Bosket silt loam, rarely fld. (Dexter)	0.32	5	0.0%	2.0%	0.060	0.247	0.481	NHEL
Bt	Bowdre clay, occas. fld.	0.37	3	0.0%	2.0%	0.060	0.247	0.249	NHEL
Bw	Bowdre clay, coarse subsoil, occas. fld.	0.37	3	0.0%	2.0%	0.060	0.247	0.249	NHEL
Ca	Calloway silt loam	0.49	3	0.0%	2.0%	0.060	0.247	0.188	NHEL
Cl	Collins silt loam, occas. fld.	0.43	5	0.0%	2.0%	0.060	0.247	0.358	NHEL
Cm	Commerce loam, occas. fld.	0.37	5	0.0%	2.0%	0.060	0.247	0.416	NHEL
Co	Commerce silty clay loam, occas. fld.	0.37	5	0.0%	2.0%	0.060	0.247	0.416	NHEL
Cr	Crevasse loamy sand, occas. fld.	0.17	5	0.0%	2.0%	0.060	0.247	0.905	NHEL
Cs	Crevasse sandy loam, occas. fld.	0.24	5	0.0%	2.0%	0.060	0.247	0.641	NHEL
Dk	Dekoven silt loam, occas. fld.	0.32	5	0.0%	2.0%	0.060	0.247	0.481	NHEL
Do	Dekoven silt loam, overwash, occas. fld.	0.32	5	0.0%	2.0%	0.060	0.247	0.481	NHEL
Ds	Dubbs silt loam, rarely fld.	0.37	5	0.0%	2.0%	0.060	0.247	0.416	NHEL
Dt	Dundee clay loam, occas. fld.	0.43	5	0.0%	2.0%	0.060	0.247	0.358	NHEL
Du	Dundee loam, occas. fld.	0.37	5	0.0%	2.0%	0.060	0.247	0.416	NHEL
Dv	Dundee silt loam, occas. fld.	0.43	5	0.0%	2.0%	0.060	0.247	0.358	NHEL
Fa	Falaya silt loam, occas. fld.	0.49	5	0.0%	2.0%	0.060	0.247	0.314	NHEL
Fd	Forestdale silt loam, occas. fld.	0.43	5	0.0%	2.0%	0.060	0.247	0.358	NHEL
Fo	Forestdale-Crevasse complex, occas. fld.								NHEL
	Forestdale part	0.43	5	0.0%	2.0%	0.060	0.247	0.358	
	Crevasse part	0.17	5	0.0%	2.0%	0.060	0.247	0.905	
Ga	Gravel pits								HEL
GrB	Grenada silt loam	0.49	3	2.0%	5.0%	0.163	0.757	0.188	HEL
GrB3	Grenada silt loam, sev. er.	0.49	3	2.0%	5.0%	0.163	0.757	0.188	HEL
GrC3	Grenada silt loam, sev. er.	0.49	3	5.0%	8.0%	0.379	1.406	0.188	HEL
GrD3	Grenada silt loam, sev. er.	0.49	3	8.0%	12.0%	0.703	2.570	0.188	HEL
Gu	Gullied land			12.0%	30.0%	1.285	11.826		HEL
Lb	Levees and borrow pits								HEL
LoB	Loring silt loam	0.49	3	2.0%	5.0%	0.163	0.757	0.188	HEL
LoB2	Loring silt loam, er.	0.49	3	2.0%	5.0%	0.163	0.757	0.188	HEL
LoB3	Loring silt loam, sev. er.	0.43	3	2.0%	5.0%	0.163	0.757	0.215	HEL
LoC3	Loring silt loam, sev. er.	0.43	3	5.0%	8.0%	0.379	1.406	0.215	HEL
LoD3	Loring silt loam, sev. er.	0.43	3	8.0%	12.0%	0.703	2.570	0.215	HEL
LoE3	Loring silt loam, sev. er.	0.43	3	12.0%	20.0%	1.285	5.897	0.215	HEL
LrE	Loring-Gullied land complex	0.43	3	12.0%	20.0%	1.285	5.897	0.215	HEL
Ma	Made land	[variable; not rated]							
MfB	Memphis silt loam,	0.49	5	2.0%	5.0%	0.163	0.757	0.314	PHEL
MfB3	Memphis silt loam, sev. er.	0.49	5	2.0%	5.0%	0.163	0.757	0.314	PHEL
MfC	Memphis silt loam	0.49	5	5.0%	8.0%	0.379	1.406	0.314	HEL
MfC3	Memphis silt loam, sev. er.	0.49	5	5.0%	8.0%	0.379	1.406	0.314	HEL
MfD3	Memphis silt loam, sev. er.	0.49	5	8.0%	12.0%	0.703	2.570	0.314	HEL
MfE3	Memphis silt loam, sev. er.	0.49	5	12.0%	20.0%	1.285	5.897	0.314	HEL

MfF	Memphis silt loam,	0.49	5	20.0%	30.0%	2.948	11.826	0.314	HEL
MfF3	Memphis silt loam, sev. er.	0.49	5	20.0%	30.0%	2.948	11.826	0.314	HEL
MfG	Memphis silt loam,	0.49	5	30.0%	50.0%	5.913	20.690	0.314	HEL
MgF	Memphis-Gullied land complex	0.49	5	20.0%	30.0%	2.948	11.826	0.314	HEL
Mo	Morganfield silt loam, occas. fld.	0.43	5	0.0%	2.0%	0.058	0.247	0.358	NHEL
Ro	Robinsonville fine sandy loam	0.28	5	0.0%	2.0%	0.058	0.247	0.549	NHEL
Rs	Robinsonville loam	0.32	5	0.0%	2.0%	0.058	0.247	0.481	NHEL
Rt	Routon silt loam	0.49	5	0.0%	2.0%	0.058	0.247	0.314	NHEL
Sa	Sharkey clay, occas. fld.	0.32	5	0.0%	2.0%	0.058	0.247	0.481	NHEL
Sh	Sharkey silty clay loam, occas. fld.	0.37	5	0.0%	2.0%	0.058	0.247	0.416	NHEL
Sw	Swamp (Rosebloom, ponded)	0.43	5	0.0%	1.0%	0.058	0.159	0.358	NHEL
Tc	Tunica clay	0.32	5	0.0%	2.0%	0.058	0.247	0.481	NHEL
Wa	Wakeland silt loam	0.37	5	0.0%	2.0%	0.058	0.247	0.416	NHEL
Ws	Waverly silt loam, occas. fld.	0.43	5	0.0%	2.0%	0.058	0.247	0.358	NHEL
Wv	Waverly silt loam, low (freq. fld.)	0.43	5	0.0%	2.0%	0.058	0.247	0.358	NHEL