BILL OF MATERIALS

MATERIAL	QUANTITY	UNIT
BASIC 50 FT. BUILDING		
CONCRETE – WALL	14.94	CU. YDS.
APRON – CONCRETE/GAVEL	15.46	CU. YDS.
METAL ROOFING	2948	SQ. FT.
METAL SIDING	1521.5	SQ. FT.
INTERIOR 3/4" PLYWOOD	596	SQ. FT.
PURLINS – 11'–2"	30	EACH
PURLINS – 10'–9"	30	EACH
PURLINS – 10'–0"	90	EACH
2" X 4" – HORIZONTAL	20	EACH
2" X 4" – VERTICAL	40	EACH
2" X 6" – HORIZONTAL	30	EACH
2" X 6" – VERTICAL	60	EACH
2" X 8" – HORIZONTAL	10	EACH
2" X 4" – RAKE TRIM	12	EACH
2" X 6" – CLOSED END TRIM	4	EACH
6" METAL TRUSS	12	EACH
TRUSS ANCHOR	12	EACH
TRUSS ANCHOR BOLTS	24	EACH
TRUSS ANCHOR NUTS	24	EACH
TRUSS ANCHOR WASHERS	24	EACH
OPTION ITEMS		
12' X 12' DOOR		
2" X 4" – FRAMING	6	EACH
2" X 6" – FRAMING	12	EACH
2" X 4" – DOOR FRAMING	13	EACH
3/4" – PLYWOOD INSIDE	144	SQ. FT.
METAL SIDING – OUTSIDE	144	SQ. FT.
6' – RUBBER FLAP	2	EACH
GALV. STEEL 3" BUTT HINGES	10	EACH
DOOR YOKES		
2" X 4" – YOKES	1	EACH
2" X 6" – YOKE LATCH	2	EACH
TRUSS ALTERNATIVE ATTACHMENT		
3/16" – STEEL TABS	100	EACH
CONCRETE – COUNTERFORT	4.74	CU. YDS.
CONCRETE – DRILLED PIER	1.54	CU. YDS.
CONCRETE – SLAB	38.64	CU. YDS.
QUANTITIES FOR 10 FT. EXTENSIONS		
CONCRETE – WALL	1.98	CU. YDS.
METAL ROOFING	567	SQ. FT.
METAL SIDING	160	SQ. FT.
INTERIOR 3/4" PLYWOOD	80	SQ. FT.
PULINS – 10'–0"	24	EACH
2" X 4" – HORIZONTAL	4	EACH
2" X 4" – VERTICAL	8	EACH
2" X 6" – HORIZONTAL	4	EACH
2" X 6" – VERTICAL	6	EACH
2" X 8" – HORIZONTAL	2	EACH
6" – TRUSS	2	EACH
TRUSS ANCHOR	2	EACH
TRUSS ANCHOR BOLTS	4	EACH
TRUSS ANCHOR NUTS	4	EACH
TRUSS ANCHOR WASHERS	4	EACH
TRUSS ALTERNATIVE ATTACHMENT		
3/16" – STEEL TABS	20	EACH
CONCRETE – COUNTERFORT	0.79	CU. YDS.
CONCRETE – DRILLED PIER	0.26	CU. YDS.
CONCRETE – SLAB	7.54	CU. YDS.