

**Practice:** 620 - Underground Outlet

**Scenario:** #1 - Pipe, no inlet, 6 inch or less

**Scenario Description:** Install 280 feet of 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 44" deep and 24" wide. Costs include 6" HDPE pipe, trench excavation, trench backfill, 20' of 6" PVC outlet pipe with rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with roof runoff management or similar practices.

**Before Situation:** Roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** "Clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Diversion (342), Roof Runoff Mangement (558) and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit, including outlet pipe

**Scenario Unit:** Foot

**Scenario Typical Size:** 300

**Total Scenario Cost:** \$1,486.20

**Scenario Cost/Unit:** \$4.95

#### Cost Details

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

#### Materials

Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	\$1.13	280	\$316.80
Pipe, PVC, 6", SCH 40	980	Materials: - 6" - PVC - SCH 40 - ASTM D1785	Foot	\$6.63	20	\$132.59
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

#### Labor

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	2	\$81.36
-----------------------	-----	--	------	---------	---	---------

#### Mobilization

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

#### Equipment Installation

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.70	82	\$139.54
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	82	\$207.22

**Practice:** 620 - Underground Outlet**Scenario:** #2 - Pipe, no inlet, greater than 6 inches and 12 inches or less

**Scenario Description:** Install 280 feet of 12" approved plastic pipe to convey storm-water from one location to a suitable and stable outlet. Trench Excavation is 44" deep and 24" wide. Costs include 12" HDPE pipe, trench excavation, trench backfill, 20' of 12" PVC outlet pipe with rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with roof runoff management or similar practices.

**Before Situation:** Roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** "Clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Diversion (342), Roof Runoff Management (558) and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit, including outlet pipe**Scenario Unit:** Foot**Scenario Typical Size:** 300**Total Scenario Cost:** \$2,744.17**Scenario Cost/Unit:** \$9.15**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Pipe, HDPE, 12", PCPT, Single Wall	1274	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 12" diameter - ASTM F667. Material cost only.	Foot	\$4.82	280	\$1,350.72
Pipe, PVC, 12", SDR 35	1252	Pipe, PVC, SDR 35, 12" Diameter - ASTM D3034. Material cost only.	Foot	\$17.83	20	\$356.64
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	2	\$81.36
-----------------------	-----	--	------	---------	---	---------

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.70	82	\$139.54
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	82	\$207.22

**Practice:** 620 - Underground Outlet**Scenario:** #3 - Pipe, no inlet, greater than 12 inch

**Scenario Description:** Install 300 feet of 18" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 44" deep and 24" wide. Costs include 18" HDPE pipe, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet (outlet pipe not separate since component is double wall pipe). This practice is often installed in conjunction with roof runoff management or similar practices.

**Before Situation:** Roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** "Clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Diversion (342), Roof Runoff Mangement (558) and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit, including outlet pipe**Scenario Unit:** Foot**Scenario Typical Size:** 300**Total Scenario Cost:** \$4,391.73**Scenario Cost/Unit:** \$14.64**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Pipe, HDPE, CPT, Double Wall, Soil Tight, 18"	1245	Pipe, Corrugated HDPE Double Wall, 18" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$11.18	300	\$3,354.92
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	2	\$81.36
-----------------------	-----	--	------	---------	---	---------

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.70	82	\$139.54
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	82	\$207.22

**Practice:** 620 - Underground Outlet**Scenario:** #4 - Pipe, riser, 6 inch or less

**Scenario Description:** Install 480 feet of 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated approximately 54" deep and 15" wide by hydraulic excavator. Costs include 6" HDPE corrugated single wall plastic tubing, 8" Perforated PVC Riser Inlet, trench excavation, trench backfill, 20' of 6" PVC outlet pipe with rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

**Before Situation:** Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit, including outlet pipe

**Scenario Unit:** Foot

**Scenario Typical Size:** 500

**Total Scenario Cost:** \$2,642.70

**Scenario Cost/Unit:** \$5.29

**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Inlet, riser, 8"	1262	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 8" diameter. Materials only.	Each	\$109.37	1	\$109.37
Pipe, HDPE, 6", CPT, Single Wall	1242	Pipe, Corrugated Plastic Tubing, Single Wall, 6" diameter - ASTM F405. Material cost only.	Foot	\$1.13	480	\$543.09
Pipe, PVC, 6", SCH 40	980	Materials: - 6" - PVC - SCH 40 - ASTM D1785	Foot	\$6.63	20	\$132.59
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.87	10	\$268.75
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	2	\$81.36

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	105	\$265.35
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$63.35	10	\$633.52

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Practice:** 620 - Underground Outlet**Scenario:** #5 - Pipe, riser, 12 inch or less

**Scenario Description:** Install 480 feet of 10" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 58" deep and 28" wide. Costs include 10" HDPE pipe, 12" Perforated PVC Riser Inlet, trench excavation, trench backfill, 20' of 10" PVC outlet pipe with rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

**Before Situation:** Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit, including outlet pipe**Scenario Unit:** Foot**Scenario Typical Size:** 500**Total Scenario Cost:** \$4,847.13**Scenario Cost/Unit:** \$9.69**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Inlet, riser, 12"	1264	Riser, polymer, complete vertical perforated UGO inlet with Tee, orifice plate if needed, 12" diameter. Materials only.	Each	\$540.37	1	\$540.37
Pipe, HDPE, 10", PCPT, Single Wall	1273	Pipe, Corrugated Plastic Tubing, Single Wall, Perforated, 10" diameter - ASTM F667. Material cost only.	Foot	\$3.86	480	\$1,853.07
Pipe, PVC, 10", SDR 35	1251	Pipe, PVC, SDR 35, 10" Diameter - ASTM D3034. Material cost only.	Foot	\$12.47	20	\$249.33
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.87	10	\$268.75
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	4	\$162.71

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	210	\$530.70
Hydraulic Excavator, .5 CY	930	Track mounted hydraulic excavator with bucket capacity range of 0.3 to 0.8 CY. Equipment and power unit costs. Labor not included.	Hour	\$63.35	10	\$633.52

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Practice:** 620 - Underground Outlet**Scenario:** #6 - Pipe, riser, greater than 12 inch

**Scenario Description:** Install 500 feet of 18" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 64" deep and 32" wide. Costs include 18" HDPE pipe, an additional 6' of 18" HDPE to serve as a Riser Inlet, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

**Before Situation:** Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit, including outlet pipe**Scenario Unit:** Foot**Scenario Typical Size:** 500**Total Scenario Cost:** \$8,511.92**Scenario Cost/Unit:** \$17.02**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Pipe, HDPE, CPT, Double Wall, Soil Tight, 18"	1245	Pipe, Corrugated HDPE Double Wall, 18" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$11.18	506	\$5,658.63
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Equipment Operators, Heavy	233	Includes: Cranes, Hydraulic Excavators >=50 HP, Dozers, Paving Machines, Rock Trenchers, Trenchers >=12", Dump Trucks, Ag Equipment >=150 HP, Scrapers, Water Wagons.	Hour	\$26.87	10	\$268.75
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	4	\$162.71

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	263	\$664.63
Hydraulic Excavator, 1 CY	931	Track mounted hydraulic excavator with bucket capacity range of 0.8 to 1.5 CY. Equipment and power unit costs. Labor not included.	Hour	\$114.85	10	\$1,148.52

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Practice:** 620 - Underground Outlet**Scenario:** #7 - Pipe, drop inlet, 6 inch or less

**Scenario Description:** Install 500 feet of 6" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench is excavated 54" deep and 24" wide by hydraulic track excavator. Costs include 6" Sch 40 PVC pipe, Precast concrete drop inlet with steel grate, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

**Before Situation:** Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit**Scenario Unit:** Foot**Scenario Typical Size:** 500**Total Scenario Cost:** \$5,333.87**Scenario Cost/Unit:** \$10.67**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Catch Basin, concrete, 2'x2'x6'	1257	Catch Basin, Precast Concrete, 2' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$610.10	1	\$610.10
Pipe, PVC, 6", SCH 40	980	Materials: - 6" - PVC - SCH 40 - ASTM D1785	Foot	\$6.63	500	\$3,314.83
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	2	\$81.36
-----------------------	-----	--	------	---------	---	---------

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.70	170	\$289.29
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	170	\$429.61

**Practice:** 620 - Underground Outlet**Scenario:** #8 - Pipe, drop inlet, 12 inch or less

**Scenario Description:** Install 500 feet of 12" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench Excavation is 58" deep and 28" wide. Costs include 12" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

**Before Situation:** Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit**Scenario Unit:** Foot**Scenario Typical Size:** 500**Total Scenario Cost:** \$5,895.89**Scenario Cost/Unit:** \$11.79**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Catch Basin, concrete, 2'x2'x6'	1257	Catch Basin, Precast Concrete, 2' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$610.10	1	\$610.10
Pipe, HDPE, CPT, Double Wall, Soil Tight, 12"	1244	Pipe, Corrugated HDPE Double Wall, 12" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$7.25	500	\$3,626.34
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	4	\$162.71
-----------------------	-----	--	------	---------	---	----------

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.70	210	\$357.36
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	210	\$530.70



**Practice:** 620 - Underground Outlet**Scenario:** #9 - Pipe, drop inlet, 18 inch or less

**Scenario Description:** Install 500 feet of 18" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench excavation is 66" deep x 39" wide. Costs include 18" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, bedding material, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

**Before Situation:** Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit**Scenario Unit:** Foot**Scenario Typical Size:** 500**Total Scenario Cost:** \$10,794.53**Scenario Cost/Unit:** \$21.59**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$40.43	60	\$2,425.98
Catch Basin, concrete, 2'x2'x6'	1257	Catch Basin, Precast Concrete, 2' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$610.10	1	\$610.10
Pipe, HDPE, CPT, Double Wall, Soil Tight, 18"	1245	Pipe, Corrugated HDPE Double Wall, 18" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$11.18	500	\$5,591.53
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	4	\$162.71
-----------------------	-----	--	------	---------	---	----------

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.70	330	\$561.57
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	330	\$833.95

**Practice:** 620 - Underground Outlet**Scenario:** #10 - Pipe, drop inlet, 24 inch or less

**Scenario Description:** Install 500 feet of 24" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench excavation is 72" x 48" wide. Costs include 24" HDPE pipe, Precast concrete drop inlet with steel grate, 24" HDPE pipe, trench excavation, bedding material, trench backfill, rodent guard and laid up stone headwall at outlet. Practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

**Before Situation:** Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit**Scenario Unit:** Foot**Scenario Typical Size:** 500**Total Scenario Cost:** \$16,103.41**Scenario Cost/Unit:** \$32.21**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$40.43	85	\$3,436.81
Catch Basin, concrete, 2'x2'x6'	1257	Catch Basin, Precast Concrete, 2' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$610.10	1	\$610.10
Pipe, HDPE, CPT, Double Wall, Soil Tight, 24"	1246	Pipe, Corrugated HDPE Double Wall, 24" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$18.81	500	\$9,403.27
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	4	\$162.71
-----------------------	-----	--	------	---------	---	----------

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.70	445	\$757.27
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	445	\$1,124.57

**Practice:** 620 - Underground Outlet**Scenario:** #11 - Pipe, drop inlet, 30 inch or less

**Scenario Description:** Install 500 feet of 30" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench excavation is 78" deep x 56" wide. Costs include 30" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, bedding material, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

**Before Situation:** Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway (412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit**Scenario Unit:** Foot**Scenario Typical Size:** 500**Total Scenario Cost:** \$21,939.94**Scenario Cost/Unit:** \$43.88**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$40.43	105	\$4,245.47
Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$802.14	1	\$802.14
Pipe, HDPE, CPT, Double Wall, Soil Tight, 30"	1247	Pipe, Corrugated HDPE Double Wall, 30" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$27.46	500	\$13,731.64
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	4	\$162.71
-----------------------	-----	--	------	---------	---	----------

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.70	565	\$961.48
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	565	\$1,427.82

**Practice:** 620 - Underground Outlet**Scenario:** #12 - Pipe, drop inlet, greater than 30 inch

**Scenario Description:** Install 500 feet of 36" approved plastic pipe to convey stormwater from one location to a suitable and stable outlet. Trench excavation is 84" deep x 64" wide. Costs include 36" HDPE pipe, Precast concrete drop inlet with steel grate, trench excavation, bedding material, trench backfill, rodent guard and laid up stone headwall at outlet. This practice is often installed in conjunction with terraces, diversions, sediment control basins, waterways or similar practices.

**Before Situation:** Excessive sedimentation and soil erosion as a result of gully, rill or sheet erosion which exceeds "T" from farm fields and other locations. Also, roof runoff or surface runoff that becomes contaminated with agricultural wastes that significantly contributes to the amount of runoff that has to be stored or treated.

**After Situation:** Field system meets "T" or "clean" storm water runoff is diverted away from an agricultural waste management system to minimize the volume of runoff that is contaminated by agricultural waste. Associated practices are Critical Area Planting (342), Grassed Waterway ( 412), Terrace (600), Diversion (342), Water and Sediment Control Basin (638), and Subsurface Drainage (606)

**Scenario Feature Measure:** Length of Conduit**Scenario Unit:** Foot**Scenario Typical Size:** 500**Total Scenario Cost:** \$27,794.85**Scenario Cost/Unit:** \$55.59**Cost Details**

Component Name	Id	Description	Unit	Cost	Qty	Total
----------------	----	-------------	------	------	-----	-------

**Materials**

Aggregate, Gravel, Graded	46	Gravel, includes materials, equipment and labor to transport and place. Includes washed and unwashed gravel.	Cubic Yard	\$40.43	135	\$5,458.46
Catch Basin, concrete, 3'x3'x6'	1258	Catch Basin, Precast Concrete, 3' square or round, cast grate, 6' deep. Includes materials, equipment and labor.	Each	\$802.14	1	\$802.14
Pipe, HDPE, CPT, Double Wall, Soil Tight, 36"	1248	Pipe, Corrugated HDPE Double Wall, 36" diameter with soil tight joints - AASHTO M294. Material cost only.	Foot	\$35.69	500	\$17,844.95
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic Yard	\$87.69	1	\$87.69

**Labor**

Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$40.68	4	\$162.71
-----------------------	-----	--	------	---------	---	----------

**Mobilization**

Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	2	\$516.63
--------------------------------	------	---	------	----------	---	----------

**Equipment Installation**

Compaction, earthfill, vibratory plate	1260	Compaction of earthfill with a walk behind vibratory plate compactor in typical 6-8 inch thick lifts, 2 passes. Includes equipment and labor.	Cubic Yard	\$2.18	2	\$4.36
Excavation, common earth, side cast, large equipment	1227	Bulk excavation and side casting of common earth with hydraulic excavator with less greater than 1 CY capacity. Includes equipment and labor.	Cubic Yard	\$1.70	690	\$1,174.19
Excavation, common earth, small equipment, 50 ft	1220	Bulk excavation of common earth with dozer <100 HP with average push distance of 50 feet. Includes equipment and labor.	Cubic Yard	\$2.53	690	\$1,743.71