

Practice: 468 - Lined Waterway or Outlet

Scenario: #1 - Rock Lined, 12 inch

Scenario Description:

Install 300' long by 15' wide by 1.5' deep trapezoidal or parabolic shaped waterway lined with riprap (D100 = 9", Velocity ~ 8 ft/sec). 1/2 the channel is excavated, before excavation for riprap. Excess excavation is spoiled in the immediate area. Riprap is installed over 100% of the width of the waterway to prevent scour. Cost include excavation, spoiling of excess material, geotextile underlayment and installing 9" Rock Riprap. Lined waterway width is measured from top of bank to top of bank.

Before Situation:

Excessive sedimentation and soil erosion as a result of ephemeral or classic gully erosion. Velocities are generally too high or saturated soil conditions make it difficult to establish a grassed waterway.

After Situation:

Rock lined waterway is 300' long by 15' wide by 1.5' deep. Waterway is excavated and rock is placed using a hydraulic excavator. Geotextile underlayment is installed by laborers. Associated practices are Subsurface Drain (606), Underground Outlet (620), Structure for Water Control (587), and Critical Area Seeding (342).

Scenario Feature Measure: Square Foot of Waterway

Scenario Unit: Square Feet

Scenario Typical Size: 4,500

Scenario Cost: \$16,214.06

Scenario Cost/Unit: \$3.60

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$1.91	276	\$527.16
Labor						
Supervisor or Manager	234	Labor involving supervision or management activities. Includes crew supervisors, foremen and farm/ranch managers time required for adopting new technology, etc.	Hour	\$38.32	2	\$76.64
General Labor	231	Labor performed using basic tools such as power tool, shovels, and other tools that do not require extensive training. Ex. pipe layer, herder, concrete placement, materials spreader, flagger, etc.	Hour	\$19.09	2	\$38.18
Materials						
Rock Riprap, Placed with geotextile	44	Rock Riprap, placed with geotextile, includes materials, equipment and labor to transport and place	Cubic yard	\$87.01	176	\$15,313.76
Mobilization						
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$258.32	1	\$258.32