

Practice: 521D - Pond Sealing or Lining, Compacted Clay Treatment

Scenario: #1 - Material haul < 1 mile

Scenario Description:

Construction of a compacted soil liner, treated with compacted clay, to reduce seepage from ponds or waste storage impoundment structures. Practice implementation includes compaction of the soil liner under proper moisture conditions to the designed liner thickness, and soil cover to protect the finished liner. Material haul < 1 mile. Associated practices include PS378, PS313, & other waste water impoundments.

Before Situation:

In-place soils at site exhibit seepage rates in excess of acceptable limits. An adequate quantity of soil suitable for constructing a clay liner without amendments is available at an economical haul distance. Material haul < 1 mile.

After Situation:

Water conservation and environmental protection provided by limiting seepage losses from ponds or waste storage impoundments.

Scenario Feature Measure: Volume of Liner Material (including volume of soil cover, as needed)

Scenario Unit: Cubic Yard

Scenario Typical Size: 2,420

Scenario Cost: \$25,215.29

Scenario Cost/Unit: \$10.42

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, clay, large equipment, 1500 ft	1217	Bulk excavation of clay with scrapers with average haul distance of 1500 feet. Includes equipment and labor.	Cubic Yard	\$6.68	1613	\$10,774.84
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.74	807	\$3,018.18
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$3.64	2420	\$8,808.80
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$103.18	8	\$825.44
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$507.42	3	\$1,522.26
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$265.77	1	\$265.77

Practice: 521D - Pond Sealing or Lining, Compacted Clay Treatment

Scenario: #2 - Material haul ≥ 1 mile

Scenario Description:

Construction of a compacted soil liner, treated with compacted clay, to reduce seepage from ponds or waste storage impoundment structures. Practice implementation includes compaction of the soil liner under proper moisture conditions to the designed liner thickness, and protection of the finished liner. Material haul approximately 5 miles ≥ 1 mile. Associated practices include PS378, PS313, & other waste water impoundments.

Before Situation:

In-place soils at site exhibit seepage rates in excess of acceptable limits. An adequate quantity of soil suitable for constructing a clay liner without amendments is available at an economical haul distance.

After Situation:

Water conservation and environmental protection provided by limiting seepage losses from ponds or waste storage impoundments.

Scenario Feature Measure: Volume of Liner Material (including volume of soil cover, as needed)

Scenario Unit: Cubic Yard

Scenario Typical Size: 2,420

Scenario Cost: \$27,957.39

Scenario Cost/Unit: \$11.55

Cost Details (by category):

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
Equipment/Installation						
Excavation, clay, large equipment, 1500 ft	1217	Bulk excavation of clay with scrapers with average haul distance of 1500 feet. Includes equipment and labor.	Cubic Yard	\$6.68	1613	\$10,774.84
Excavation, common earth, large equipment, 150 ft	1223	Bulk excavation of common earth including sand and gravel with dozer >100 HP with average push distance of 150 feet. Includes equipment and labor.	Cubic Yard	\$3.74	807	\$3,018.18
Hauling, bulk, highway truck	1615	Hauling of bulk earthfill, rockfill, waste or debris. One-way travel distance using fully loaded highway dump trucks (typically 16 CY or 20 TN capacity). Includes equipment and labor for truck only. Does not include cost for loading truck.	Cubic Yard Mile	\$0.34	8065	\$2,742.10
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$3.64	2420	\$8,808.80
Labor						
Specialist Labor	235	Labor requiring a specialized skill set: Includes Agronomists, Foresters, Biologists, etc. to provide additional technical information during the planning and implementation of the practice. Does not include NRCS or TSP services.	Hour	\$103.18	8	\$825.44
Mobilization						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$507.42	3	\$1,522.26
Mobilization, medium equipment	1139	Equipment with 70-150 HP or typical weights between 14,000 and 30,000 pounds.	Each	\$265.77	1	\$265.77