

**Practice: 659 - Wetland Enhancement****Scenario: #4 - Depression Sediment Removal and Ditch Plug****Scenario Description:**

A Depressional HGM class wetland is to be enhanced. The tract size is 15 acres, and the actual wetland size is 10 acres. The site is a recharge depression, fed only from surface runoff. Resource Concerns are: 4-SOIL QUALITY DEGRADATION - Organic matter depletion, 11-WATER QUALITY DEGRADATION - Excess nutrients in surface and ground waters, 12 - WATER QUALITY DEGRADATION - Pesticides transported to surface and ground waters, 16 - WATER QUALITY DEGRADATION - Excessive sediment in surface waters, 18 - DEGRADED PLANT CONDITION - Undesirable plant productivity and health, 19 - DEGRADED PLANT CONDITION, Inadequate structure and composition, 22- INADEQUATE HABITAT FOR FISH AND WILDLIFE - Habitat degradation.

**Before Situation:**

The wetland has been converted to agricultural production, and the tract drained with a surface ditch. The ditch is 4' average depth, and 12 feet average width. The wetland receives surface runoff from an adjacent upland watershed, and ponds water on a shallow perched layer. The watershed has been converted from native to agricultural landuse, and the resultant soil erosion has deposited 6" of sediment in the bottom of the depression.

**After Situation:**

The ditch has been plugged by the installation of a 50' long section of compacted clay fill, and the deposition has been removed down to the original topsoil layer. A herbaceous plant community has been seeded. Facilitative practices include Conservation Cover. Restoration of hydrology and plant community functions will improve the WATER QUALITY and DEGRADED PLANT CONDITION concerns listed above. The hydrologic and vegetative practices will address the SOIL QUALITY DEGRADATION and INADEQUATE HABITAT FOR FISH AND WILDLIFE concerns.

**Scenario Feature Measure:** Cubic yds of earth excavation

**Scenario Unit:** Cubic Yard

**Scenario Typical Size:** 8,067

**Scenario Cost:** \$17,150.12

**Scenario Cost/Unit:** \$2.13

**Cost Details (by category):**

Component Name	ID	Component Description	Unit	Price (\$/unit)	Quantity	Cost
<b>Equipment/Installation</b>						
Earthfill, Roller Compacted	49	Earthfill, roller or machine compacted, includes equipment and labor	Cubic yard	\$3.64	89	\$323.96
Excavation, Common Earth, side cast, small equipment	48	Bulk excavation and side casting of common earth with hydraulic excavator with less than 1 CY capacity. Includes equipment and labor.	Cubic yard	\$1.96	8067	\$15,811.32
<b>Mobilization</b>						
Mobilization, large equipment	1140	Equipment >150HP or typical weights greater than 30,000 pounds or loads requiring over width or over length permits.	Each	\$507.42	2	\$1,014.84